

COUNTY OF FRESNO
DEPARTMENT OF PUBLIC WORKS AND PLANNING
PROJECT: SB1 OVERLAY 2022-23 VARIOUS LOCATIONS
CONTRACT NO: 23-07-M
BASE BID

REVISED FOR ADDENDUM #2

Road Name	Start	End	Length		Width	Overlay Thickness	Hot Mix Asphalt Overlay		Tack Coat	Binder (Fabric)	Geosynthetic Pavement Interlayer
			MILES	FEET	FEET	FEET	AREA (SQFT)	TON	TON	TON	SQYD
COLORADO	0.125 S/O MANNING	SR 145	6.51	34373	40.5	0.3	1,392,107	32,889	25.78	103	91,661
MANNING	JAMESON	SR 145	4.04	21332	32	0.25	682,624	13,440	25.3		
BRAWLEY	0.10 N/O SR180	MCKINLEY	1.91	10085	31.15	0.3	314,148	7,422	5.82	30	26,893
BRAWLEY	SR180	JENSEN	1.742	9198	22.3	0.3	205,115	4,846	3.8	26	22,791
MANNING	ELM	BLYTHE	4.5	23760	31.5	0.3	748,440	17,682	13.86		
ASHLAN	MINNEWAWA	CLOVIS	0.504	2662	41.05	0.25	109,275	2,152	2.03		
ASHLAN	CLOVIS	0.030 E/O SUNNYSIDE	0.527	2783	60.6	0.25	168,650	3,321	3.13		
MT. WHITNEY	GARFIELD	WESTLAWN	1.5	7920	30.2	0.25	239,184	4,709	4.43		
WILLOW	NEVADA	OLIVE	0.79	4172	34	0.3	141,848	3,352	2.63		
ALTA	DINUBA	FLORAL	0.997	5265	41.4	0.25	217,971	4,292	4.04		
McCALL	MANNING	DINUBA	0.948	5006	33	0.15	165,198	1,952	3.06		
PAVING MAT							Cross Roads	2458.18			

Total Miles	23.968
-------------	--------

Rounded up Totals	4,384,560	98,516	94	160	141,346
-------------------	-----------	--------	----	-----	---------

ADDITIVE ALTERNATES

BRAWLEY	MADISON AVE	0.25 N/O MADISON AVE	0.25	1320	24	0.3	31,680	749	0.59	4	3,520
WOODLAND RD	SR180	SSR180	2.8	14784	24	0.20	354,816	5,589	6.58		
W. MARIPOSA LILLY	WILDROSE LN	END OF CUL-DE-SAC	0.17	898	26	0.20	23,348	368	0.44	3	2,395
WOODY LANE	TOLLHOUSE ROAD	END OF WOODY LANE	0.17	898	25	0.20	22,450	354	0.42		

Total Miles	3.390
-------------	-------

Rounded up Totals	432,294	7,060	9	7	5,915
-------------------	---------	-------	---	---	-------

Highlighted cells reflect changes from prior release

COUNTY OF FRESNO
DEPARTMENT OF PUBLIC WORKS AND PLANNING
PROJECT: SB1 OVERLAY 2022-23 VARIOUS LOCATIONS
CONTRACT NO: 23-07-M
BASE BID

REVISED FOR ADDENDUM #2

Road Name	Start	End	Length		Width	Overlay Thickness	Cold Planing	Repl. Asphalt Pgmt.	Dikes	Misc Areas	Minor HMA	Imp. Borrow	Shoulder Backing
			MILES	FEET	FEET	FEET	SQYD	CUYD	LF	SQYD	TON	CYD	CYD
COLORADO	0.125 S/O MANNING	SR 145	6.51	34373	40.5	0.3	3,382	742	2,395	255	0.45		7,257
MANNING	JAMESON	SR 145	4.04	21332	32	0.25	2,000	270		48	0.08		3,259
BRAWLEY	0.10 N/O SR180	MCKINLEY	1.91	10085	31.15	0.3	1,221	135	150	1,350	2.36		2,129
BRAWLEY	SR180	JENSEN	1.742	9198	22.3	0.3	2,583	135		969	1.70		1,942
MANNING	ELM	BLYTHE	4.5	23760	31.5	0.3	5,479	270	1,660	924	1.62		5,016
ASHLAN	MINNEWAWA	CLOVIS	0.504	2662	41.05	0.25	1,854	675	*400	-	0.00		407
ASHLAN	CLOVIS	0.030 E/O SUNNYSIDE	0.527	2783	60.6	0.25	178	135		-	0.00		425
MT. WHITNEY	GARFIELD	WESTLAWN	1.5	7920	30.2	0.25	1,897	135		360	0.63		1,210
WILLOW	NEVADA	OLIVE	0.79	4172	34	0.3	118	135	375	-	0.00		881
ALTA	DINUBA	FLORAL	0.997	5265	41.4	0.25	226			300	0.53		765
McCALL	MANNING	DINUBA	0.948	5006	33	0.15	450	68		500	0.88		804

PAVING MAT

From Dikes 132

*Dike Removal Only

Total Miles	23.968
-------------	--------

Rounded up Totals	19,390	2,700	4,580	4,706	141	-	24,095
-------------------	--------	-------	-------	-------	-----	---	--------

ADDITIVE ALTERNATES

BRAWLEY	MADISON AVE	0.25 N/O MADISON AVE	0.25	1320	24	0.3	323			261.00	1.00		202
WOODLAND RD	SR180	SSR180	2.8	14784	24	0.20	222	45	980		26	6	1,533
W. MARIPOSA LILLY	WILDROSE LN	END OF CUL-DE-SAC	0.17	898	26	0.20	20	122	180		5		93
WOODY LANE	TOLLHOUSE ROAD	END OF WOODY LANE	0.17	898	25	0.20	56		1,740		46		93

Total Miles	3.390
-------------	-------

Rounded up Totals	621	167	2,900	261	78	6	1,921
-------------------	-----	-----	-------	-----	----	---	-------

Highlighted cells reflect changes from prior release

COUNTY OF FRESNO
DEPARTMENT OF PUBLIC WORKS AND PLANNING
PROJECT: SB1 OVERLAY 2022-23 VARIOUS LOCATIONS
CONTRACT NO: 23-07-M
BASE BID

REVISED FOR ADDENDUM #2

Road Name	Start	End	Length		Width	Overlay Thickness	SURVEY MON.	UTILITY BOX	MANHOLE
			MILES	FEET	FEET	FEET	QTY	QTY	QTY
COLORADO	0.125 S/O MANNING	SR 145	6.51	34373	40.5	0.3	10		
MANNING	JAMESON	SR 145	4.04	21332	32	0.25	7	1	
BRAWLEY	0.10 N/O SR180	MCKINLEY	1.91	10085	31.15	0.3	6	11	1
BRAWLEY	SR180	JENSEN	1.742	9198	22.3	0.3	1	4	1
MANNING	ELM	BLYTHE	4.5	23760	31.5	0.3	10	2	
ASHLAN	MINNEWAWA	CLOVIS	0.504	2662	41.05	0.25	4	23	9
ASHLAN	CLOVIS	0.030 E/O SUNNYSIDE	0.527	2783	60.6	0.25	4	19	11
MT. WHITNEY	GARFIELD	WESTLAWN	1.5	7920	30.2	0.25	4	4	
WILLOW	NEVADA	OLIVE	0.79	4172	34	0.3	4		
ALTA	DINUBA	FLORAL	0.997	5265	41.4	0.25	4		
McCALL	MANNING	DINUBA	0.948	5006	33	0.15	4		
PAVING MAT								Adjusted by Municipalities	

Total Miles 23.968

Rounded up Totals 58 64 22

ADDITIVE ALTERNATES

BRAWLEY	MADISON AVE	0.25 N/O MADISON AVE	0.25	1320	24	0.3	4	4	
WOODLAND RD	SR180	SSR180	2.8	14784	24	0.20	4	7	
W. MARIPOSA LILLY	WILDROSE LN	END OF CUL-DE-SAC	0.17	898	26	0.20	2	4	
WOODY LANE	TOLLHOUSE ROAD	END OF WOODY LANE	0.17	898	25	0.20	4	2	
Total Miles			3.390		Rounded up Totals		14	17	-

Highlighted cells reflect changes from prior release