



County of Fresno

DEPARTMENT OF PUBLIC WORKS AND PLANNING
STEVEN E. WHITE, DIRECTOR

January 10, 2025

Contract No. 24-11-PR

ADDENDUM NO. 1 to CHOINUMNI PARK IMPROVEMENTS, revising the Bidding and Contract Documents as follows:

TABLE OF CONTENTS

No changes

NOTICE TO BIDDERS

No changes

SPECIAL PROVISIONS

Section 8-1.04C(2) Second Order of Work

DELETE:

Complete the second order of work before the expiration of
SEVENTY (70) WORKING DAYS

REPLACE with:

Complete the second order of work before the expiration of
NINETY (90) WORKING DAYS

STATE REQUIREMENTS

No changes

PROJECT DETAILS / DRAWINGS

No changes

TECHNICAL SPECIFICATIONS

Section 34 00 00 Bid Item Descriptions

DELETE: Section 34 00 00 Bid Item Descriptions

REPLACE with: attached Section 34 00 00 Bid Item Descriptions

PROPOSAL/BID BOOK: PAPER

DELETE: Bid Item List – Proposal 2

REPLACE with: attached Bid Item List – Proposal 2A

PROPOSAL/BID BOOK: BID EXPRESS

DELETE: Bid Item List – Proposal 2

REPLACE with: attached Bid Item List – Proposal 2A

AGREEMENT

No changes

PLANS

No changes

END OF ADDENDUM NO. 1

Please attach this Addendum to the inside cover of the Specifications booklet. If you have given the Bidding and Contract Documents to someone else, please forward this Addendum.



1/10/24

Date Signed

A handwritten signature in black ink, appearing to be "S. Artal", written over a horizontal line.

Supervising Engineer: _____

Sebastian Artal, PE C76724

FRESNO COUNTY
Department of Public Works and Planning
m/a 2220 Tulare Street, Suite 720
Fresno, CA 93721-2106

In responsible charge of the Special Provisions Sections 1 through 94

1-10-25

Date Signed



Consultant Engineer:

Orfil Muniz, PE C88165

A&M Consulting Engineers
220 N. Locust St.
Visalia, CA 93291

**SECTION 34 00 00
BID ITEM DESCRIPTIONS**

The unit prices paid for the items listed in the Contractor's Proposal as defined herein shall be considered full compensation for furnishing all labor, materials, tools, and equipment, and doing all work involved in furnishing and installing the materials complete and in place, in accordance with the details shown on the Plans, as specified herein, and directed by the Engineer.

All incidental work which is neither shown on the Plans nor otherwise specified, and which is necessary to complete the improvements as shown on the Plans and as specified in the Contract Documents (defined in the Contract/Agreement), shall be furnished and installed as though such work were shown on the Plans or specified in the Contract Documents, and no additional compensation shall be allowed therefore.

The scope of work includes but is not limited to, each bid item listed in the Contractor's Proposal and as described in the following.

GENERAL**1. MOBILIZATION & DEMOBILIZATION**

The work under this item shall conform to the provisions of Section 01 71 13 "Mobilization, Site Maintenance, Demobilization" of these Specifications, the Standard Specifications and as directed by the Engineer.

Payment for Mobilization, Demobilization, Insurance, Bonds, and Project Signs will be made at the lump sum price. The amount paid for this item shall not exceed 5% of the total construction cost and constitutes full compensation for providing all work complete as shown and specified in the Contract Documents.

2. JOB SITE MANAGEMENT

This bid item is a lump sum bid item for the cost of all work involved with job site management and includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in spill prevention and control, material management, waste management, non-stormwater management, and dewatering and identifying, sampling, testing, handling, and disposing of hazardous waste resulting from your activities, as specified in the Section 14 of the Standard Specifications and these Special Provisions, and as ordered by the Engineer.

3. IMPLEMENT APPROVED STORM WATER POLLUTION PREVENTION PLAN (SWPPP)

This bid item is a lump sum bid for review and implement a Storm Water Pollution Prevention Plan ("SWPPP") prepared by the Engineer, and includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals and for doing all the work involved in reviewing, implementing, maintaining, monitoring, inspecting, and removing water pollution control practices in accordance with the approved SWPPP as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

This bid item shall be paid at the lump sum price bid. Payment will be prorated based on the percentage of contract work completed.

4. STATE WATER RESOURCES CONTROL BOARD NOTICE OF INTENT FILING FEE

This bid item is specifically provided to reimburse the Contractor for payment of the NOI filing fee charged by the SWRCB and paid by the Contractor after the Contractor has completed the NOI filing process started by the County. The amount paid for this bid item will be the fee only. No payment will be made for overhead or processing costs. Full compensation for any overhead and processing costs will be considered to be included in the various items of work, and no separate compensation will be made therefor.

The dollar amount shown in the Proposal is an estimate only and shall be included in each bidder's proposal. Payment for this bid item will be adjusted based on the actual fee paid. The provisions of Section 9-1.06 for increased or decreased quantities shall not apply to the "State Water Resources Control Board – Notice of Intent" bid item.

5. DEMOLITION, CLEARING, & GRUBBING

The work under this item shall conform to the provisions of Sections 02 41 13 "Site Demolition" and 31 10 00 "Site Clearing" of these Specifications.

The work shall consist of the removal and disposal of all existing surfaces, soil spoil, roots, stumps, limbs, buried logs, tree/bush pruning, concrete, asphalt concrete, aggregate base, buried trash, saw cutting of asphalt and concrete, excavation of asphalt, and all other obstructing materials encountered during the excavation and installation of the proposed improvements, as shown on the Plans in conformance with the provisions in these Specifications and as directed by the Engineer.

Payment for this item will be made at the lump sum price, and no additional payment will be made therefore.

SITE PREPARATION & GRADING

6. CONSTRUCTION STAKING

The work under this item shall conform to the provisions of Section 01 73 00 "Execution" of these Specifications and as directed by the Engineer.

Payment for this item will be made at the lump sum price. This includes full compensation for all labor, materials, tools, and equipment necessary for providing construction stakes and marks required for the completion of the work shown on the Plans. No additional payment shall be made therefore.

7. EARTHWORK (ROUGH AND FINE GRADING)

The work under this item shall conform to the provisions of Section 31 22 00 "Grading" of these Specifications and as directed by the Engineer.

Payment for this item will be made at the lump sum price. This includes full compensation for all labor, materials, tools, equipment, and for performing all work necessary for rough and fine grading including, but not limited to, all daylighting, construction of the playground mound, and privacy berms as shown on the Plans. No additional payment shall be made therefore.

BASES & SIDEWALK AT VARIOUS LOCATIONS

8. CONSTRUCT 6" THICK CLASS II AGGREGATE BASE

This item shall conform to the Plans, these Specifications, and Section 26-1.02B "Class 2 Aggregate Base" of the 2023 Caltrans Standard Specifications.

This item shall be paid for at the Contract unit price per cubic yard of placed material. Said price includes full compensation for furnishing all labor, materials, tools, equipment and for doing all the work involved in constructing the class II aggregate base complete and in place, as shown on the Plans and specified herein, including, but not limited to, the parking lot, ADA campsite parking areas, crosswalks leading to the various existing restrooms, stamped concrete crosswalks, ~~embankment slide mound~~, and restroom. No additional payment will be made therefore.

9. CONSTRUCT 4" THICK CLASS II AGGREGATE BASE FOR PLAYGROUND EMBANKMENT MOUND

This item shall conform to the Plans, these Specifications, and Section 26-1.02B "Class 2 Aggregate Base" of the 2023 Caltrans Standard Specifications.

This item shall be paid for at the Contract unit price per cubic yard of placed material. Said price includes full compensation for furnishing all labor, materials, tools, equipment and for doing all the work involved in constructing the class II aggregate base complete and in place, as shown on the Plans and specified herein, including, but not limited to, embankment slide mound. No additional payment will be made therefore.

10. CONSTRUCT 4" THICK CONCRETE ~~PLAYGROUND SIDEWALK~~

The work under this item shall conform to the provisions of Section 03 30 00 "Cast-In-Place Concrete" of these Specifications.

Payment for this item shall be made per square footage. This includes full compensation for all labor, materials, tools, and equipment necessary to construct the sidewalk at the locations specified in the Plans including, but not limited to, the playgrounds ~~and concrete transitions from the decorative reinforced concrete crosswalks to the stabilized dg paths~~. No additional payment shall be made therefore.

11. CONSTRUCT 6" THICK CONCRETE PADS AND SIDEWALK

The work under this item shall conform to the provisions of Section 03 30 00 "Cast-In-Place Concrete" of these Specifications.

Payment for this item shall be made per square footage. This includes full compensation for all labor, materials, tools, and equipment necessary to construct the concrete pads (including thickened sections) for, but not limited to, all furnishings, group fire pit area, restroom perimeter sidewalk, and ADA campsites. No additional payment shall be made therefore.

RESTROOM & SEPTIC SEWAGE SYSTEM

12. CONSTRUCT PREFABRICATED PUBLIC RESTROOM BUILDING MODEL# S-301 (SANTIAGO) COMPLETE AND IN PLACE

The work under this item shall conform to the provisions of Section 13 00 00 "Prefabricated Restroom" of these Specifications and the Manufacturer's Specifications.

This item includes, but is not limited to, the furnishing and installation of the "CXT Incorporated" Prefabricated Restroom, construction of 6 inch layer of crushed rock, the installation of all required water and sewer plumbing and plumbing fixtures pertinent to the restroom, connecting to the existing water service line, installing backflow prevention device and shut off valve, and installation of all electrical systems, as shown on the Plans.

Payment for this item will be made at the lump sum price which includes full compensation for locating and connecting to the existing water service line, all required trenching and pipe, backfilling and compaction, labor, materials, tools, and equipment necessary to complete the work. No additional payment shall be made therefore.

13. CONSTRUCT SEPTIC SEWAGE SYSTEM COMPLETE AND IN PLACE

The work under this item shall conform to the provisions of Section 33 30 00 "Septic Sewage System" of these Specifications.

This item includes, but is not limited to, the installation of all required sewer plumbing and fixtures, installation of septic sewer cleanouts, installation of 2500 gallon septic tank, Construction of effluent pump system including the installation of the basin, duplex pump system, and control panel, installation of the distribution box, furnishing and installing silty sand fill, construction of mounded leach field, installation of perforated leach lines, drain rock, and connecting the system to the prefabricated restroom shown on the Plans.

Payment for this item will be made at the lump sum price which includes full compensation for connecting to the restroom, all required trenching and pipe, backfilling and compaction, labor, materials, tools, and equipment necessary to complete the work. No additional payment shall be made therefore.

PARKING LOT & ADA SITE CONCRETE IMPROVEMENTS

14. CONSTRUCT 6" THICK REINFORCED CONCRETE PAVEMENT

The work under this item shall conform to the provisions of Section 03 30 00 "Cast-In-Place Concrete" and Section 03 20 00 "Concrete Reinforcing" of these Specifications.

Payment for this item shall be made per square footage. This includes full compensation for all labor, materials, tools, and equipment necessary to construct the reinforced concrete pavement at the locations specified in the Plans including, but not limited to, the parking lot, ADA campsite parking areas, and the crosswalks leading to the various restrooms from the ADA campsites. No additional payment shall be made therefore.

15. INSTALL 5' LONG X 3' WIDE DETECTABLE WARNING SURFACE PANEL COMPLETE AND IN PLACE

Payment for this item shall be made per each surface panel required. This includes full compensation for all labor, materials, tools, and equipment to install the warning surface panels at the locations specified in the Plans. No additional payment shall be made therefore.

16. INSTALL 72" PRECAST CONCRETE WHEEL STOPS

Payment for this item shall be made per each concrete wheel stop and includes full compensation for all labor, materials, tools, and equipment required to install the wheel stops at the locations specified in the Plans. No additional payment shall be made therefore.

LANDSCAPING & STAMPED CONCRETE

17. PERFORM ALL LANDSCAPE CONSTRUCTION WORK

The work under this item shall conform to the provisions of Section 32 15 40 "Stabilized Natural Pavement", Section 31 22 00 "Grading", and Section 31 25 00 "Erosion and Sedimentation Controls" of these Specifications.

This item includes, but is not limited to, the construction of the stabilized California gold decomposed granite walking paths, path edging, stabilized California gold decomposed granite maze, the gathering and placement of river rock for the maze, construction of riprap swale, **hydroseeding all exposed slopes and graded soils with California native seed mix**, and the installation of landscaping fabric as shown on the Plans. This bid item excludes the Hiking Trail.

Payment for this item will be made at the lump sum price which includes full compensation for locating and placing river rocks, backfilling and compaction, **hydroseeding**, labor, materials, tools, and equipment necessary to complete the work. No additional payment shall be made therefore.

18. CONSTRUCT 6" THICK REINFORCED STAMPED CONCRETE CROSSWALKS

The work under this item shall conform to the provisions of Section 03 30 00 "Cast-In-Place Concrete" and Section 03 20 00 "Concrete Reinforcing" of these Specifications.

Payment for this item shall be made per square footage. This includes full compensation for all labor, materials, tools, and equipment necessary to construct the decorative reinforced concrete crosswalks at the location shown on the Plans. No additional payment shall be made therefore.

HIKING TRAIL

19. CONSTRUCT HIKING TRAILS AND PLACE RIVER ROCK

Payment for this item will be made at the lump sum price which includes full compensation for, but not limited to, clearing the path, collecting and placing the river rock, compaction, labor, materials, tools, and equipment necessary to complete the work. No additional payment shall be made therefore.

SITE FURNISHINGS

20. INSTALL 92" SMOOTH TOP PICNIC TABLE STANDARD LEGS (MODEL# 100S)

Payment for this item shall be made per each "Outdoor Creations" picnic table, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the picnic tables at the locations specified in the Plans. No additional payment shall be made therefore.

21. INSTALL 96" SERVICE TABLE WIDE LEG (MODEL# 102W)

Payment for this item shall be made per each "Outdoor Creations" service table, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the service table at the location specified in the Plans. No additional payment shall be made therefore.

22. INSTALL GROUP BBQ WITH ADJUSTABLE GRILL (MODEL# 3001AG)

Payment for this item shall be made per each "Outdoor Creations" group bbq grill, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the bbq grills at the locations specified in the Plans. No additional payment shall be made therefore.

23. INSTALL ADA 30" X 17 3/8" HIGH, NON-ADJUSTABLE, SINGLE FLANGE, SINGLE WALL, PAINTED, FIRE RING, 23" HIGH DRAFT HOLES, WITH (2) STAPLES (MODEL# 11302-SP23)

Payment for this item shall be made per each "Jamestown Advanced Products" ADA compliant fire ring, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the fire rings at the locations specified in the Plans. No additional payment shall be made therefore.

24. INSTALL GROUP FIRE PIT WITH STEEL LINER (4' DIAMETER) (MODEL# 304, 304SL)

Payment for this item shall be made per each "Outdoor Creations" group fire pit, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the fire pit at the location specified in the Plans. No additional payment shall be made therefore.

25. INSTALL CORN HOLE GAME SET (BEAN TOSS)-2 PIECES (MODEL# 1510)

Payment for this item shall be made per each "Outdoor Creations" corn hole board, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the corn hole boards at the locations specified in the Plans. No additional payment shall be made therefore.

26. INSTALL 72" CONTOUR BENCH (MODEL# 407)

Payment for this item shall be made per each "Outdoor Creations" bench, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the benches at the locations specified in the Plans. No additional payment shall be made therefore.

27. INSTALL 14" X 83.5" BENCH WITH 203" RADIUS CURVE (MODEL# 404R203)

Payment for this item shall be made per each "Outdoor Creations" curved bench, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the benches at the locations specified in the Plans. No additional payment shall be made therefore.

28. RELOCATE EXISTING FIRE RINGS AS SHOWN ON THE PLANS COMPLETE AND IN PLACE

This bid item is a lump sum bid item that accounts for all work required in relocating the existing fire rings onsite and includes full compensation for furnishing all labor, materials, tools, equipment, and incidentals necessary for reinstalling the fire rings at the locations specified on the Plans complete and in place. This includes, but is not limited to, removal and transport of fire rings, site preparation, and reinstallation ensuring a securely positioned and functional fire ring. No additional payment shall be made therefore.

PAVILION STRUCTURES

29. CONSTRUCT 30' X 40' X 8.5' RECTANGULAR GABLE SHELTER COMPLETE AND IN PLACE

The work under this item shall conform to the provisions of Section 10 73 60 "Site Shelters" of these Specifications.

Payment for this item shall be made per each structure and includes full compensation for all labor, materials, tools, equipment, and all work related to the furnishing and installation of the "ICON Shelter Systems Inc." pavilions, at the locations specified in the Plans. This includes, but is not limited to, coordination with manufacturer, furnishing, assembling, installing all support structures, concrete footings, bolts and fittings, connections, and roofing. No additional payment shall be made therefore.

30. CONSTRUCT PAVILION CONCRETE PAD

The work under this item shall conform to the provisions of Section 03 30 00 "Cast-In-Place Concrete" of these Specifications.

Payment for this item shall be made per square footage. This includes full compensation for all labor, materials, tools, and equipment necessary to construct the concrete pads for the pavilions as shown on the Plans. No additional payment shall be made therefore.

MULTI-AGE PLAYGROUND SITES

31. INSTALL PLAY STACK (MODEL# 4500-008) COMPLETE AND IN PLACE

Payment for this item shall be made per each and includes full compensation for all labor, materials, tools, and equipment required for the furnishing and installation of the "Columbia Cascade" play stack, or approved equal, as specified in the Plans. This includes, but is not limited to, installing all support structures, concrete footings, bolts and fittings, and connections. No additional payment shall be made therefore.

32. INSTALL 7FT EMBANKMENT SLIDE (MODEL# C-1650-71-EMB) AND TURF COMPLETE AND IN PLACE

Payment for this item shall be made in lump sum and includes full compensation for all labor, materials, tools, and equipment required for the furnishing and installation of the "Columbia Cascade" slide, or approved equal, as specified in the Plans. This includes, but is not limited to, installing all support structures, concrete footings, bolts and fittings, connections, recycled plastic lumber nailer boards, asphalt concrete pad, fall pad, and turf. No additional payment shall be made therefore.

33. INSTALL LOG STEPPERS (MODEL# 1501-3) COMPLETE AND IN PLACE

Payment for this item shall be made per each and includes full compensation for all labor, materials, tools, and equipment required for the furnishing and installation of the "Columbia Cascade" log steppers, or approved equal, as specified in the Plans. This includes, but is not limited to, installing all support structures, concrete footings, bolts and fittings, and connections. No additional payment shall be made therefore.

34. INSTALL AGE 2-5 LOG SCRAMBLE (MODEL# 4500-304) COMPLETE AND IN PLACE

Payment for this item shall be made per each and includes full compensation for all labor, materials, tools, and equipment required for the furnishing and installation of the "Columbia Cascade" log scramble, or approved equal, as specified in the Plans. This includes, but is not limited to, installing all support structures, concrete footings, bolts and fittings, and connections. No additional payment shall be made therefore.

35. INSTALL AGE 5-12 LOG SCRAMBLE (MODEL# 4500-305) COMPLETE AND IN PLACE

Payment for this item shall be made per each and includes full compensation for all labor,

materials, tools, and equipment required for the furnishing and installation of the "Columbia Cascade" log scramble, or approved equal, specified in the Plans. This includes, but is not limited to, installing all support structures, concrete footings, bolts and fittings, and connections. No additional payment shall be made therefore.

36. CONSTRUCT 6" WIDE PLAYGROUND CONCRETE KEY COMPLETE AND IN PLACE

The work under this item shall conform to the provisions of Section 03 30 00 "Cast-In-Place Concrete" and Section 03 20 00 "Concrete Reinforcing" of these Specifications.

Payment for this item shall be made per linear footage. This includes full compensation for all labor, materials, tools, and equipment necessary to construct the concrete key as specified in the Plans. No additional payment shall be made therefore.

37. CONSTRUCT 12" THICK PLAYGROUND PLAY AREA WOOD FIBER SURFACING COMPLETE AND IN PLACE

Payment for this item shall be made per square footage. This item includes full compensation for all labor, materials, tools, and equipment required for installing the wood fiber as shown on the Plans and as directed by the Engineer. This includes, but is not limited to, preparing and compacting the subgrade, furnishing and placing wood fiber, placing crushed gravel, and installing landscaping fabric. No additional payment shall be made therefore.

38. CONSTRUCT 6" CONCRETE RETAINING CURB

The work under this item shall conform to the provisions of Section 03 30 00 "Cast-In-Place Concrete" and Section 03 20 00 "Concrete Reinforcing" of these Specifications.

Payment for this item shall be made per linear foot. This includes full compensation for all labor, materials, tools, and equipment necessary to construct the concrete retaining curb for the playground, as specified in the Plans. No additional payment shall be made therefore.

SITE ELECTRICAL

39. CONSTRUCT ALL PARK SITE ELECTRICAL CONDUITS, WIRING, FIXTURE, PANELS, AND APPARATUSES COMPLETE AND IN PLACE

The work under this item shall conform to the provisions of Section 26 00 00 "Electric General Requirements" and Section 26 50 00 "Basic Materials and Methods" of these Specifications.

This item includes, but is not limited to, locating the point of connection as shown on the Plans and extending conduit to prefabricated restroom and picnic pavilions, pulling wire from existing electrical panel to the locations specified on the Plans, and installing all panels and apparatuses required.

Payment for this item will be made at the lump sum price which includes full compensation for trenching, pipe, backfilling and compaction, labor, materials, tools, and equipment necessary to complete the work. No additional payment shall be made therefore.

STRIPING, SIGNAGE, AND MARKINGS

40. SIGNAGE, STRIPING AND MARKINGS

Payment for this item will be made at the lump sum price which includes full compensation

for all labor, materials, tools, and equipment necessary to complete the work specified on the Plans. No additional payment shall be made therefore.

WATER SPIGOTS

41. RELOCATE AND INSTALL SELF-CLOSING WATER SPIGOTS COMPLETE AND IN PLACE

This item includes, but is not limited to, locating the points of connection and connecting to the existing water system, constructing concrete pads, installing pipe, redwood posts, and installing “Haws” self-closing faucet valves Model 6252EHLF, or approved equal, at the locations specified on the Plans.

Payment for this item will be made at the lump sum price which includes full compensation for trenching, pipe, backfilling and compaction, labor, materials, tools, and equipment necessary to complete the work. No additional payment shall be made therefore.

ASPHALT TREATMENT

42. CONSTRUCT POLYMER MODIFIED EMULSION (PME) CHIP SEAL

The work under this item shall conform to the provisions of Section 37-2.03 “Polymer Modified Asphaltic Emulsion Chip Seals” of the Special Provisions.

Payment for this item shall be made per square yard which includes full compensation for all labor, surface preparation, materials, and equipment required to complete the work. No additional payment shall be made therefore.

43. CONSTRUCT TYPE 'A' ASPHALT CONCRETE PAVEMENT SECTIONS AND PATCHES

The work under this item shall conform to the provisions of Section 39-2.02 “Type A Hot Mix Asphalt” of the Special Provisions.

This item includes, but is not limited to, removing existing asphalt concrete, compacting the subgrade, and placing the new HMA as shown on the Plans.

This item shall be paid for at the Contract unit price per ton **up to the theoretical maximum**, additional tonnage will not be compensated. The theoretical maximum shall be measured and agreed upon by the County and the Contractor prior to commencing work. Said price includes full compensation for furnishing all labor, materials, tools, equipment and for doing all the work involved in constructing the asphalt concrete pavement sections, **and** patches, **digout repairs, and pothole repairs**, Type ‘A’ complete and in place, as shown on the Plans. No additional payment will be made therefore.

BID ADDITIVES

44. BID ADDITIVE 1: CONSTRUCT TWO-POST TIMBER KIOSKS

Payment for this item shall be made per each “Romtec” timber kiosk, approved equal, or Contractor to provide his/her own material per plans and specifications and includes full compensation for, but not limited to, the construction of concrete footings, connections, bolts and nuts, all labor, materials, tools, and equipment required to furnish and install the timber kiosk at the location specified on the Plans. No additional payment shall be made therefore.

45. BID ADDITIVE 2 – INSTALL SOLAR-POWERED LIGHTED BOLLARDS (PLB SERIES)

Payment for this item shall be made per each "First Light Technologies" solar lighted bollard, or approved equal, and includes full compensation for all labor, materials, tools, and equipment required to furnish and install the solar lighted bollards at the locations specified in the Plans. No additional payment shall be made therefore.

46. BID ADDITIVE 2 – INSTALL RAB SCENCE LIGHTS FOR PAVILIONS

Payment for this item shall be made per each "RAB" sconce light, or approved equal, and includes full compensation for all labor, materials, tools, wiring, and equipment required to furnish and install the sconce lights at the locations specified in the Plans. No additional payment shall be made therefore.

47. BID ADDITIVE 3: CONSTRUCT SAND VOLLEYBALL COURTS COMPLETE AND IN PLACE

The work under this item shall conform to the provisions of Section 31 23 04 "Excavation and Fill for Structures" of these Specifications.

This item includes, but is not limited to, the installation of all "Sports Imports", or approved equal, posts, volleyball nets, post safety pads, boundary lines, all bolts, nuts and fittings, the construction of concrete footings, 6" wide concrete edging, import and installation of volleyball court sand, gravel, and the installation of landscaping fabric as shown on the Plans.

Payment for this item will be made at the lump sum price which includes full compensation for backfilling and compaction, labor, materials, tools, and equipment necessary to complete the work. No additional payment shall be made therefore.

48. BID ADDITIVE 4: CONSTRUCT 6" THICK REINFORCED BASKETBALL COURT CONCRETE

The work under this item shall conform to the provisions of Section 03 30 00 "Cast-In-Place Concrete" and Section 03 20 00 "Concrete Reinforcing" of these Specifications.

Payment for this item shall be made per square footage. This includes full compensation for all labor, materials, tools, and equipment necessary to construct the reinforced concrete basketball court as specified in the Plans. No additional payment shall be made therefore.

49. BID ADDITIVE 4: INSTALL FIXED HEIGHT BASKETBALL HOOP

Payment for this item shall be made per each basketball hoop and includes full compensation for all labor, materials, tools, and equipment required to install the "MegaSlam Hoops" basketball hoops model FX72, or approved equal. This includes, but is not limited to, the installation of the anchor system, construction of concrete footings, and the installation of equipment. No additional payment shall be made therefore.

50. BID ADDITIVE 5 - CONSTRUCT POLYMER MODIFIED EMULSION (PME) CHIP SEAL

The work under this item shall conform to the provisions of Section 37-2.03 "Polymer Modified Asphaltic Emulsion Chip Seals" of the Special Provisions.

Payment for this item shall be made per square yard, which includes full compensation for all labor, surface preparation, materials, and equipment required to complete the work. No additional payment shall be made therefore.

Fresno County Department of Public Works and Planning

Bid Item List - Proposal 2A

Contract # 24-11-PR

Contract Name Choinumni Park Improvements
Location 26501 Pine Flat Road, Sanger, CA 93657

Item ID	Quantity	Unit	Unit Price	Total
Description				

Base Bid - General

1	1	LS	\$	\$
---	---	----	----	----

Mobilization & Demobilization

2	1	LS	\$	\$
---	---	----	----	----

Job Site Management

3	1	LS	\$	\$
---	---	----	----	----

Implement Approved Storm Water Pollution Prevention Plan (SWPPP)

4	1,500	\$	\$1.00	\$1,500.00
---	-------	----	--------	------------

State Water Resources Control Board Notice of Intent Filing Fee

5	1	LS	\$	\$
---	---	----	----	----

Demolition, Clearing & Grubbing

Base Bid - Site Preperation and Grading

6	1	LS	\$	\$
---	---	----	----	----

Construction Staking

7	1	LS	\$	\$
---	---	----	----	----

Earthwork (Rough & Fine Grading)

Item ID	Quantity	Unit	Unit Price	Total
Description				

Base Bid - Bases & Sidewalk at Various Locations

8	143	CY	\$	\$
---	-----	----	----	----

Construct 6" Thick Class II Aggregate Base - Final Pay Item

9	23	CY	\$	\$
---	----	----	----	----

Construct 4" Thick Class II Aggregate Base for Playground Embankment Mound

10	5,190	SF	\$	\$
----	-------	----	----	----

Construct 4" Thick Concrete Playground Sidewalk

11	13,955	SF	\$	\$
----	--------	----	----	----

Construct 6" Thick Concrete Pads and Sidewalk

Base Bid - Restroom & Septic Sewage System

12	1	LS	\$	\$
----	---	----	----	----

Construct Prefabricated Public Restroom Building Model# S-301 (Santiago) Complete and In Place

13	1	LS	\$	\$
----	---	----	----	----

Construct Septic Sewage System Complete and In Place

Base Bid - Parking Lot & Site Concrete Improvements

14	6,442	SF	\$	\$
----	-------	----	----	----

Construct 6" Thick Reinforced Concrete Pavement

15	26	EA	\$	\$
----	----	----	----	----

Install 5' Long x 3' Wide Detectable Warning Surface Panels Complete and in Place

16	7	EA	\$	\$
----	---	----	----	----

Install 72" Precast Concrete Wheel Stops

Item ID	Quantity	Unit	Unit Price	Total
Description				

Base Bid - Landscaping & Stamped Concrete

17	1	LS	\$	\$
Perform All Landscape Construction Work				
18	752	SF	\$	\$
Construct 6" Thick Reinforced Stamped Concrete Crosswalks				

Base Bid - Hiking Trail

19	1	LS	\$	\$
Construct Hiking Trail, Clear Path and Place River Rock				

Base Bid - Site Furnishings

20	90	EA	\$	\$
Install 92" Smooth Top Picnic Table Standard Legs (Model# 100S)				
21	1	EA	\$	\$
Install 96" Service Table Wide Leg (Model# 102W)				
22	2	EA	\$	\$
Install Group BBQ with Adjustable Grill (Model# 3001AG)				
23	4	EA	\$	\$
Install ADA 30" X 17 3/8" High, Non-Adjustable, Single Flange, Single Wall, Painted, Fire Ring, 23" High Draft Holes, with (2) Staples (Model# 11302-SP23)				
24	1	EA	\$	\$
Install Group Fire Pit with Steel Liner (4' diameter) (Model# 304, 304SL)				
25	5	EA	\$	\$
Install Corn Hole Game set (bean toss)-2 Pieces (Model# 1510)				

Item ID	Quantity	Unit	Unit Price	Total
Description				
26	8	EA	\$	\$
Install 72" Contour Bench (Model# 407)				
27	4	EA	\$	\$
Install 14" x 83.5" Bench with 203" radius curve (Model# 404R203)				
28	1	LS	\$	\$
Relocate Existing Fire Rings As Shown on Plans Complete and In Place				
Base Bid - Pavilion Structures				
29	2	EA	\$	\$
Construct 30' x 40' x 8.5' Rectangular Gable Shelters Complete and in Place				
30	5,000	SF	\$	\$
Construct Pavilion Concrete Pad				
Base Bid - Multi-Age Playground Sites				
31	1	EA	\$	\$
Install Play Stack (Model# 4500-008) Complete and In Place				
32	1	LS	\$	\$
Install 7ft Embankment Slide (Model# C-1650-71-EMB) and Turf Complete and In Place				
33	4	EA	\$	\$
Install Log Steppers (Model# 1501-3) Complete and In Place				
34	1	EA	\$	\$
Install Age 2-5 Log Scramble (Model# 4500-304) Complete and In Place				
35	1	EA	\$	\$
Install Age 5-12 Log Scramble (Model# 4500-305) Complete and In Place				

Item ID	Quantity	Unit	Unit Price	Total
36	346	LF	\$	\$
Construct 6" Wide Playground Concrete Key Complete and In Place				
37	2,900	SF	\$	\$
Construct 12" Thick Playground Play Area Wood Fiber Surfacing Complete and In Place				
38	58	LF	\$	\$
Construct 6" Concrete Retaining Curb				
Base Bid - Site Electrical				
39	1	LS	\$	\$
Construct All Park Site electrical conduits, wiring, fixture, panels, and apparatuses complete and In place				
Base Bid - Striping, Signage, and Markings				
40	1	LS	\$	\$
Signage, Striping and Markings				
Base Bid - Water Spigots				
41	1	LS	\$	\$
Relocate and Install Self-Closing Water Spigots Complete and In Place				
Base Bid - Asphalt Treatment				
42	5,050	SY	\$	\$
Construct Polymer Modified Emulsion (PME) Chip Seal				
43	39	TON	\$	\$
Construct 'Type A' Asphalt Concrete Pavement Sections and Patches				
Base Bid Items Total (Items 1 through 41):				\$

Additive 1 - Trail Kiosks

Item ID	Quantity	Unit	Unit Price	Total
Description				
44	6	EA	\$	\$
Construct Two-Post Timber Kiosk				
Additive 1 Bid Items Total (Items 42):				\$

Additive 2 (Park Lighting)

Item ID	Quantity	Unit	Unit Price	Total
Description				
45	36	EA	\$	\$
Install Solar-Powered Lighted Bollards (PLB Series)				
46	12	EA	\$	\$
Install RAB Sconce Lights for Pavilions				
Additive 2 Bid Items Total (Items 43 through 44):				\$

Additive 3 (Sand Volleyball Courts)

Item ID	Quantity	Unit	Unit Price	Total
Description				
47	1	LS	\$	\$
Construct Sand Volleyball Courts Complete and In Place				
Additive 3 Bid Items Total (Items 45):				\$

Additive 4 (Basketball Court and Equipment)

Item ID	Quantity	Unit	Unit Price	Total
Description				
48	6,048	SF	\$	\$
Construct 6" Thick Reinforced Basketball Court Concrete				
49	2	EA	\$	\$
Install Fixed Height Basketball Hoop				

Additive 4 Bid Items Total (Items 46 through 47): \$

Additive 5 (Asphalt Treatment for Rest of Existing HMA Pavement)

Item ID	Quantity	Unit	Unit Price	Total
Description				
50	22,325	SY	\$	\$
Construct Polymer Modified Emulsion (PME) Chip Seal				

Additive 5 Bid Items Total (Items 48): \$

Total Bid (Base Bid Items + Additive Items) Items 1 through 48: \$