

ADDENDUM 02

Contract # 24-S-03


Dated: February 14, 2025

The foregoing documents are amended in the respects as herein set forth. This addendum and the amendments herein shall become part of said documents and of any contract entered into pursuant to said documents.

PLEASE ACKNOWLEDGE THIS ADDENDUM ON YOUR PROPOSAL. IF YOU HAVE GIVEN THE CONTRACT DOCUMENTS TO SOMEONE ELSE, PLEASE FORWARD THIS ADDENDUM.

2025-02-14

Date Signed



Architect of Record: _____ Barry Mast, Lic.# C-38769

FRESNO COUNTY
Department of Public Works and Planning
Development Services and Capital Projects Division
m/a 2220 Tulare Street, Eighth Floor
Fresno, CA 93721 (559) 600-4536
bmast@fresnocountyca.gov

A. BID FORMS: PAPER

- a. Section 0002113 Instructions to Bidders
1.06. SUBMISSION OF PROPOSAL

DELETE: A Electronic Bid Submittal

The bidder has the option to submit the bid for this Project electronically. The bidder must either attach an electronic bid bond or provide an original bid bond (or other form of bid security authorized by Public Contract Code Section 20129(a)), prior to the bid opening.

Bidders submitting online may use one of the accepted electronic sureties (Tinubu Surety or Surety 2000) to submit their bid bond; or may submit cash, cashier's check, certified check, or a bidder bond to Design Services at 2220 Tulare St., Seventh Floor, Fresno, CA 93721. Those submitting bid bonds directly to Design Services must submit their bid bond:

1. Under sealed cover
2. Marked as a bid-bond
3. Identifying the contract number and the bid opening date on the cover

If necessary, please e-mail DesignServices@fresnocountyca.gov or call (559) 353-4919 or (559) 600-4543, so that arrangements may be made to hand deliver your bid bond. Each proposal shall be submitted in a sealed envelope labeled to clearly indicate the contract and contents.

REPLACE with: A. Electronic Bid Submittal

The bidder has the option to submit the bid for this Project electronically. The bidder must either attach an electronic bid bond or provide an original bid bond (or other form of bid security authorized by Public Contract Code Section 20129(a)), prior to the bid opening.

Bidders submitting online may

1. use one of the accepted electronic sureties (Tinubu Surety or Surety 2000) to submit their bid bond; or
2. attach to the online bid a scan of a notarized paper bid, followed by delivery of the original paper notarized bidder's bond by the admitted surety insurer so that it is received by Design Services no later than 4:00 PM on the fifth (5th) calendar day after the bid opening.; or
3. submit cash, cashier's check, certified check, or a bidder bond so that it is received by Design Services prior to the bid opening.

Hardcopy bid bonds shall be

- submitted in a sealed envelope
- addressed to "Department of Public Works and Planning, Office of the Design Engineer" and
- labeled with
 - the name of the bidder,
 - contract number,
 - name of the project, and
 - the statement "Do Not Open Until The Time Of Bid Opening – BID BOND."

The address for hand delivery is listed in the Notice to Bidders for the bid opening (Seventh Floor, Fresno County Plaza Building, 2220 Tulare St., Fresno, CA 93721). The address for delivery by mail is Sixth Floor, Fresno County Plaza Building, 2220 Tulare Street, Fresno, CA 93721).

B. BID FORMS: BID EXPRESS

Bid Security Form Section 004313 – 1 replaced with Bid Security Form
Section 004313 - 1A and replaced Required Documents with Required Documents A.
Updated to add the option of attaching a scan of a notarized paper bid bond.

C. CONTRACT CONDITIONS

No changes

D. SPECIFICATIONS

No changes

E. DRAWINGS

- a. Sheet A-103
 - i. SITE PLAN KEYNOTES, item 35. Revise to indicate 24-foot-wide gate assembly. Provide sliding gate to match materials, height, and appearance of adjacent steel fence. Provide a reinforced concrete grade beam along entire length of sliding gate track.
 - ii. Provide new concrete curb and asphalt patch adjacent to parking stall 151 at north PUBLIC PARKING area. See also SITE DEMOLITION PLAN, detail A2/A-102.
 - iii. Provide new concrete curb and asphalt patch adjacent to parking stall 25 at south REAR GATE PARKING. See also SITE DEMOLITION PLAN, detail A2/A-102.
- b. Sheet A-105
 - i. Detail E1.
 - 1. Provide security mesh on secure side of swing gate and 16" minimum wide on secure side of fence at latch to prevent access to egress hardware.
 - 2. Revise to provide 3" square posts instead of 3" diameter posts.
 - ii. Detail A9. Revise to provide 6" high wheel stop per keynote 32, SITE PLAN KEYNOTES, sheet A-103.
- c. Sheet A-201.1, PARTIAL GROUND FLOOR DEMOLITION PLAN, detail A2. Replace keynote 6 in (E) VIP ROOM [149] to indicate ceiling tile and grid shall be removed and replaced.
- d. Sheet A-201.2, PARTIAL SECOND FLOOR DEMOLITION PLAN, detail G2. Delete keynote 5 at rooms 202 thru 218. Existing carpet and base to remain.
- e. Sheet A-202.1, PROPOSED PARTIAL GROUND FLOOR PLAN "A", detail A2. Provide level 3 ballistic rated fiberglass panel below windows behind new gypsum board, typical full width of window from sill to floor.
- f. Sheet A-203.0, GROUND FLOOR REFLECTED CEILING DEMO PLAN, detail J2. Replace keynote 1 at room between grids 7.9 and 8.0 and between grids E and F

(Existing VIP Room 149) to indicate ceiling tile and grid shall be removed and replaced.

- g. Sheet A-601
 - i. DOOR OPENING SCHEDULE & LEGEND, detail H2
 - 1. Delete DOOR TYPE C
 - 2. Revise DOOR SCHEDULE as follows:
 - a. MARK 04, revise to DOOR TYPE B
 - b. MARK 05, revise to DOOR TYPE B
 - 3. Revise HARDWARE SCHEDULE as follows:
 - a. SET #1. Delete hinge specification. Center pivot hinges in narrow stile single glaze swing door to be provided as part of storefront entry system to match existing. Contractor shall verify.
 - b. Set #4. Delete surface closer. Provide surface mounted automatic door operator compatible with push-button actuator specified.
 - ii. FINISH LEGEND, FLOORING, F3. Revise to indicate basis of design as daltile Keystones Colorbody Porcelain 2x2 Mosaic or similar. Color to be selected from manufacturer standard palette.