






FP0.1














	Sprinkler Legend										
Symbol	Manufacturer	SIN	Model	Quantity	K-Factor	Туре	Size	Response	Finish	Temperature	Note
$\odot$	Generic			17	5.6	Upright	1/2	Standard	Brass	165 °F	Out of Scope
<b>&gt;</b>	Generic			3	5.6	Sidewall	1/2	Quick	Chrome	155 °F	Out of Scope
	Minimax	MX7302		119	5.6	Pendent	1/2	Quick	Chrome	155 °F	-
0	Minimax	MX7300		60	5.6	Upright	1/2	Quick	Brass	155 °F	
0	Minimax	MX7300		2	5.6	Upright	1/2	Quick	Brass	200 °F	
	1.			Total = 201							

Sprinkler Components Legend

PIPING W/ GROOVED FITTINGS PIPING W/ THREADED FITTINGS PIPING W/ PENDENT SPRINKLER (Varies - See Details) PIPING W/ UPRIGHT SPRINKLER (Varies - See Details)

( 0 ) HYDRAULIC NODE REF (DEMO) PIPING (NEW) PIPING THRU RATED WALL

Sheet(s) FP1.0-2.0

Sprinkler Brace / Hanger Legend Symbol Description Detail Reference LATERAL SEISMIC BRACE (Perpindicular) Sheet(s) FP2.0 LONGITUDINAL SEISMIC BRACE (Parallel) -Sheet(s) FP2.0 Sheet(s) FP2.0 4-WAY SEISMIC BRACE (Parallel / Perpindicular) END OF LINE RESTRAINT Sheet(s) FP1.0 PIPE HANGER

1. SYSTEM SHALL BE DESIGNED TO CONFORM WITH NFPA 13 (2016 CALIFORNIA EDITION), CFC/CBC (2016), CITY OF FRESNO FIRE PREVENTION STANDARDS.

 BRIX BUILDING - OBSTRUCTED CONCRETE TEE CONSTRUCTION.
 MERCER BUILDING - UNOBSTRUCTED METAL WEB JOIST CONSTRUCTION.
 FIRE SPRINKLER SYSTEM POINT OF CONNECTION AT EXISTING OVERHEAD SPRINKLER SYSTEM. 4. SPRINKLER DISCHARGE DENSITY FOR THIS PROJECT SHALL BE IN ACCORDANCE WITH NFPA 13 (2016) §11.2.1.2.4 WITH DENSITY CURVES IN ACCORDANCE WITH FIG. 11.2.3.1.1. a. LIGHT HAZARD OCCUPANCY SHALL INCLUDE ALL OFFICE, CORRIDOR, DINING, CONCEALED ATTIC SPACES, RESTROOMS, AND SIMILAR AREAS. LIGHT HAZARD OCCUPANCY SHALL HAVE A DESIGN DENSITY OF 0.10 GPM/FT² OVER A MINIMUM REMOTE AREA OF 1500 FT³. THE MAXIMUM ALLOWABLE PROTECTION AREA OF COVERAGE FOR A SPRINKLER SHALL BE IN ACCORDANCE WITH THE VALUE INDICATED IN TABLE 8.6.2.2.1(a) AND SHALL NOT EXCEED 225FT<sup>2</sup>.

b. ORDINARY HAZARD GROUP I (OH1) SHALL FOOD SERVICE AREAS, ELECTRICAL AND MECHANICAL EQUIPMENT ROOMS, PORTE COCHERES, AND SIMILAR AREAS INDICATED IN NFPA 13 (2016) §A.5.3.1. OH1 OCCUPANCY SHALL HAVE A DENSITY OF

0.15GPM/FT² OVER A MINIMUM REMOTE AREA 0F 1500FT². THE MAXIMUM ALLOWABLE PROTECTION AREA OF COVERAGE FOR A SPRINKLER SHALL BE IN ACCORDANCE WITH THE VALUE INDICATED IN TABLE 8.6.2.2.1(b) – 130FT². c. ORDINARY HAZARD GROUP II (OH2) SHALL INCLUDE AUTOMOTIVE WORKSHOP AREAS, SCIENCE LABRATORIES, STAGES, STORAGE ROOMS, SIMILAR AREAS INDICATED IN NFPA 13 (2016) A.5.3.2. OH2 OCCUPANCY SHALL HAVE A DESIGN DENSITY OF 0.20GPM/FT<sup>2</sup> OVER A MINIMUM REMOTE AREA OF 1500FT<sup>2</sup>. THE MAXIMUM ALLOWABLE PROTECTION AREA OF COVERAGE FOR A SPRINKLER SHALL BE IN ACCORDANCE WITH THE VALUE INDICATED IN TABLE 8.6.2.2.1(b) – 130FT.

5. MAXIMUM SPRINKLER SPACING SHALL NOT EXCEED 15'-0" ON CENTER, UNLESS SPECIFICALLY LISTED BY THE SPRINKLER MANUFACTURER. SPRINKLER MANUFACTUREK.

6. HOSE STREAM ALLOWANCE GPM FLOW SHALL BE IN ACCORDANCE WITH THE VALUES INDICATED IN TABLE 11.2.3.1.2: LIGHT HAZARD – 100 GPM; ORD HAZARD – 250 GPM.

7. PER NFPA 13 (2016) §11.2.3.2.3.1, WHERE LISTED QUICK-RESPONSE SPRINKLERS ARE USED THROUGHOUT A SYSTEM OR PORTION OF A SYSTEM HAVING THE SAME HYDRAULIC DESIGN BASIS, THE SYSTEM AREA OF OPERATION SHALL

BEPERMITTED TO BE REDUCED WITHOUT REVISING THE DENSITY AS INDICATED IN FIG. 11.2.3.2.3.1. NOTE: REMOTE AREA REDUCTION EXCLUDES EXTENDED COVERAGE SPRINKLER HEADS AND ONLY APPLICABLE TO LIGHT HAZARD OCCUPANCY 8. PER NFPA 13 (2016) §11.2.3.2.4, THE SYSTEM REMOTE AREA SHALL BE INCREASED BY 30% WITHOUT REVISING THE DENSITY WHEN SPRAY SPRINKLERS AND CMSA SPRINKLERS ARE USED ON SLOPED CEILINGS WITH A PITCH EXCEEDING 1 IN

9. PER NFPA 13 (2016) §11.2.3.2.7.1, MULTIPLE ADJUSTMENTS CAN BE MADE TO THE REMOTE AREA WHEN BOTH QUICK RESPONSE SPRINKLER AREA REDUCTIONS AND SLOPED CEILING AREA INCREASE ARE APPLICABLE. 10. THE HYDRAULIC CALCULATION SOURCE SHALL BE TO THE FLOW TEST HYDRANT OR APPLICABLE STREET CONNECTION, ACCORDING TO LOCAL FIRE PREVENTION DISTRICT WATER CURVE DETERMINATIONS AND OR TESTING PROCEDURES. REFER TO SITE PLAN AND HYDRAULIC CALCULATIONS. STORAGE HEIGHT SHALL NOT EXCEED 8-FEET.
 MICROBIAL INDUCED CORROSION WILL NOT BE A FACTOR FOR THIS SYSTEM.

13. THE FIRE SPRINKLER ALARM SYSTEM SHALL BE DESIGNED, INSTALLED AND PERMITTED BY OTHERS, AND IS NOT IN THE SCOPE OF WORK. SUPERVISORY FLOW DETECTORS AND TAMPER RESISTANT VALVES INSTALLED ON THE OVERHEAD SPRINKLER SYSTEM PIPING WILL BE SUPPLIED AND INSTALLED BY FIRE SPRINKLER CONTRACTOR AND WIRED BY ALARM 14. PER PROJECT SPECIFICATIONS, IF DESIGN OR MATERIALS DIFFER FROM THAT SPECIFIED HEREIN, SUPPLEMENTAL ENGINEERING DESIGN, SUBMITTAL, AND REVIEW SHALL BE REQUIRED.

GENERAL INSTALLATION REQUIREMENTS:

1. OVERHEAD FIRE SPRINKLER PIPING SHALL BE AS FOLLOWS (UNLESS NOTED OTHERWISE ON PLANS): a. PIPING 2-1/2" AND LARGER SHALL BE SCH.10 BLACK STEEL WITH ROLLED FITTINGS, RISER TO BE SCH.10 BLACK STEEL

 b. PIPING 2" AND LESS SHALL BE SCH.40 BLACK STEEL.
 c. DRAINAGE PIPING 2" OR SMALLER, DOWNSTREAM OF THE DRAIN VALVE SHALL BE SCH. 40 BLACK STEEL WITH ROLLED 2. WHERE APPLICABLE IN UNOBSTRUCTED CONSTRUCTION CONDITIONS (AS DEFINED PER NFPA 13 §3.7.2); PER NFPA 13 (2016) §8.6.4.1.1, THE DISTANCE BETWEEN THE SPRINKLER DEFLECTOR AND THE CEILING SHALL BE A MINIMUM OF 1-INCH AND A MAXIMUM OF 12-INCHES THROUGHOUT THE AREA OF COVERAGE OF THE SPRINKLER.

3. WHERE APPLICABLE IN OBSTRUCTION CONSTRUCTION CONDITIONS (AS DEFINED PER NFPA 13 §3.7.1); PER NFPA 13 (2016) §8.6.4.1.2, SPRINKLER DEFLECTORS SHALL BE INSTALLED WITH THE DEFLECTORS WITHIN THE HORIZONTAL PLANES OF 1-INCH TO 6-INCHES BELOW THE STRUCTURAL MEMBERS AND A MAXIMUM DISTANCE OF 22-INCHES FROM THE CEILING/ROOF DECK.

4. PER NFPA 13 (2016) §8.3.1.3 UPRIGHT SPRINKLERS SHALL BE INSTALLED WITH THE FRAME ARMS PARALLEL TO THE BRANCH LINE, UNLESS SPECIFICALLY LISTED FOR OTHER ORIENTATION. 5. PER NFPA 13 (2016) §8.5.4.2 DEFLECTORS OF SPRINKLERS SHALL BE ALIGNED PARALLEL TO CEILINGS, ROOFS, OR THE 6. PER NFPA 13 (2016) §8.15.1.1 CONCEALED SPACES OF EXPOSED COMBUSTIBLE CONSTRUCTION SHALL BE PROTECTED BY SPRINKLERS EXCEPT IN CONCEALED SPACES WHERE SPRINKLERS ARE NOT REQUIRED TO BE INSTALLED BY 8.15.1.2.1 THROUGH 8.15.1.2.18 AND 8.15.6.

7. PER NFPA 13 (2016) 8.15.1.2.1 CONCEALED SPACES OF NONCOMBUSTIBLE WITH MINIMAL COMBUSTIBLE LOADING HAVING NO ACCESS SHALL NOT REQUIRE SPRINKLER PROTECTION. 8. PER NFPA 13 (2106) 8.15.1.2.3 CONCEALED SPACES FORMED BY STUDS OR JOISTS WITH LESS THAN 6-INCHES BETWEEN THE INSIDE OR NEAR EDGES OF THE STUDS OR JOISTS SHALL NOT REQUIRE SPRINKLER PROTECTION. 9. PER NFPA 13 (2016) 8.15.1.2.7 CONCEALED SPACES FILLED WITH NONCOMBUSTIBLE INSULATION SHALL NOT REQUIRE SPRINKLER PROTECTION; MAXIMUM 2-INCH AIR GAP AT THE TOP OFTHE SPACE SHALL BE PERMITTED. 10. PER NFPA 13 (2016) 8.15.7.3 SPRINKLERS SHALL BE PERMITTED TO BE OMITTED FROM BELOW THE EXTERIOR PROJECTIONS OF COMBUSTIBLE CONSTRUCTION, PROVIDED THE EXPOSED FINISH MATERIAL ON THE EXTERIOR PROJECTIONS ARE NON-COMBUSTIBLE AND THE EXTERIOR PROJECTIONS CONTAIN ONLY SPRINKLERED CONCEALED SPACES OR ANY OF THE FOLLOWING UNSPRINKLERED COMBUSTIBLE CONCEALED SPACES: (1) COMBUSTIBLE CONCEALED SPACES FILLED ENTIRELY WITH NON-COMBUSTIBLE INSULATION, (2) LIGHT OR ORDINARY HAZARD OCCUPANCIES WHERE NONCOMBUSTIBLE OR LIMITED-COMBUSTIBLE CEILINGS ARE DIRECTLY ATTACHED TO THE BOTTOM OF SOLID WOOD
JOISTS SO AS TO CREATE ENCLOSED JOIST SPACES 160-FT<sup>3</sup> OR LESS IN VOLUME, INCLUDING SPACE BELOW INSULATION THAT IS LAID DIRECTLY ON TOP OR WITHIN THE CEILING JOISTS IN AN OTHERWISE SPRINKLERED ATTIC, OR (3) CONCEALED SPACES OVER ISOLATED SMALL EXTERIOR PROJECTIONS NOT EXCEEDING 55FT IN AREA

11. CAGE-TYPE SPRINKLER HEAD GUARDS SHALL BE INSTALLED TO PROTECT ALL SPRINKLERS SUBJECT TO MECHANICAL DAMAGE, INCLUDING ALL NON-CONCEALED PENDENT SPRINKLER BELOW 8-FEET ABOVE FINISH FLOOR OR EXPOSED UPRIGHTS AND PENDENT SPRINKLER INSTALLED DIRECTLY ON PIPING WITHIN A GYMNASIUM AREA. 2. ALL HANGERS, BRACES, AND RESTRAINTS SHALL BE INSTALLED IN ACCORDANCE WITH NFPA 13 (2016 CALIFORNIA EDITION), CBC/CFC (2016), CITY OF FRESNO FIRE PREVENTION.

13. PER NFPA 13 (2016) §9.3.6.5 BRANCH LINE RESTRAINT SHALL NOT BE REQUIRED WHERE BRANCH LINES ARE SUPPORTED BY RODS LESS THAN 6" IN LENGTH WHEN MEASURED BETWEEN THE TOP OF THE PIPE TO THE POINT OF ATTACHMENT TO



CONSULTANT STAMP



LIC. C-16, 982763 4277 W. RICHERT AVE. STE. 103 FRESNO, CALIFORNIA (559) 275-4894



AUG 2 9 2024 09

FRESNO FIRE DEPARTMENT

REV.	DESCRIPTION PC COMMENTS	DATE 05-18-2024
DATE:		11/11/202
SCALE:		As indicate

ADDRESS:

JOB NUMBER:

**BRIX & MERCER BLDGS** 1221 FULTON ST FRESNO, CA 93721

PROJECT:

21-1137

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION


SHEET TITLE:

BRIX BUILDING FIRE SPRINKLER LAYOUT PLAN


SHEET NUMBER




⚠ "FOR REFERENCE ONLY"



Sprinkler Components Legend









MURATORE ASSOCIATES





FRESNO FIRE DEPARTMENT


-	REVISION	TABLE:	
-	REV.	DESCRIPTION	DATE
1			
-			
-			
-			
-			
1			
-			
- 1			

11/15/2022 As indicated

BRIX & MERCER BLDGS


FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT


BASEMENT DEMO PLUMBING




REV.	DESCRIPTION	DATE
		MANAGEMENT OF THE PERSON NAMED IN COLUMN 2

11/15/2022 As indicated






DETAILED PLUMBING PLAN - MERCER BLDG.











# **APPROVED**

AUG 2 9 2024 00

FRESNO FIRE DEPARTMENT

REVISION	TABLE:	
REV.	DESCRIPTION	DATE

11/15/2022 SCALE: As indicated JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT

RENOVATION


ENLARGED BASEMENT PLUMBING PLANS


SHEET NUMBER


DEVELOPMENT SERVICES

P2.02

P2.02








DETAILED PLUMBING PLAN - MERCER BLDG.


APPROVED AU3 2 9 2024 0



DETAILED PLUMBING PLAN - MERCER BLDG.

SCALE: 1/4"=1'-0"


SCALE: 1/4"=1'-0"



DETAILED PLUMBING PLAN - MERCER BLDG.

SCALE: 1/4"=1'-0"

SCALE: 1/4"=1'-0"



C P2.03

REVISION T	ABLE:	
REV.	DESCRIPTION	DATE

FRESNO FIRE DEPARTMENT

11/15/2022 SCALE: As indicated JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379


FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

ENLARGED BASEMENT PLUMBING PLANS

SHEET NUMBER

P2.03

		·
	PLUMBING LEGEND	
SYMBOL	ITEM	ABBR
	SOIL or WASTE	S or W
	VENT	V
	VENT RISER	VR
	VENT THRU ROOF	VTR
	DOMESTIC COLD WATER	CW
	DOMESTIC HOT WATER	HW
	DOMESTIC HOT WATER RETURN	HWR
—-G—	LOW PRESSURE NATURAL GAS	G
<b>−</b> 5#G <b>−</b>	5 PSI GAS	5#G
<b></b> GSM	GAS SERVICE MAIN BY THE LOCAL GAS UTILITY	GSM
<u>—с—</u>	CONDENSATE DRAIN	CD
RWL	RAIN WATER LEADER	RWL
—OD—	OVERFLOW DRAIN	OD
—SD —	STORM DRAIN	SD
—/W —	INDIRECT WASTE	IW
F	FIRE PROTECTION LINE	F
	EXISTING PIPING	(E)
(E)	EXISTING	
(N)	NEW	
	ABOVE CEILING	ABV CLG
- April 1997	BELOW FLOOR	BEL FLR
	BELOW GRADE	BEL GR
	TYPICAL	TYP
	CONTINUATION	CONT
_	DOWN	DN
<u> </u>	FLOOR CLEANOUT	FCO
<u>-Ф-</u>	CLEANOUT TO GRADE	COTG
<u> </u>	WALL CLEANOUT	WCO
$\frac{\circ}{\circ}$	PIPING TURN UP	
<del></del>	PIPING TURN DOWN	
<del></del>	POINT OF CONNECTION	P.O.C
_ <u>~</u>	SHUT-OFF VALVE IN BOX	SOV
<del>\$</del> _	SHUT-OFF VALVE SHUT-OFF VALVE IN RISER	SOV
<del></del>	SHUT-OFF VALVE IN RISER	-
_ <u></u>	GATE VALVE	
<del>_</del> _	BUTTERFLY VALVE	
_ <del>_</del>	GLOBE VALVE	
<del>-</del>	CHECK VALVE	
$\neg \nabla \vdash$	PLUG VALVE	
-IOH	BALL VALVE	-
ーロー	BALANCE COCK	
$\overline{}$	REDUCER	-
$\overline{}$	MANHOLE	MH
	FLOW LINE	FL
	UNION	-
<b>A</b>	RELIEF VALVE	-
<u></u>	BALANCING VALVE	-
-	PRESSURE GAUGE	-
	THERMOMETER	
	10/0 1// 075	4144
-AW-	ACID WASTE	AW



# CONDENSATE DRAIN CONNECTION DETAIL

SCALE: NONE



APPROVED

03/17/2023

COUNTY OF FRESNO
DEVELOPMENT SERVICES

### PLUMBING FIXTURE SCHEDULE

WC-1

"KOHLER" K-84325 KINGSTON ULTRA, WALL MOUNTED ELONGATED WATER CLOSET, 1.28 GPF, "CHURCH" #295SSC OPEN-FRONT SEAT WITH CHECK STAINLESS STEEL HINGE POSTS AND FASTENERS AND SELF-SUSTAINING HINGES, LESS COVER, BOLT CAPS, "SLOAN ROYAL" #111-1.28 (OR #111-1.28-TP WITH TRAP PRIMER CONNECTION WHERE SHOWN ON DRAWINGS) MANUAL LEVER FLUSH VALVE, (1.28 GALLONS/FLUSH)., "JAY R. SMITH" SERIES #410 COMPACT VERTICAL SUPPORT CARRIER, SEE ARCHITECTURAL DRAWINGS FOR MOUNTING HEIGHTS, 1" C.W., 4" S., 2" V. WC-2

"KOHLER" #K-84325 KINGSON ULTRA, ACCESSIBLE WALL MOUNTED ELONGATED WATER CLOSET ,1.28 GPF, "CHURCH" #295SSC OPEN-FRONT SEAT WITH CHECK STAINLESS STEEL HINGE POSTS AND FASTENERS AND SELF-SUSTAINING HINGES, LESS COVER, BOLT CAPS, ""SLOAN ROYAL" #111-1.28 (OR #111-1.28-TP WITH TRAP PRIMER CONNECTION WHERE SHOWN ON DRAWINGS) MANUAL LEVER FLUSH VALVE WITH LEVER POINTING TOWARDS WIDE SIDE OF STALL, (1.28 GALLONS/FLUSH), "JAY R. SMITH" SERIES #410 COMPACT VERTICAL SUPPORT CARRIER, SEE ARCHITECTURAL DRAWINGS FOR ACCESSIBLE MOUNTING HEIGHTS, 1" C.W., 4" S., 2" V.

"KOHLER" #K-4991-ET BARDON, ACCESSIBLE WALL MOUNTED URINAL WITH STAINLESS STEEL STRAINER, "SLOAN ROYAL" #186-0.125-DBP MANUAL LEVER FLUSH VALVE, (0.125 GALLONS/FLUSH), "JAY R. SMITH" #637 SUPPORT CARRIER WITH BOTTOM PLATE FOR FLOOR AND WALL ATTACHMENT. SEE ARCHITECTURAL DRAWINGS FOR MOUNTING HEIGHTS, ACCESSIBLE MOUNTING HEIGHT SHALL BE 17" AFF TO LIP, 3/4" C.W., 2" S., 1-1/2" V., 2" W.C.O.

<u>L-1</u> "KOHLER" KINGSTON

#K-2005, ACCESSIBLE WALL HUNG VITREOUS CHINA LAVATORY, (20" X 18") WITH BACKSPLASH AND WALL BRACKET, 4" CENTER FAUCET HOLES, "MOEN" #8886 SELF CLOSING METERING FAUCET WITH 0.5 GPM LAMINAR FLOW OUTLET. ADJUST FAUCET TO STAY OPEN FOR 10-15 SECONDS. "WATTS" #LFUSG-B-M2 THERMOSTATIC MIXING VALVE WITH COLD WATER BYPASS, "MCGUIRE" 155WC OFFSET GRID DRAIN, "JAY R. SMITH" #700-Z FLOOR MOUNTED, CONCEALED ARM CARRIER. SEE ARCHITECTURAL DRAWINGS FOR ACCESSIBLE MOUNTING HEIGHTS, LOOSE KEY COMPRESSION ANGLED WALL STOPS WITH SUPPLY, 17 GA. C.P. P-TRAP/TAILPIECE WITH ESCUTCHEON, (WRAP C.W. AND TRAP/TAILPIECE PER SPECIFICATIONS), 1/2" H.W./C.W., 2" S., 1- 1/2"

"KOHLER" CAXTON RECTANGLE #K-20000, ACCESSIBLE UNDER COUNTER MOUNT VITREOUS CHINA LAVATORY WITH UNDER DECK MOUNTING CLAMPS,

#1281904-7 UNDER MOUNT TEMPLATE 4" CENTER FAUCET HOLES IN COUNTER, "MOEN" #8886 SELF CLOSING METERING FAUCET WITH 0.5 GPM LAMINAR FLOW OUTLET. ADJUST FAUCET TO STAY OPEN FOR 10-15 SECONDS, "WATTS" #LFUSG-B-M2 THERMOSTATIC MIXING VALVE WITH COLD WATER BYPASS, "MCGUIRE" 155WC OFFSET GRID DRAIN, (2) LOOSE KEY COMPRESSION ANGLED WALL STOPS WITH SUPPLIES, 17 GA. C.P. P-TRAP/TAILPIECE WITH ESCUTCHEON, (WRAP C.W., H.W. AND TRAP/TAILPIECE PER SPECIFICATIONS)1/2" H.W./C.W., 2" S., 1- 1/2" V.

"JUST" #SL-ADA-2119-A-GR, ACCESSIBLE COUNTER MOUNTED, 18 GAUGE TYPE 304 STAINLESS STEEL SINGLE BOWL HAND SINK, 16" X 16" X 6 ½" DEEP BOWL SIZE, WITH CENTER REAR DRAIN OUTLET, WITH "JUST" # J35-GS BASKET STRAINER, "CHICAGO" #201-AHA8AE35ABCP FAUCET WITH HIGH ARC SWING SPOUT, LEVER HANDLES, AND 1.5 GPM AERATOR, "WATTS" #LFUSG-B-M2 THERMOSTATIC MIXING VALVE WITH COLD WATER BYPASS,, (2) LOOSE KEY ANGLED WALL STOPS WITH SUPPLIES, 17 GA. C.P. TRAP/TAILPIECE WITH ESCHUTCHEON, (WRAP C.W., H.W. AND TRAP/TAILPIECE PER SPECIFICATIONS), 1/2" H.W./C.W., 2" W., 1-1/2" V., 2" W.C.O.

"JUST" # NSFB-372-24RL, THREE COMPARTMENT, FREE STANDING NSF SINK WITH DRAINBOARDS, 14 GAUGE TYPE 304 STAINLESS STEEL, 12" DEEP EACH BOWL SIZE, 12" HIGH BACKSPLASH, WITH 24" RIGHT AND LEFT DRAINBOARDS, THREE "JUST" #J-35-LAC-1-1/2 TWIST HANDLE DRAINS, TWO "CHICAGO" #445-L12E35ABCP BACKSPLASH MOUNT FAUCETS WITH 12" SPOUT AND LEVER HANDLES AND WITH 1.5 GPM AERATOR, (2) LOOSE KEY ANGLED WALL STOPS PER FAUCET, WITH SUPPLIES, (2) 1/2" H.W./C.W., 2" I.W.

"JUST" #SL-ADA-2125-A-GR, ACCESSIBLE COUNTER MOUNTED, 18 GAUGE TYPE 304 STAINLESS STEEL SINGLE BOWL PREP SINK, 16"X 25" X 6 ½" DEEP BOWL SIZE, WITH CENTER REAR DRAIN OUTLET, WITH "JUST" # J35-GS BASKET STRAINER, "CHICAGO" #201-AHA8AE35ABCP FAUCET WITH HIGH ARC SWING SPOUT, LEVER HANDLES, AND 1.5 GPM AERATOR, "WATTS" #LFUSG-B-M2 THERMOSTATIC MIXING VALVE WITH COLD WATER BYPASS,, (2) LOOSE KEY ANGLED WALL STOPS WITH SUPPLIES, 17 GA. C.P. TRAP/TAILPIECE WITH ESCHUTCHEON, (WRAP C.W., H.W. AND TRAP/TAILPIECE PER SPECIFICATIONS), 1/2" H.W./C.W., 2" W., 1-1/2" V., 2" W.C.O.

FLOOR MOUNTED ENAMELED CAST IRON 28" X 28" MOP SINK, "KOHLER" #K-6710 WHITBY, WITH #K-8940 RIM GUARD, AND #K-9146 GRID DRAIN, "CHICAGO" # 897-CP FAUCET WITH VACUUM BREAKER AND TOP BRACE, "FLORESTONE" #MR-0360 5 FT. HOSE WITH WALL BRACKET, AND "FLORESTONE" #MR-372 MOP HANGER, 3" P-TRAP, 3/4" H.W./C.W., 3" S., 2" V., 3" W.C.O.

ACCESSIBLE PRESSURE BALANCED SHOWER, "MOEN" #T8342EP15, SHOWER VALVE WITH LEVER HANDLE, DETACHABLE HAND-HELD SHOWERHEAD WITH 69" METAL HOSE, 30" WALL BAR, QUICK DISCONNECT AND IN-LINE VACUUM BREAKER, FIXED SHOWER HEAD, AND DIVERTER VALVE WITH LEVER HANDLE, 1.5 GPM FLOW, 1/2" H.W./C.W.

ACCESSIBLE IN-WALL MOUNT REFRIGERATED STAINLESS STEEL DUAL (HI-LO) DRINKING FOUNTAINS AND BOTTLE FILLING STATION, "ELKAY" #LZWS-LRPBM28K, WITH RECESSED CHILLER, MOUNTING FRAME, STAINLESS STEEL LOUVER, MECHANICAL PUSH ACTIVATED BUBBLERS, ELECTRONIC POWERED SENSOR BOTTLE FILLER STATION, AND WATER FILTER. PROVIDE ADDITIONAL 12 PACK BOTTLE FILLER WATER FILTERS (#51300C-12PK). UNIT REQUIRES 120V, 1.0 FLA, 370 WATTS ELECTRICAL POWER. (1) SERVICE STOP, (2) 17 GA. C.P. TRAP/TAILPIECE, 1/2" C.W., 2" S., 1-1/2" V. OPERATING WEIGHT = 173 LBS.

RECESSED METAL WATER SUPPLY BOX WITH WHITE FINISH, INTEGRAL SHUTOFF VALVE, AND MINI WATER HAMMER ARRESTOR, "SPECIALTY PRODUCTS" #0B-509.

EVERPURE "INSURICE SINGLE i2000" MODEL #EV9324-01 ICE MACHINE WATER FILTER SYSTEM WITH #EV9612-22 0.5 MICRON CARTRIDGE (PROVIDE TWO ADDITIONAL #EV9612-22 REPLACEMENT CARTRIDGES), 1.67 GPM MAXIMUM FLOW RATE, 9,000 GALLONS RATED CAPACITY, WALL MOUNTING BRACKET, OVERALL DIMENSIONS: 29.64" HIGH X 8.04" WIDE X 5.25" DEEP. WEIGHT = 9 LBS.

FD-1 CAST IRON FLOOR DRAIN, "JAY.R. SMITH" # 2005Y02-P050-HP-NB, WITH 5" DIAMETER NICKEL BRONZE HEEL-PROOF GRATE (OR 2005-B WITH SQUARE GRATE SEE PLANS), 1/2" TRAP PRIMER CONNECTION, 2" S., 2" P-TRAP AND 1-1/2" V. BELOW SLAB.

CAST IRON FLOOR SINK, "JAY.R. SMITH" #3140Y02-12, (12-1/2" X 12-1/2" X 6" DEEP) WITH ACID RESISTANT COATED INTERIOR, FLASHING CLAMP, NICKEL BRONZE RIM AND HALF GRATE, # 2697 AUXILLARY TRAP PRIMER CONNECTION, 1/2" C.W., 2" S., 2" P-TRAP AND 1-1/2" V BELOW SLAB. FS-2

CAST IRON FLOOR SINK, "JAY.R. SMITH" #310Y04-12, (12-1/2" X 12-1/2" X 10" DEEP) WITH ACID RESISTANT COATED INTERIOR, FLASHING CLAMP, NICKEL BRONZE RIM AND HALF GRATE, # 2697 AUXILLARY TRAP PRIMER CONNECTION, 1/2" C.W., 4" S., 2" P-TRAP AND 2" V BELOW SLAB. HR-1

WALL MOUNTED BENT NOSE ROUGH CHROME PLATED BRASS LOOSE TEE KEY HOSE BIBB, "WOODFORD" # 24P WITH INTEGRAL VACUUM BREAKER, 3/4" C.W.

TRAP PRIMER IN WALL ACCESS DOOR, "PRECISION PLUMBING PRODUCTS"

#PR-500 WITH #DIJ4/DIJJI DISTRIBUTION UNIT AS REQUIRED FOR MULTIPLE T

#PR-500 WITH #DU-4/DU-U DISTRIBUTION UNIT AS REQUIRED FOR MULTIPLE TRAPS, AND 12" X 12" STAINLESS STEEL ACCESS DOOR WITH CYLINDER LOCK, 1/2" C.W. W/ BALL VALVE TO PRIMER INLET.


TP-2

ELECTRONIC TRAP PRIMER IN WALL WITH ACCESS DOOR, "PRECISION PLUMBING PRODUCTS" #MPB-500 WITH BOX AND "PPP" #D-814SS STAINLESS STEEL ACCESS DOOR, SOLENOID VALVE ACTIVATED, 120V/1ø.

SEAMLESS COPPER CHAMBER APPROVED FOR CONCEALED INSTALLATIONS, "SIOUX CHIEF" HYDRA-RESTER MODELS 653-AS (PDI B) OR 654-AS (PDI C) SIZED AS REQUIRED.

SINK BOWL MOUNT WITH SINK ADAPTOR, CONTINUOUS FEED FOOD WASTE DISPOSER, "IN-SINK-ERATOR" PRO SERIES COMPACT, WITH STAINLESS STEEL GRINDING ELEMENTS, SOUNDSEAL TECHNOLOGY, 3/4 HP. MOTOR, 120V/1 PH., 4 YEAR WARRANTY.






URATORE ASSOCIATES

1222 M SHAW AVE.
FRESNO, CA 49711

CONSULTANT STAMP





**APPROVED** 

AUG 2 9 2024 9

FRESNO FIRE DEPARTMENT

REV.	DESCRIPTION	DAT

DATE: 11/15/2022

SCALE: As indicated

JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379
PROJECT:

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:

PLUMBING SCHEDULES AND DETAILS

CUEET NUMBE

P3.01

INTERNAL NUMBER: 829

ä

### **GRILLE SCHEDULE**

Titus Model MCD modular core diffuser with adjustable throw pattern for T-bar ceiling mounting. Complete with OBD, round-to-square neck adapter & off-white finish. Adapter shall match inlet duct diameter unless otherwise shown. With the following round ducts, provide adapter as shown.

8" Round to 12" x 12" neck 10" Round to 12" x 12" neck 12" Round to 12" x 12" neck

When the S.A. duct is 9" diameter, provide 9" to 10" increaser at neck of grille and use the 10" Round to 12" x 12" neck.

Titus Model MCD modular core diffuser with adjustable throw pattern for surface mounting. All else per CD-1, above. See plans for throw pattern and neck size. Contractor to provide round-to-square adapter when required. Face size shall be only large enough to accommodate specified neck size.

Titus Model TDC louver faced diffuser for surface mounting. Complete with OBD, round neck & off-white finish. See plans for throw pattern and neck size. Face size shall be only large enough to accommodate specified neck size.

# CR-1 & CE-1

Titus Model 50F aluminum eggcrate grille with 1/2" x 1/2" x 1/2" eggcrate core and off-white finish for mounting in T-bar ceiling. Size shall be 24"x24", 48"x24", or 24"x12" as shown on the plans.

# CR-2 & CE-2

Titus Model 350RL steel grille with 3/4" blades at 35-degree deflection, off-white finish for mounting in T-bar ceiling. Nominal size shall be 24"x24", 48"x24", or 24"x12" as shown on the plans.

# CR-3, CE-3, & WR-1

blades and off-white finish.

Titus Model 350RL steel grille with 3/4" blades at 35-degree deflection, off-white finish for surface mounting.

Titus Model 3FFL aluminum aeroblade filter-return grille with 3/4"

45-degree deflection, and off-white finish for mounting in nominal 24"x24" T-bar ceiling. Provide (1) 20"x 20"x2" Camfil AP-13 (MERV13) filter with each grille.

# Titus Model 272RS steel wall supply grille with 3/4" double deflection

Notes:

1. Paint all exposed shiny surfaces, behind grille face, flat black.

DESIGNATION	ODU-1, ODU-2	ODU-3		
COOLING CAPACITY (MBH)	228 (SEE NOTE1)	69 (SEE NOTE 1)		
HEATING CAPACITY (MBH)	256 (SEE NOTE 2)	77 (SEE NOTE 2)		
VOLTS/PHASE	460/3	460/3		
RLA	26 AMPS	9.4 AMPS		
MCA / MOP	34 / 40	19/25		
EER / IEER (AT ARI)	N.A.	13.9 / 21.3		
HEATING COP	N.A.	3.7		
REFRIG. LINE SIZE	SEE SHEET M-11.1	SEE SHEET M-11.1		
GAS (IN. OD)	1-3/8	3/4		
LIQUID (IN. OD)	5/8	3/8		
H/L LIQUID (IN. OD)	1-1/8	5/8		
REFRIGERANT	R410A	R410A		
MANUFACTURER	DAIKIN	DAIKIN		
TYPE	ROTARY INVERTER	ROTARY INVERTER		
MODEL NUMBER	REYQ240AAYDA	REYQ72XAYDA		
AREA SERVED	BRIX BASEMENT	BRIX BASEMENT		
LOCATION	MERCER BUILDING ROOF	MERCER BUILDING ROOF		
OPER. WT (LBS)	1,000	750		
ACCESSORIES				

# NOTES:

- 1. COOLING CAPACITY IS AT 80/67 INDOORS AND 95/75 OUTDOORS.
- 2. HEATING CAPACITY IS AT 70/60 INDOORS AND 47/43 OUTDOORS.

	NOMINAL	MODEL			BLOWER					COOLING CAPACITY		HEATING		
UNIT	TONS	NUMBER	SUPPL	Y AIR	EXT. S P.	MCA	MOCP	FLA	VOLTS/PHASE	TOTAL	SENSIBLE	CAPACITY	OPER. WT.	ACCESSORIES
TYPE		(See Note 1)	MAX CFM	MIN CFM	IN. WC	AMPS	AMPS	AMPS		MBH	МВН	MBH	(LBS)	& NOTES
DHS	4.5	FXMQ54PBVJU	1600	1125	0.40	3.4	15	2.7	208/1	54.00	40.30	60.00	110	2, 3
DHS	4.0	FXMQ48PBVJU	1375	975	0.00	3.4	15	2.7	208/1	48.0	35.8	54.0	110	2, 3
DHS	3.0	FXMQ36PBVJU	1125	800	0.00	2.9	15	2.3	208/1	36.0	28.8	40.0	110	2, 3
DHS	2.0	FXMQ24PBVJU	675	575	0.00	1.8	15	1.4	208/1	24.0	15.6	27.0	90	2, 3
DHS	1.5	FXMQ18PBVJU	625	525	0.00	1.6	15	1.3	208/1	18.0	14.4	20.0	90	2, 3
DHS	1.0	FXMQ12PBVJU	450	400	0.60	1.4	15	1.1	208/1	12.0	9.7	13.5	75	2, 3
HSW	2.0	FXAQ24PVJU	625	470	0	0.6	15	0.50	208/1	24.0	18.0	26.5	40	3, 4
HSW	1.5	FXAQ18PVJU	500	400	0	0.5	15	0.40	208/1	18.0	13.5	20.0	40	3, 4
HSW	0.9	FXAQ09PVJU	280	175	0	0.4	15	0.30	208/1	9.5	7.1	10.5	30	3, 4
CC	1.5	FXZQ18MVJU9	495	350	0	0.9	15	0.70	208/1	18.0	13.5	21.0	50	2, 3

3. Cooling capacities rated at 95/75 (db/wb) ambient and 80/67 indoor. Heating capacities rated at 47/43 ambient and 70 indoor. Heating and cooling capacities include indoor fan heat... 4. Provide with external condensate pump and 72" of lift.

Zone		IDU	Nominal	Supply	O.A.	Filters	
Fan Coils	Room Number(s)	Туре	Tons of A/C	CFM	CFM	2" - Merv 13	Notes
IDU / B-1	Caged Storage - Southeast	DHS	3.0	1100	250	(2) 25" x 20"	
100 / 0-1		DIIO	3.0	1100	250	(2) 20 × 20	1
IDU / B-2	Caged Storage - Center	DHS	3.0	1100		(4) 24" x 12"	1
IDU / B-3	Caged Storage - Northwest	DHS	3.0	1100	250	(4) 24" x 12"	1
.20,20		Billo	3.0	1100	230	(,, = , , , , =	
IDU / B-4	Ground Floor Lobby - Southeast	DHS	4.5	1350	300	(4) 24" x 12"	1
IDU / B-5	Ground Floor Lobby - Northwest	DHS	4.5	1350	300	(4) 24" x 12"	1
	D D (11 11						
IDU / B-6	Prep Room / Hall	DHS	2.0	650	200	At filter/return grille	
IDU / B-7	Media Room B0302	DHS	2.0	650	250	At filter/return grille	
IDII / D O	Madia Danas Boood	5110				A	
IDU / B-8	Media Room B0301	DHS	2.0	650	425	At filter/return grille	
IDU / B-9	Conference B0204	DHS	2.0	650	250	At filter/return grille	
IDU / B-10	Conference B0211	DHS	1.5	550	200	At filter/return grille	
100 / 6-10	Conference B0211	DHS	1.5	550	200	At interreturn grille	
IDU / B-11	Conference B0203	DHS	1.5	550	200	At filter/return grille	
IDU / B-12	Office / Lounge / Hall	DHS	4.0	1350	550	At filter/return grille	
100 / 0-12		DIIS	4.0	1350	550	7 te intervietarii grine	
IDU / B-13	Men's and Women's Toilet Rooms	DHS	2.0	650		At filter/return grille	
IDU / B-14	Break Room #4	DHS	2.0	650	225	At filter/return grille	6
IDU / B-15	Break Room #3	DHS	2.0	650	225	At filter/return grille	6
IDU / B-16	Break Room #2	DHS	2.0	650	225	At filter/return grille	6
	D. Kitch						
IDU / B-17	Prep Kitchen	CC	1.5	350		See Notes	4, 5
IDU / B-18	Break Room w/ Aud. Seating	HSW	1.5	400	225	See Notes	4, 5, 6, 7
IDU / B-19	Moreor Network Room M0100	LICIA	0.0	005		O Note-	4.5.7
100 / 6-19	Mercer Network Room M0108	HSW	2.0	625		See Notes	4, 5, 7
IDU / B-20	Vestibule & Electrical Room B0106	DHS	2.0	650	100	(1) 25" x 16"	1
IDU / B-21	Hall B0210	HSW	0.75	275		See Notes	4, 5, 7
		11000	5.76	210		OSC NOLCS	7, 0, 7
IDU / B-22	Vestibule B0101	DHS	2.0	650	100	(1) 25" x 16"	1
	Total		50.8		4275	At EF/B-7 Low Speed	
		1	30.0		7210	A4 FF/D 7 LL'-1- O	

SHEE I	INDEX						
M-1.0	SCHEDULES						
M-1.1	SCHEDULES						
M-2.0	BASEMENT HVAC DEMO PLAN						
M-2.1	1 BASEMENT MECH ROOM - DEMO AND NEW						
M-3	PARTIAL ROOF PLAN						
M-4.0	DETAILS AND KEYNOTES FOR M-4.3 & M-4.4						
M-4.1	BASEMENT HVAC PLAN - MERCER NORTHEAST						
M-4.2	BASEMENT HVAC PLAN - MERCER SOUTHHEAST						
M-4.3 BASEMENT HVAC PLAN - BRIX SOUTHWEST							
M-4.4 BASEMENT HVAC PLAN - BRIX NORTHWEST							
M-5 HOOD EXHAUST SECTIONS							
M-6	SECTIONS						
M-7	DETAILS						
M-8	DETAILS						
M-9	KITCHEN HOOD EXHAUST DETAILS						
M-10	CONTROL DIAGRAMS						
M-11.1	VRF PIPING DIAGRAMS						
M-11.2	VRF WIRING DIAGRAMS						
M-12.1	TITLE 24						
M-12.2	TITLE 24						
M-12.3	TITLE 24						
M-12.4	TITLE 24						
M-15	FIRE ALARM - HVAC FANS AND FSDS						

				SI	NGLE DU	CIVA	KIABL	E VOL	UME II	ERMINA	AL SCI	HEDUL	.E											
Tag	AHU	Room	Model		Size	С	FM	St	atic Press	sure	NC I	_evels	T				Hot W	later Hea	at Coil					Wei
	Tag			Unit	Outlet	Max	Min	Inlet	Down	Min	Rad	Dis	CFM	МВН	EAT	EWT	LAT	APd	GPM	LWT	WPd	Rows	FPI	LI
RCER ZONE COI	NTROL																	-	-				-	
				1					1				-			-		1	1				+	
VAV / B-1	AH / B-2	Staff T.R.s and Storage	DESV	10	14x12.5	700	600	1	0.25	0.17	22	27	600	21.0	55	170	87.2	0.16	1.1	130.4	0.14	2	10	
VAV / B-2	AH / B-2	Toilet Rooms - M0105 and M0106	DESV	09	14x12.5	400	300	1	0.25	0.04	14	18	300	11.0	55	170	88.8	_	1.6	155.5	0.26	1	10	
VAV / B-3	AH / B-2	Hall - M0102	DESV	09	14x12.5	400	150	1	0.25	0.04	14	18	200	7.5	55	170	89.5	-	0.7	147.2	0.08	1	10	
		Total for AH / B-2				1500															0.00			
VAV / B-4	AH / B-1	Meeting Room - East Zone	DESV	14	20x17.5	1400	450	1	0.25	0.1	20	20	700	25.2	55	170	88.2	0.08	4.3	158.1	0.93	1	10	7
VAV / B-5	AH / B-1	Meeting Room - Middle Zone	DESV	14	20x17.5	-	450	1	0.25	0.1	20	20	700	25.2	55	170	88.2			158.1	0.93	1	10	-
VAV / B-6	AH / B-1	Meeting Room - West Zone	DESV	14	20x17.5	-	450	1	0.25	0.1	20	20	700	25.2	55	170	88.2	-	-	158.1	0.93	1	10	
		Total for AH / B-1				4200								20.2		1.0	00.2	0.00	7.0	100.1	0.00		10	
VAV / B-7	AH / B-4	Storage Room - M0203	DESV	10	14x12.5	550	200	1	0.25	0.06	22	23	300	11.2	55	170	89.4	0.05	1.8	157.1	0.33	1	10	
VAV / B-8	AH / B-4	Prepared Food Holding	DESV	10	14x12.5	550	175	1	0.25	0.06	22	23	300	11.2	55	170	89.4		1.8		0.33	1	10	
VAV / B-9	AH / B-4	Breakout Room	DESV	10	14x12.5	300	100	1	0.25	0.03	19	18	150	5.3	55	170	95.2	0.03	-	149.6	0.08	1	10	
VAV / B-10	AH / B-4	Hall, Storage, and Lobby	DESV	14	20x17.5		500	1	0.25	0.1	20	20	700	25.2	55	170	88.2	_		158.1	0.93	1	10	
		Total for AH / B-4				2700								20.2			00.2	0.00	1.0	100.1	0.00		10	
X GROUND FLO	OR ZONE CON	NTROL																-						
VAV / B-11	AHU-2	4 SE Offices on Ground Floor	DESV	10	14x12.5	480	175	1	0.25	0.06	20	23	250	9.3	55	170	89.3	0.05	1	150.6	0.13	1	10	
VAV / B-12	AHU-2	3 SE Offices on Ground Floor	DESV	09	14x12.5	420	140	1	0.25	0.05	14	18	210	7.4	55	170	88.3	0.08	-		0.08	1	10	
VAV / B-13	AHU-2	7 NW Offices on Ground Floor	DESV	12	16x15	880	300	1	0.25	0.08	19	23	450	17.0	55	170	89.8	-	3.5		1.5	1	10	-
VAV / B-14	AHU-2	5 NW Offices on Ground Floor	DESV	10	14x12.5	500	175	1	0.25	0.06	20	23	250	9.3	55	170	89.3	0.05	1	150.6	0.13	1	10	
		Partial Airflow from AHU-2				2280												0.00	·	100.0	0.10			
X MINIMUM OUT	DOOR AIR CO	ONTROL																						
													1					+					+	-
VAV / B-15	AH-B5	Open Space (South) and IDU/B-4	DESV	09	14x12.5	550	550	1	0.25	0.02	17	23	N.A.					-					+	
VAV / B-16	AH-B5	Open Space (North) and IDU/B-5	DESV	12	16x15	1000	1000	1	0.25	0.01	22	24	N.A.					1						
VAV / B-17	AH-B5	Break Room - East	DESV	09	14x12.5	625	225	1	0.25	0.02	18	24	N.A.										<del></del>	
VAV / B-18	AH-B5	Break Room - East Middle	DESV	09	14x12.5	625	225	1	0.25	0.02	18	24	N.A.											
VAV / B-19	AH-B5	Break Room - West Middle	DESV	09	14x12.5	625	225	1	0.25	0.02	18	24	N.A.											
VAV / B-20	AH-B5	Break Room - West	DESV	09	14x12.5	625	225	1	0.25	0.02	18	24	N.A.											
VAV / B-21	AH-B5	Office/Lounge to IDU/B-12	DESV	09	14x12.5	550	550	1	0.25	0.02	17	23	N.A.					+			-			

- Selections are based on Titus as Manufacturer. . All performance based on tests conducted in accordance with ASHRAE 130-2008 and AHRI 880-2008.
- 3. All NC levels determined using AHRI 885-2008 Appendix E.
- 4. All airflow, pressure losses and heating performance values have been corrected for altitude.

5. Units of measure: dimensions (in), airflow (cfm), water flow (gpm), air pressure (in wg), water head losses (ft) and temperatures (degF). 6. Water pressure drop (WPd) units is in ft. water.

REFRIGERANT SYSTEM BR	ANCH SELECTOR	BOX SCHEDULE					
DESIGNATION	BSB / B-1	BSB / B-2	BSB / B-3	BSB / B-4	BSB / B-5	BSB / B-6	BSB / B-7
BRANCH PORTS (TOTAL / USED)	6/4	6/4	1/1	4/4	4/2	4/3	4/3
POWER INPUT (W)	64	64	10	50	50	50	50
VOLTS/PHASE	208/1	208/1	208/1	208/1	208/1	208/1	208/1
MCA	0.50	0.50	0.10	0.40	0.40	0.40	0.40
MOCP	15	15	15	15	15	15	15
DDU ASSIGNMENT	ODU-1	ODU-1	ODU-1	ODU-2	ODU-2	ODU-2	ODU-3
MANUFACTURER	DAIKIN	DAIKIN	DAIKIN	DAIKIN	DAIKIN	DAIKIN	DAIKIN
YPE	MAIN	MAIN	MAIN	MAIN	MAIN	MAIN	MAIN
MODEL NUMBER	BSF6Q54TVJ	BSF6Q54TVJ	BSQ36TVJ	BSF4Q54TVJ	BSF4Q54TVJ	BSF4Q54TVJ	BSF4Q54TVJ
OPER. WT (LBS)	50	50	30	50	50	50	50
ACCESSORIES	1, 2	1, 2	1	1, 2, 3	1, 2	1, 2	1, 2

5875 At EF/B-7 High Speed

1. PROVIDE WITH BC-SERIES BALL VALVES FOR EACH BRANCH OUTLET CONNECTION.

2. PROVIDE WITH BC-SERIES BALL VALVES FOR UNUSED OUTLET CONNECTION.

1. Filters at unit require a shop fabricated filter box on the inlet of the unit. Filters shall be side and/or bottom access.

6. Outdoor Air CFM shown is with EF/B-7 on Low Speed. O.A. to Zone = 625 CFM when EF/B-7 is on High Speed.

2. Match Cooling Tons in this schedule with Indoor Unit Schedule for additional fan coil information.

5. When the manufacturer's standard filter is used, MERV rating is less than 13 and the filter is 1" thick.

3. Unit type: DHS = Ducted High Static, HSW = High Sidewall, CC = 4-way Ceiling Cassette.


4. HWS and CC units use the manufacturer's standard washable filter.

. Refer to Detail F/M-8 for remote condensate pump and field wiring.

3. ONE OUTLET SERVES TWO IDUS.

**APPROVED** 03/17/2023 COUNTY OF FRESNO DEVELOPMENT SERVICES





CONSULTANT STAMP



7084 N. Maple Ave., Suite 101 Fresno, CA 93720 (559) 431-0101 **21003** FAX (559) 431-1362

FRESNO FIRE DEPARTMENT

	REVISION	TABLE:	
	REV.	DESCRIPTION	DATE
	_		
	-		
١			
I			
1	THE REAL PROPERTY AND ADDRESS OF THE PARTY O		COLUMN TWO IS NOT THE OWNER, THE

11/15/2022 As indicated JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #:

21-1137 21-105379

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:

SCHEDULES

SHEET NUMBER

	AIR CONDITIONING LEGEND	
SYMBOL	ITEM	ABBR.
$\leftarrow$	ROUND METAL DUCT	_
<b>//////</b>	ROUND FLEXIBLE DUCT	_
	RECTANGULAR METAL DUCT	_
	DUCT W/ACOUSTIC LINING	_
	SUPPLY AIR DUCT DROP	_
	RETURN AIR DUCT DROP	
	EXHAUST DUCT AIR DROP	_
	SUPPLY AIR DUCT RISE	
	RETURN AIR DUCT RISE	
	EXHAUST AIR DUCT RISE	_
	TURNING VANES	TV
	EXTRACTOR	_
	VOLUME CONTROL DAMPER w/LOCKING QUADRANT	VCD
p	VOLUME CONTROL DAMPER w/REMOTE OPERATOR	VCD
<del>∨∨∨</del> -or- □	FIRE/SMOKE DAMPER WITH ACCESS PANEL	F/SD
<del>\ \ \ \ \ \</del>	SMOKE DAMPER	SD
CFM	CUBIC FEET OF AIR PER MINUTE	CFM
Ŧ	THERMOSTAT @ +4'-0"	T'STAT
<u> </u>	ROOM SENSOR @ 4'-0"	_
	DIRECTION OF FLOW	
h	SUPPLY AIR	SA
	RETURN AIR	RA RA
h .		
<u></u>	EXHAUST AIR	EA
	OUTSIDE AIR	OA
-	PIPE/DUCT TURN DOWN	
-	THE DOCT TORN DOWN	_
-	PIPE/DUCT TURN UP	_
		— — ВРТ
	PIPE/DUCT TURN UP	- BPT POC
	PIPE/DUCT TURN UP BYPASS TIMER	POC
	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)	
—X —X —7—	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING	POC
—————————————————————————————————————	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING	POC (E)
—————————————————————————————————————	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY	POC (E) HWS
—————————————————————————————————————	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN	POC (E) HWS
—————————————————————————————————————	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY	POC (E) HWS
—————————————————————————————————————	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN	POC (E) HWS
—————————————————————————————————————	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY	POC (E)  HWS HWR CWS
—————————————————————————————————————	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER RETURN	POC (E)  HWS HWR CWS CWR
—————————————————————————————————————	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER RETURN  BACKDRAFT DAMPER	POC (E)  HWS HWR CWS CWR BDD
— X — T — — HWS — — HWR — — CWS — — CWR — — HHHH	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN	POC (E)  HWS HWR CWS CWR BDD
— X — X — T — — E — — HWS — — HWR — — CWS — — CWR — — HHHH — D — — RD — — RL —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT LIQUID	POC (E)  HWS HWR CWS CWR BDD D RD RL
— X — X — T — — HWS — — HWR — — CWS — — CWR — — HHHH — D — — RD — — RS —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION	POC (E)  HWS HWR CWS CWR BDD D RD
— X — T — — HWS — — HWR — — CWS — — CWR — — HHHH — D — — RD — — RS — — RS — — H□ —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK	POC (E)  HWS HWR CWS CWR BDD D RD RL
— X — T — — T — — HWS — — HWR — — CWS — — CWR — — HHHH — D — — RD — — RL — — RS — — I□	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE	POC (E)  HWS HWR CWS CWR BDD D RD RL
— X — T — — HWS — — HWR — — CWS — — CWR — — HHHH — D — — RD — — RS — — RS — — H□ —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE	POC (E)  HWS HWR CWS CWR BDD D RD RL
— X — T — — T — — HWS — — HWR — — CWS — — CWR — — HHHH — D — — RD — — RL — — RS — — I□	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE	POC (E)  HWS HWR CWS CWR BDD D RD RL
— X — T — — T — — HWS — — HWR — — CWS — — CWR — — HHHH — D — — RD — — RL — — RS — —   □   — — I □   — — I □   — — I □   —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE	POC (E)  HWS HWR CWS CWR BDD D RD RL
— X — — — — — — — — — — — — — — — — — —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE  CHECK VALVE	POC (E)  HWS HWR CWS CWR BDD D RD RL
— X — — — — — — — — — — — — — — — — — —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE  CHECK VALVE  GATE VALVE	POC (E)  HWS HWR CWS CWR BDD D RD RL
— X — — — — — — — — — — — — — — — — — —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE  CHECK VALVE  PLUG VALVE	POC (E)  HWS HWR CWS CWR BDD D RD RL RS
—	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE  CHECK VALVE  PLUG VALVE  PRESSURE RELIEF VALVE  UNION	POC (E)  HWS HWR CWS CWR BDD D RD RL RS
—	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE  CHECK VALVE  PLUG VALVE  PRESSURE RELIEF VALVE  UNION  INSTRUMENT WELL	POC (E)  HWS HWR CWS CWR BDD D RD RL RS
—	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE  CHECK VALVE  PLUG VALVE  PRESSURE RELIEF VALVE  UNION  INSTRUMENT WELL  FLOW SWITCH	POC (E)  HWS HWR CWS CWR BDD D RD RL RS
— X — T — HWS — HWR — CWS — CWR — HHHH — RD — RL — PS — D — D — D — D — D — D — D — D — D —	PIPE/DUCT TURN UP  BYPASS TIMER  POINT OF CONNECTION  EXISTING (DESIGNATED)  THERMOSTAT WIRING  ELECTRICAL WIRING  HOT WATER SUPPLY  HOT WATER RETURN  CHILLED WATER SUPPLY  CHILLED WATER RETURN  BACKDRAFT DAMPER  DRAIN  REFRIGERANT DISCHARGE  REFRIGERANT SUCTION  BALANCING COCK  BALL VALVE  BUTTERFLY VALVE  CHECK VALVE  PLUG VALVE  PRESSURE RELIEF VALVE  UNION  INSTRUMENT WELL	POC (E)  HWS HWR CWS CWR BDD D RD RL RS

DESIGNATION	AH / B-1	AH / B-2	AH / B-3	AH / B-4	AH / B-5
SUPPLY FAN					
SUPPLY AIR FLOW (CFM)	4,200	3,300	1,600	3150 (2700 Now)	7.000
EXTERNAL SP (IN. WC.)	3.00	1.25	3.00	3.00	3.00
TOTAL SP (IN. WC)	3.71	2.3	3.84	3.61	0.00
OCCUPIED MIN. O.A. (CFM)	SEE NOTE 4, UP TO 1800	SEE NOTE , UP TO 1000	1,000	1,000	7000 (ALL OUTDOOR AIR)
UNOCCUPIED MIN. O.A. (CFM)	600	300	1000	.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
MOTOR HP	7.5	5	3	5	10
TOTAL OPERATING BHP	4.5	2.7	1.7	2.9	8.8
VOLTS/PHASE	460/3	460 / 3	460/3	460 / 3	460 / 3
RPM	3248	1611	1904	2785	3480
FAN TYPE/DIA.	AIRFOIL / 13.2	FORWARD CURVED / 10.62	FORWARD CURVED / 10.62	AIRFOIL / 13.2	AIRFOIL / 14.5
ISOLATOR DFLEC (IN.)	2	2	2	2	2
CONNECTION	TOP	TOP	TOP	TOP	FRONT
COOLING COIL	11.0	8.5	5.9	8.6	26.8
TOTAL (MBH)	131.9	101.6	70.7	103.3	321.5
SENSIBLE (MBH)	115.7	89.8	64.6	92.9	321.5
MINIMUM COIL SIZE (FT.2)	11.2	7.50	5.69	7.50	17.00
AIR PD (IN. WC)	0.48	0.73	0.28	0.39	0.34
EADB/EAWB (°F)	80.0 / 64	78 / 63	92/68	83 / 65	
LAT (DB/WB)	54.8 / 53.3	53.1 / 52.3			105/70
	6/6	53.1752.3	55.1 / 53.6	56.0 / 54.0	63.0 / 55.6
ROWS / FINS PER INCH GPM / PD (FT.)	24.9 / 6.2	20 / 5.4	4/10	5/9	3 / 10
<i>EWT</i> (°F)			13.8 / 2.6	20.7 / 5.8	64.3 / 9.3
	45	45	45	45	45
BRANCH SIZE (IN.)	1.5	1.5	1.5	1.5	(2) 1.5
VALVE TYPE	2-WAY	2-WAY	2-WAY	2-WAY	2-WAY
HEATING COIL					
CAPACITY (MBH)	141.9	113	80	98.7	401.9
MINIMUM COIL SIZE (FT.2)	10.54	7.0	5.25	7.0	16.0
AIR PD (IN. WC)	0.10	0.14	0.07	0.09	0.25
EADB (°F)	60	60	45	60	25
LAT (DB)	91	91.3	91	88.7	77.5
ROWS / FINS PER INCH	1/8	1/9	1/10	1/10	2/10
GPM/PD (FT.)	13.8 / 3.5	10.8 / 3.3	7.9/2.0	10.3 / 2.7	38.3 / 1.1
EWT (°F)	170	170	170	170	170
BRANCH SIZE (IN.)	1.5	1.5	1.5	1.5	
VALVE TYPE	2-WAY	2-WAY	2-WAY	2-WAY	2-WAY
FILTER/MIXING BOX					
AREA (SQ. FT.) OR	(6) 0011 - 0011 - 011	(0) 0.411 0.411 0.11	(0) 00# - 00# - 0#	(0) 00# 00# 0"	(0) 00""
FILTER / QUAN. SIZE	(6) 20" x 20" x 2"	(2) 24" x 24" x 2"	(6) 20" x 20" x 2"	(6) 20" x 20" x 2"	(9) 20" x 20" x 2"
TYPE	MERV 13	MERV 13	MERV 13	MERV 13	MERV 13
FINAL PD (IN WC)	0.6	0.6	0.6	0.6	0.6
MANUFACTURER	DAIKIN VISION	DAIKIN VISION	DAIKIN VISION	DAIKIN VISION	DAIKIN VISION
TYPE	INDOOR	INDOOR	INDOOR	INDOOR	INDOOR
MODEL NUMBER	CAH012GDAM	CAH008GDAC	CAH006GDAC	CAH008GDAC	CAH019GDAM
AREA SERVED	MEETING ROOMS	ACTIVITY AREA	NORTHWEST TOILET, SHOWER,	LOBBY, COFFEE	BRIX BASEMENT
			AND VESTIBULES	AND STORAGE ROOMS	
AIR HANDLER LOCATION	MERCER BASEMENT	MERCER BASEMENT	MERCER BASEMENT	MERCER BASEMENT	BRIX MECHANICAL ROOM
OPER. WT (LBS)	1,700	1,600	1,300	1,600	2,400
ACCESSORIES	1, 2	1, 2	1, 2	1, 2, 6	1, 2, 3, 5

- 1. DOUBLE WALL CONSTRUCTION WITH R-13 INJECTED FOAM INSULATION, INVERTER DUTY MOTORS ON SUPPLY FAN(S), AND 6" HIGH BASE RAIL.
- 2. REFER TO SECTIONS FOR FILTER SIZE AND QUANTITY.
- 3. (2) STACKED HEATING COILS AND (2) STACKED COOLING COILS.
- 4. DETERMINED BY CO2 SENSOR.
- 5. SUPPLY AIR CFM SHOWN IS FOR AIR HANDLER SELECTION PURPOSES. FOR ACTUAL AIRFLOW, SEE VRF FAN COIL SCHEDULE, SHEET M-1.0.
- 6. SELECT AH AT 3150 CFM SHOWN, BUT ADJUST TO 2700 CFM NOW.

		Damper Positon During	Damper Position Whe
Damper I.D.	Duty	Normal Operation	with Smoke Detected
FSD B- 1	S.A. to Mercer Meeting Rooms	OPEN	Close
FSD B- 2	R.A. from Mercer Meeting Rooms	OPEN	Close
FSD B- 3	O.A. to AH / B-1	OPEN	Close
FSD B- 4	R.A. to AH / B-4	OPEN	Close
FSD B- 5	E.A. duct from Equipment and Food Storage Room	OPEN	Close
FSD B- 6	R.A. from Storage and Breakout Room	OPEN	Close
FSD B- 7	R.A. from Hall	OPEN	Close
FSD B- 21	South S.A. riser off IDU / B-4 to Mercer Lobby floor grille	OPEN	Close
FSD B- 22	North S.A. riser off IDU / B-4 to Mercer Lobby floor grille	OPEN	Close
FSD B- 23	South S.A. riser off IDU / B-5 to Mercer Lobby floor grille	OPEN	Close
FSD B- 24	North S.A. riser off IDU / B-5 to Mercer Lobby floor grille	OPEN	Close
FSD B- 25	S.A. from AHU-2 to VAV / B-16	OPEN	Close
FSD B- 26	S.A. from VAV / B-14 through east wall of Breakroom	OPEN	Close
FSD B- 27	S.A. from VAV / B-14 to S.A. plenum and risers to Ground Floor	OPEN	Close
FSD B- 28	S.A. from VAV / B-12 to S.A. plenum and risers to Ground Floor	OPEN	Close
FSD B- 29	S.A. from VAV / B-11 to S.A. plenum and risers to Ground Floor	OPEN	Close
FSD B- 30	O.A. duct to north side of Brix Basement (See Note 5)	OPEN	Close
FSD B- 31	S.A. from AHU-2 to VAV / B-13 and VAV / B-14 (See Note 5)	OPEN	Close
FSD B- 32	S.A. from VAV / B-13 to S.A. plenum and risers to Ground Floor	OPEN	Close

### NOTES (Typical for all FSDs shown):

- 1 Refer to Detail B/M-1.1 for FSD installation of FSD B21, B-22, B-23, and B-24. Refer to Detail A/M-1.1 for all others.
- 2. There must a duct, smoke detector associated with each Fire/Smoke Damper and located within 5' of the FSD. Refer to Electrical Drawings.
- 3. Access panels for each FSD shall be located on the open ceiling or T-bar side whenever possible.
- 4. Field measurement of existing openings is required before ordering dampers.
- 5. FSDs B-30 & B-31 must be vertical with actuators on the bottom. Other dampers may need to be vertical if space is not available on side of duct. The contractor must make this determination.

DESIGNATION	EF / 4	EF/7	EF / 12
CFM	3,600	2,500	2,800
EXT. S P (IN. WC)	1.00	3.10	1.00
MOTOR HP/ BHP	2.0 / 0.98	3.0 / 2.13	1.5 / 0.76
VOLTS/ PHASE	460/3	460/3	460/3
RPM	1202	2160	1202
DRIVE	DIRECT	BELT	DIRECT
MOUNTING	SEE NOTE 2	SEE NOTE 2	SEE NOTE 2
MANUFACTURER	GREENHECK	GREENHECK	GREENHECK
TYPE	UPBLAST UTILITY SET	UPBLAST UTILITY SET	UPBLAST UTILITY SET
MODEL NUMBER	USF-20	USF-15	USF-20
CONTROL	INTERLOCK WITH AH/B-1	SEE DETAIL A/M-10	INTERLOCK WITH AH/B-3
LOCATION	MERCER ROOF	EAST STAIRWAY ROOF	MERCER ROOF
DUTY	MEETING ROOMS ECON. RELIEF	KITCHEN HOOD & GEN. EXHAUST	ACTIVITY ROOM ECON. RELIEF
OPER. WT. (LBS)	375	250	375
ACCESSORIES	1 - 7	1 - 8	1 - 7

- 1. PREMIUM EFFICIENCY, INVERTER-DUTY MOTOR, ADJUSTABLE DRIVE PULLEY, AND WEATHERHOOD.
- 2. 1" SPRING ISOLATORS WITH SEISMIC RESTRAINTS.
- 3. INLET AND OUTLET COMPANION FLANGES.
- 4. BOLTED ACCESS DOOR AND 1" DRAIN PLUG.
- 5. UP DISCHARGE AND BAKED ENAMEL FINISH. 6. UP DISCHARGE AND BAKED ENAMEL FINISH.
- 7. WELDED SCROLL HOUSING.
- 8. UL/cUL-762 POWER VENTILATOR FOR RESTAURANT EXHAUST APPLIANCES.

# **KEYNOTES**

- (2) Existing concrete floor of Ground Floor Lobby.
- (4) Ruskin Model FSD60-2-1 fire/smoke damper with TS-150 firestat and 20" length sleeve. manufacturer's recommendations.

------


\_\_\_\_\_\_

- (6) Breakaway duct connection.
- (9) 120-volts to actuator provided by Electrical.
- (10) Duct, smoke detector. Refer to Electrical Drawings for specifications, installation, and

- 1) Remove existing floor grille and reinstall within frame of damper sleeve. Nominal size is 6" x 48, but field verification is required.
- 3) Perimeter angle frame. Refer to Ruskin installation instructions.
- Damper shall be installed in accordance with CSFM Listing 3235-0245:126.
- (5) 2-position electric actuator (fail close).
- 7 Supply air duct. See Sheet M-4.4 for size.
- (8) 6" x 24" access panel in bottom of duct.

**APPROVED** 03/17/2023 COUNTY OF FRESNO DEVELOPMENT SERVICES









FRESNO FIRE DEPARTMENT

	REVISION	TABLE:	
	REV.	DESCRIPTION	DATE
1			
-			
1			
١			

11/15/2022 SCALE: As indicated

JOB NUMBER:


BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

21-1137 21-105379 PROJECT:

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:

SCHEDULES




SCALE: N.T.S.

REDUCER OR INCREASER

1.16 GA. L FRAME WELDED, (MIN. 50% PERIMETER) TO ALL 4 SIDES OF SLEEVE. L FRAME SHALL BE DESIGNED TO LAP WALL NOT LESS THAN 1". ROUGH OPENING IN MASONRY WALLS AND NET OPENING IN FRAME WALLS SHALL EXCEED NET O.D. OF DAMPER ASSEMBLY. DO NOT FASTEN SIDES OR TOP OF L TO WALL OR PARTITION.

2. FIRE DAMPER SHALL BE SFM LISTED AND INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS.


FIRE/SMOKE DAMPER THROUGH WALL



FIRE/SMOKE DAMPER THROUGH FLOOR TO LOBBY FLOOR GRILLE SCALE: 1-1/2"=1'-0"

7





# **DEMOLITION KEYNOTES:** 1 Existing HWS and HWR routed to Mercer equipment. 2 Existing chilled water expansion tank to be temporarily removed to permit removal of RF-1 and ductwork. (3) Remove existing duct supports and R.A. drop from floor to finished floor +100". Support existing duct (including elbow drop) from structure above as floor supports are removed. (4) Remove existing ductwork. 5 Remove RF-1 serving the Brix Basement. Fan may need to be cut up to remove. (6) Provide permanent sheet metal cover of R.A. opening

- isolate these upper floors.
- for new AH/B-5.
- during construction. and seal airtight. Reinforce with vertical supports if
  - (24) Existing domestic water chiller. Disconnect electrical and piping connections and temporarily relocate to remove AHU-1 and install AH-5B. Provide temporary bypass of CW to maintain supply to drinking fountains.
  - (25) Existing control air compressor to remain.
  - (26) Cut piping and provide a removable cap.
- 9 Existing 5 HP VFD for RF-1 to be abandoned in place.
- (11) Existing EMS panel for AHU-1 and AHU-2. Replace existing AHU-1 controls with new EMS controls.
- (12) Existing RF-2 (serving Ground Floor) to remain active
- (14) Existing AHU-2 (serving Ground Floor) to remain active during construction. Approximately 5400 supply
- (15) Existing HW shut-off valves.

during construction.

- (16) Access panel to mixed air plenum.
- (17) South end of O.A. plenum on level above.
- (18) Remove existing O.A. damper. Actuator will be

required. Patch does not require insulation.

7 Existing R.A. plenum to remain active during

8 Existing R.A. damper to remain active during

(10) Existing 2 HP VFD for RF-2 to remain active.


(13) Existing mechanical room exhaust fans to remain.

- (19) Remove AHU-1, filter rack, hot and chilled water piping, and discharge ductwork up to P.O.C. shown on the drawings. The opening to mixed air plenum must be temporarily sealed.
- (20) Existing chilled and hot water piping to and from upper floors. There are no shut off valves, at this location, to
- (21) Remove existing HWS and HWR in front of AHU-1.
- (22) Existing VFD for AHU-1 shall remain and be reused
- (23) Existing refrigerant-leak purge fan to remain active

- (27) Remove existing HW piping to and from existing HW
- (28) Existing fire pump controls.
- 29 Existing fire jockey pump.
- (30) Existing fire pump.
- (31) Existing domestic water booster pump assembly.
- 32 Existing exhaust air riser to remain. See Sheet M-4.3


# KEYNOTES:

- 1) Floor to ceiling double wall partition with 2" insulation and threshold for access door. This partition separates the existing O.A. plenum into two plena. Seal around all
- (2) 30" x 76" high door, with gasketing, double wall construction with 2" insulation, and access handle on both sides. Verify sizes of all dampers and doors prior to
- (3) 30" x 42" outdoor air, opposed blade damper in ceiling of plenum for AHU-2. Damper shall be furnished by Control Contractor and installed by Mechanical Contractor. Control Contractor to relocate the existing actuator to this damper and test for proper operation during the economizer cycle.
- (4) Shaded area requires sheet metal work to frame in new O.A. damper in ceiling of
- (5) Unobstructed O.A. opening to AH/B-5.
- (6) Existing partition is in the O.A. plenum in the level above.
- (7) Mixed air plenum for AHU-2.
- (8) Return air plenum for AHU-2.
- (9) Existing elbow abandoned in place.
- (10) Provide S/M cover over belt and pulley of purge fan.
- (11) Area around side and front of air handler for hot and chilled water manifolds for AH/B-5. Piping on the side shall not interfere with access to the fan motor.
- (12) Restore 2-1/2" (verify) HWS and HWR offset loop between P.O.C.s 1 and 2. Piping on this loop shall be grooved to facilitate removal. Provide floor or ceiling support.
- (13) P.O.C. 1 with grooved piping and shut-off valves where shown.
- (14) P.O.C. 2 with grooved piping.
- (15) 2" HWS to and HWR from hot water coils. See Detail F/M-7.
- (16) 2-1/2" CWS to and CWR from chilled water coils. See Detail F/M-7.



KEY PLAN:





Muratore associates

CONSULTANT STAMP





AUG 2 9 2024 9

FRESNO FIRE DEPARTMENT

11/15/2022 As indicated JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

21-1137 21-105379


SHEET TITLE:


MECHANICAL ROOM DEMO & NEW PLAN

SHEET NUMBER

M-2.1

M-2.1








MECHANICAL ROOM DEMOLITION PLAN



MECHANICAL ROOM (NEW WORK) PLAN SCALE: 1/4"=1'-0"

**APPROVED** 03/17/2023 COUNTY OF FRESNO DEVELOPMENT SERVICES





PARTIAL MECHANICAL ROOF PLAN

## KEYNOTES:

- (A) Extend existing ductwork to plenum. Stainless steel not required.
- B Sheet metal exhaust plenum with 18" in direction of airflow. Provide 14" x 14" access panel at side of duct.
- (C) VFD cabinet for EF-10. Cabinet shall be NEMA 3R with thermostatically controlled fan and ABB drive with BACnet card. VFD shall be 2 HP (connected motor will be less horsepower). Cabinet shall be furnished by Controls Contractor, installed by Electrical.
- D VFD cabinet for EF-11. All else per Keynote C.
- (E) VFD cabinet for EF-12 with 3 HP VFD (connected motor will be less horsepower). All else per Keynote C.
- (F) VFD cabinet for EF-4 with 3 HP VFD (connected motor will be less horsepower). All else per Keynote C.
- (G) Square, sheet metal reducer to accommodate inlet cone companion flange. Attach flex connection with sheet metal cover over top and sides.
- (H) Remove existing spring isolators and pedestal support and install new isolators per Detail E/M-5. Seal existing openings caused by removal of bolts.
- (J) Install 24" high discharge duct on outlet and expand to 18" x 24" to accommodate a Ruskin BD6 backdraft damper. Provide 1/2" x 1/2" mesh screen on top of duct just beyond BDD open blades.
- (K) Electrical subpanel on roof for mechanical equipment. See Electrical Drawings.
- (L) Refer to Sheet M-11.1 for refrigerant pipe sizing. One line (on the drawing) represents three refrigerant lines.
- (M) Remove roofing down to top of concrete. Install pipe support per Detail F/M-6 and restore roof. See Specifications for spacing.
- (N) Refer to Detail B/M-3 for ODU attachments. Also refer to Structural Detail 3/S1.02 and Architectural details.

- (1) At the top of existing discharge duct, install a backdraft damper (approximately 13" x 10") and cover with 1" square-mesh screen.
- 2) Provide 1/2" x 1/2" square-mesh screen over fan discharge duct.
- 3 Existing exhaust duct(s) to remain. 4 Existing VFDs for EF-8 and EF-9 to remain.
- 5 See Sheet M-4.3 for continuation.
- 6 Existing, welded exhaust risers to remain. See Detail A/M-3 for modification and extension of ductwork.
- 7 Remove existing fan. Patch holes in existing platform cover to maintain weather-tight condition, typical at all existing platforms. Fill existing screw holes with wood putty and use heavy mastic on holes in sheet metal cover.
- 8 VFD cabinet for EF-13 with 2 HP VFD (motor may be less HP). All else per Keynote C/Detail A/M-3.
- 9 Install full-size Ruskin BD-6 in discharge duct just below 1" mesh
- (10) Provide increaser from existing duct to new EF-12 inlet. Provide flex connection with sheet metal cover over top and sides.
- (11) Remove existing fan and install new EF-12. Install 24" high discharge duct on outlet and expand to 18" x 24" to accommodate a Ruskin BD6 backdraft damper. Provide 1/2" x 1/2" mesh screen on top of duct just beyond BDD open blades.
- (12) Remove equipment from existing platforms and seal holes. Existing platforms may be used to support refrigerant piping.
- (13) Replace existing motor with new. Refer to Roof Exhaust Fan
- Existing platform and sheet metal cover to remain. Patch unused holes and seal weather tight.
- (15) Future Emergency Generator will replace existing generator.
- (16) Remove exhaust fan, support rail, isolators, and exhaust duct through platform. Provide weatherproof sealant over bolt holes in
- Three sets of (3) refrigerant lines through platform into duct shaft. See Detail K/M-8.
- (18) Three sets of (3) refrigerant lines on roof.
- (19) Existing gas up through roof. See Plumbing Drawings.
- (20) Remove existing water supply and drain piping above roof that is no longer required. Provide S.O.V. on supply lines, insulate, and cap above roof. Restore roofing as required.






# ODU ATTACHMENTS

SCALE: NONE

top to bottom	of this sheet)		Balance to	
Fan I.D.	Duty	Action	CFM	Notes
EF-10	General Relief Air (from Corridor)	Replace existing motor with 1 HP motor	1600	2
EF-2	General Exhaust	Replace/adjust drives for new CFM	700	4
EF-11	Economizer Relief Air for AH-B4	Replace existing motor with 1 HP motor	1900	2
EF-1	No Longer Required	Remove fan and inlet ductwork		6
EF-3 (west)	No Longer Required	Remove fan and inlet ductwork		6
EF-14	Serves Floors above the Basement	Remain Active		1
EF-15	None	Abandon in place		3
EF-13	Brix Toilet Rooms	Remain Active	600	5
EF-3 (east)	None	Remove Under This Project		
existing) EF-4	None	Remove Under This Project		-
EF-4	Econ. Relief for Mercer Meeting Rooms	New fan replaces existing EF-4	3600	
EF-12	Econ. Relief for Mercer Activity Room	New fan replaces existing EF-12	2500	
EF-6	None	Abandon in place		
EF-8	None	Abandon in place		
EF-9	None	Abandon in place		
EF-5	Mercer East Toilet Rooms	Replace/adjust drives for new CFM	850	4

- 1. Balancing of this fan is not within scope.
- 2. New motor shall be inverter duty, 460-volt, 3-phase.
- 3. Exhaust duct terminates near Brix toilet rooms and is reserved for future use.
- 4. Reconnect existing, 120-volt exhaust fan circuit and route circuit through an EMS start contactor. Use existing wiring and contactors where possible. Field verify, see Electrical Drawings, and coordinate with Electrical Contractor.
- 5. Existing plans show motor to be 1 HP at 460/3. Field verify.
- 6. Refer to Keynote 16.





Muratore associates

CONSULTANT STAMP





# APPROVED

AU3 29 2024 09

FRESNO FIRE DEPARTMENT

REVISION	N TABLE:	
REV.	DESCRIPTION	DATE
<u></u>		
<b></b>	<u> </u>	

11/15/2022 SCALE: As indicated JOB NUMBER:

ADDRESS:

M-3

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:

MERCER ROOF PLAN


SHEET NUMBER


**APPROVED** 

03/17/2023

COUNTY OF FRESNO


DEVELOPMENT SERVICES





# DEMOLITION SECTION AT AC-1 (AHU-1)

SCALE: 1/4"=1'-0"




SECTION

TO SPACE.-

LOOKING SOUTH

SCALE: NONE



# KEYNOTES FOR M-4.3 AND M-4.4

- (1) Liquid, suction, and gas refrigerant lines between BSBs and ODU (listed). Refer to VRF piping diagrams (Sheet M-11.1) for line sizes.
- (2) Liquid and gas refrigerant lines between BSBs and IDUs. Refer to VRF piping diagrams (Sheet M-11.1) for line sizes.
- (3) Refrigerant piping through existing masonry wall. If the penetration is not shown on the Structural Drawings, submit an RFI for approval.
- (4) Refer to Detail A/M-8 for branch dampers, typical.
- ( 5 ) VAV box (by Controls Contractor) set at constant volume to maintain constant Outdoor Air airflow. Refer to Detail E/M-7 for mounting. Controls Contractor to provide 24 VAC. For VAV-17, 18, 19, 20 (in the Brix Break Room), boxes are mounted with the control box on the bottom, for access.
- (6) O.A. grille for minimum outside air to the south portion of the Caged Storage
- 7 O.A. grille for minimum outside air to the north portion of the Caged Storage
- 8 O.A. grille within 18" of inlet to IDU/B-4. This provides ventilation air to the (south) Ground Floor Lobby.
- (9) O.A. grille within 18" of inlet to IDU/B-5. This provides ventilation air to the (north) Ground Floor Lobby.
- (10) CFM shown is the supply air (in the existing riser) to a typical Ground Floor office. Refer to Section E/M-9 for typical notations.
- (11) Typical duct-mounted, smoke detector, located within 5' of FSD. Refer to Electrical Drawings for specifications and wiring.
- (12) Refer to Detail G/M-8 for equipment support, typical.
- (13) Refer to Detail A/M-8 for typical S.A. grille connections.
- (14) Refer to Detail B/M-8 for typical R.A. or E.A. grille connections.
- (15) Air quantity up to Ground Floor Lobby.
- (16) Offset ductwork down below beam.
- (17) Automatic Balancing Damper (ABD) to maintain constant outdoor airflow to fan coil or supply-air grille during occupancy hours. ABD shall be duct size unless otherwise indicated. Refer to "VRF Fan Schedule," Sheet M-1.0, for O.A. CFM.
- (18) Branch dampers not required upstream of VAV boxes or ABDs, typical.
- (19) Duct insulation not required.

MOUNTING HEIGHT

SCALE: NONE

CONCRETE OR

MASONRY WALL

6#/FT<sup>3</sup>CERAMIC FIBER

INSULATION SECTION:

PIPING THRU WALL.-

SEAL ENDS WITH DOW

CORE THRU WALL. PROVIDE 1" NOMINAL ANNULAR SPACE.-

**CORNING 3-6548** 

SILICONE FOAM. -

(20) Provide 5' of insulated flex duct at connection to grille, and then connect to sheet metal duct with no insulation required.

CENTERLINE OF THERMOSTAT.

SWITCH, OUTLET, CONTROL.

FINISH FLOOR

THERMOSTAT OR CONTROL

SWITCH MOUNTING HEIGHT

- (21) Duct, hot water piping, or refrigerant lines through existing opening in wall. Refer to Architectural Drawings for sealing the opening, if required.
- (22) Refer to Detail B/M-10 for Conference Room fan coil control (by EMS Contractor)
- (23) When R.A. duct connects to plenum with O.A. duct, no balancing dampers are
- Q4) O.A. duct from AH/B-5. Air is pre-tempered, so insulation not required unless
- (25) Refer to Details C, D, & E/M-7 for VAV box controls, piping, and mounting.
- (26) Refer to Detail A/M-1.1 for fire/smoke damper installation, typical.

(27) FSD access panel, typical at all FSDs weather or not shown.

- (28) Refer to Detail A/M-8 for support, but all duct must be sheet metal in exposed
- (29) Ducts, grilles, pipes (insulated or not), hangers, etc. shall be painted flat black in Break Room. VAV boxes shall also be painted, but do not paint over any labels.
- (30) Provide sheet metal escutcheon (with 2" flange) where duct meets wall framing.
- (31) EMS control panel with controller for Conference Room controls (Detail B/M-10) and control transformer for nearby VAV boxes. Panel requires 120 volts, see
- (32) Duct increases in height to allow duct taps. May be required in other areas.
- (33) Refrigerant piping through holes in existing 1/4" steel plate. Piping insulation may be reduced to 1/4" neoprene to fit existing holes in plate and concrete wall.
- (34) Existing 16" diameter S.S. duct to be reused. See Sheet M-3 for roof exhaust fan
- (35) P.O.C. of existing 16" diameter exhaust to reducer and connect to 12" round.
- (36) Refer to Detail D/M-8 for "Ceiling Cassette" IDU.
- (37) Provide new Tee with 1-1/2" top connection on exiting HWS and HWR. Provide 1-1/2" ball valves and connect into new reheat piping.
- (38) Hold ductwork tight to north-south beams.

TOP OF THERMOSTAT,

CONTROL

FINISH FLOOR.

PACK ANNULAR SPACE

WITH HEAVY DENSITY

MINERAL WOOL.

1. SEE PLANS FOR PIPE SIZE.

M-4.0

**OVER OBSTRUCTION** 

44" MAX. FOR WHEEL CHAIR FORWARD


PER CBC 1127A.9.6.

APPROACH AND 46" MAX. FOR SIDE APPROACH

- (39) Actual dimension may be different than shown on the plan. Field verify.
- (40) Maximum air temperature rise at full-range output and 2,500 CFM exhaust is 20

- (41) Duct shall be welded stainless steel from hood connection to flex connection at exhaust fan. Provide access panels as required by Code. Connection to hood may be offset to the north (within hood limits) to lessen the duct offset. Hood must be ordered this way.
- (42) 16" x 16" sheet metal sleeve. Verify for fit.
- (43) End of acoustic lining. Downstream duct shall be wrapped.
- (44) Location of ABD and diffuser may be relocated to fit field conditions and avoid
- (45) Field coordinate IDU location to maintain access to fan compartment and filter. Existing fire sprinkler in this area will need to be relocated.
- (46) Exposed S.A. duct does not require insulation. Ducts over ceilings require
- (47) ABD with 6" diameter discharge duct into 30" of 6" x 6" acoustic lined duct. Locate high. This duct supplies outdoor air to the vestibule area.
- (48) Refer to Detail F & J/M-8 for "High-wall" IDUs.
- (49) I-touch controller for VRF system. Refer to Sheet M-11.2. The 120-volt circuit to the EMS panel also feeds this panel.
- (50) Connect new exhaust grilles (with balancing dampers) to existing exhaust system.
- (51) Existing exhaust riser is active and also serves floors above.
- (52) Refer to Detail B/M-4.0 for piping through masonry wall.
- (53) Existing S.A. ductwork from AHU-2 to remain. This duct serves the offices at the Ground Floor, above.
- (54) Refer to Detail D/M-4.0 for end-of-line piping connections.
- Provide sheet metal cap with sealant over existing opening, typical where ducts (55) have been removed.
- (56) Provide sheet metal cap over existing R.A. opening.
- (57) Exposed ductwork in storage areas does not require painting.
- (58) Hard connect fan coil R.A. duct to side of plenum box over R.A. grille.

**APPROVED** 03/17/2023 COUNTY OF FRESNO DEVELOPMENT SERVICES



PENETRATION FIRESTOP FOR AN UNINSULATED PIPE THROUGH A GYPSUM WALLBOARD ASSEMBLY

- 1. WALL ASSEMBLY THE 1,2,3, OR 4 HR FIRE -RATED GYPSUM WALLBOARD/STUD WALL ASSEMBLY SHALL BE CONSTRUCTED OF THE MATERIALS AND IN THE MANNER SPECIFIED IN THE INDIVIDUAL U300 OR U400 SERIES WALL AND PARTITION DESIGNS IN THE UL FIRE RESISTANCE DIRECTORY AND SHALL INCLUDE THE FOLLOWING CONSTRUCTION FEATURES.
- A. STUDS: WALL FRAMING MAY CONSIST OF EITHER WOOD STUDS OR STEEL CHANNEL STUDS. WOOD STUDS TO CONSIST OF NOM. 2x4 IN. LUMBER SPACED 16" O.C. STEEL STUDS TO BE MIN 3 5/8" WIDE AND SPACED MAXIMUM 24" O.C.
- B. <u>WALLBOARD</u>, <u>GYPSUM\*</u>: THICKNESS, TYPE, NUMBER OF LAYERS AND FASTENERS, AS SPECIFIED IN THE INDIVIDUAL WALL AND PARTITION DESIGN. MAX DIAM OF OPENING IS 9". THE HOURLY F RATING OF THE FIRESTOP SYSTEM IS EQUAL TO THE HOURLY FIRE RATING OF THE WALL ASSEMBLY IN WHICH IT IS INSTALLED.
- THROUGH PENETRANTS ONE METALLIC PIPE OR TUBING TO BE INSTALLED EITHER CONCENTRICALLY OR ECCENTRICALLY WITHIN THE FIRESTOP SYSTEM. THE ANNULAR SPACE BETWEEN PIPE, CONDUIT OR TUBING AND PERIPHERY OF OPENING SHALL BE MIN 0 (POINT CONTACT) IN TO MAX 1 3/8" PIPE, CONDUIT OR TUBING TO BE RIGIDLY SUPPORTED ON BOTH SIDES OF WALL ASSEMBLY.
- THE FOLLOWING TYPES AND SIZES OF METALLIC PIPES, CONDUITS OR TUBING MAY BE USED: A. STEEL PIPE: NOM 24" DIAM (OR SMALLER) SCHEDULE ST 40 (OR HEAVIER) STEEL PIPE. 1A. NOM 4" DIAM (OR SMALLER) SCHEDULE 7 (OR HEAVIER) STEEL PIPE.
- 2A. NOM 8" DIAM (OR SMALLER) SCHEDULE 10 (OR HEAVIER) STEEL PIPE. 3A. NOM 10" DIAM (OR SMALLER) SCHEDULE 20 (OR HEAVIER) STEEL PIPE.
- 4A. NOM 24" DIAM (OR SMALLER) SCHEDULE 40 (OR HEAVIER) STEEL PIPE.


IS USED T RATING IS 0 HR.

SCALE: NONE

- B. <u>IRON PIPE</u>: NOM 24" DIAM (OR SMALLER) CAST OR DUCTILE IRON PIPE. WHEN IRON PIPE IS USED T RATING IS 1/4" HR. WHEN STEEL OR IRON PIPE IS USED T RATING IS 1/4 HR FOR NOM 4" DIAM (OR SMALLER) AND 0 HR FOR STEEL OR IRON PIPES GREATER THAN NOM 4" DIAM.
- C. CONDUIT: NOM 6" DIAM (OR SMALLER) STEEL ELECTRICIAL METALLIC TUBING (EMT). WHEN EMT IS USED T RATING IS 1/4 HR.
- D. CONDUIT: NOM 6" DIAM (OR SMALLER) STEEL CONDUIT. WHEN STEEL CONDUIT IS USED T RATING IS 1/4 HR. E. <u>COPPEER TUBING</u>: NOM 6" DIAM (OR SMALLER) TYPE L (OR HEAVIER) COPPER TUBE IS USED T RATING IS 1/4 HR. F. COPPEER PIPE: NOM 6" DIAM (OR SMALLER) REGULAR (OR HEAVIER) COPPER PIPE. WHEN COPPER PIPE
- 3. FILL, VOID OR CAVITY MATERIAL\* SEALANT MIN 5/8" THICKNESS OF FILL MATERIAL FOR 1 HR FIRE RATED WALL ASSEMBLIES AND MIN 1" THICKNESS OF FILL MATERIAL FOR 2, 3 OR 4 HR FIRE RATED WALL ASSEMBLIES, APPIED WITHIN THE ANNULUS, FLUSH WITH BOTH SURFACES OF WALL. AT POINT CONTACT LOCATION BETWEEN PIPE COVERING AND WALLBOARD, A MIN 1/2" DIAM BEAD OF FILL MATERIAL SHALL BE APPLIED AT THE WALLBOARD / PIPE COVERING INTERFACE ON BOTH SURFACES OF WALL.

PIPE THROUGH STUD WALL w/FIRESTOP

M-4.0



CONSULTANT STAMP





FRESNO FIRE DEPARTMENT

REVISION	TABLE:	
REV.	DESCRIPTION	DATE
***************************************		

11/15/2022 SCALE: As indicated

JOB NUMBER:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

21-1137 21-105379

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:


DETAILS


M-4.0

M-4.0

SCALE: NONE

PIPE THROUGH CONCRETE WALL W/ FIRESTOP (B)









Muratore associates







AUG 2 9 2024 09


FRESNO FIRE DEPARTMENT


11/15/2022 As indicated

ENLARGED BASEMENT HVAC









559-365-6534 info@muratoreassociates.com 1222 M SHAW AVE. FRESNO, CA 93711



7084 N. Maple Ave., Suite 101 21003

REVISION TABLE: DESCRIPTION

11/15/2022 As indicated JOB NUMBER:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721


21-1137 21-105379

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:

ENLARGED BASEMENT HVAC PLAN


SHEET NUMBER



SECTION

SCALE: 1/4"=1'-0"


SCALE: 1/4"=1'-0"





M-6

M-6

SCALE: NONE











CONSULTANT STAMP



21003 Fresno, CA 93720 FAX (559) 431-1362

AUS 2 9 2024 00

FRESNO FIRE DEPARTMENT

REV.	DESCRIPTION	DATE

11/15/2022 DATE: SCALE: As indicated JOB NUMBER:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379

PROJECT:


FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION


SHEET TITLE:


SECTIONS


SHEET NUMBER


M-6












SECTION AT 1-HOUR SUPPLY-AIR PLENUM

SCALE: 1"=1'-0"





NURATORE ASSOCIATES 1222 M SHAW AVE. FRESNO, CA 93711 info@muratoreassociates.co

CONSULTANT STAMP





FRESNO FIRE DEPARTMENT

REV.	DESCRIPTION	DATE

11/15/2022 SCALE: As indicated JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379


FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:


DETAILS

SHEET NUMBER

M-9



# **DUCT WRAP & HANGERS**




SCALE: NONE

M-9

KITCHEN HOOD

SCALE: NONE

**APPROVED** 03/17/2023 COUNTY OF FRESNO DEVELOPMENT SERVICES



SCALE: NONE

INTERNAL NUMBER: 829

TYPICAL (E) S.A. GRILLE AND S.A. RISER FROM BASEMENT. SEE SHEET M-4.2 FOR CFM.

SEE ARCH. DWG'S.

24"x10" RANGE HOOD

SEE SHEET M-4.3 FOR CONTINUATION. SEE

DET. B/M-9 FOR DUCT

THRU FLOOR.-

EXHAUST FROM BASEMENT.

PARTIAL GROUND FLOOR MECHANICAL PLAN

THROUGH PENETRATION DETAIL 3M FIRE WRAP - DUCT WRAP DETAILS

ROUND DUCT PATTERN: RECTANGULAR DUCT PATTERN: TWO REQUIRED FOR EACH SIDE

LEGEND

4 1st layer transition pattern Fire Barrier 615+ Duct Wrag

5 2nd layer transition pattern FireBarrier 615+ Duct Wra

2 1st layer Fire Barrier 615+ Duct Wrap

3 2nd layer Fire Barrier 615+ Duct Wrap

6 3" minimum overlap

8 Anchor fastner system

9 Bar stock 2" - 3" wide, 1/8" thick

INSTALL FIRE BARRIER 615+ DUCT


RECOMMENDATIONS.

WRAP IN STRICT ACCORDANCE WITH

MANUFACTURER'S INSTRUCTIONS AND

SUGGESTED INSTALLATION FOR TERMINATION OF DUCT WRAP AT NON-RATED HOOD LOCATION

TWO REQUIRED FOR EACH SIDE



**Point Type** 

Trend Alarm Totalize

Notes

hrough BACnet

Through BACnet

See Note 2

Not required for AH/B-5

Not required for AH/B-5

To allow for CFM reduction

To allow for CFM reduction

Through BACnet

Through BACnet

hrough BACnet

Through BACnet

Through BACnet

Current Sensor

Through BACnet

hrough BACnet

See Detail A/M-10 for control

See Note 4 and Detail C/M-

Global in Mercer ductwork

Monitor only

See Detail B/M-1

Hard wired

Refer to Sheet M-11.2

Field verify existing wiring

Summation of VAV Boxes (N.A. to AH/B-2)

RANGE HOOD VENTILATION CONTROL

Units

Working or Fault

Off On

1. For VAV terminals or IDUs serving the Ground Floor, replace the existing room sensor with a new sensor. Restore wall surfaces where existing sensors were removed.

4. Remove existing controls on the Ground Floor and replace with new VRF or VAV room controllers. Locate new sensors or thermostats in the same location and patch wall.

2. Airflow station shall be the thermistor type because entering air is unfiltered. Airflow stations shall have access for cleaning.

5. This is a PARTIAL list. Other EMS points may be required by the Sequences of Operation.

Occupied, Not Occupied

DIAGRAMATIC

BUILDING EMS POINTS LIST

Air Handlers (AH/B-1, AH/B-2, AH/B-3, AH/B-4)

em Point Description

Supply Fan Enable

Fan Speed (to VFD)

Supply Air Temperature

Return Air Temperature

Mixed Air Temperature

Chilled Water Control Valve Hot Water Control Valve

Outside Air Airflow Station

California Economizer Status

Downstream Duct Static Pressure

Occupancy Sensor in room for AH/B-1

Occupancy Sensor in room for AH/B-3

Outside Air Damper

Total Supply Airflow

Supply Fan Enable

Fan Speed (to VFD)

Supply Air Temperature

Entering Air Temperature

Hot Water Control Valve Outside Air Airflow Station

Chilled Water Control Valve

Basement Isolation Damper, SD-40

Damper end switch - fully open

Damper end switch - fully closed

Room Temperature Sensor with Adjustable Set Point

Downstream Duct Static Pressure

Fan Status

Filter Status

vpical VAV Box with Reheat

Air Volume Control

Air Volume Monitor

Air Volume Control

Air Volume Monito

ODU-1 Status

ODU-2 Status

ODU-3 Status

Fan Enable

Fan Enable

Fan Status

Kitchen Hood Exhaust Fan, EF-7

Ground Floor Temperature Control

Miscellaneous Mechanical Systems

Outside Air Temperature

Occupancy Sensor

Room Temperature

IDU Disable

Fan Status

Leaving Air Temperature

Hot Water Control Valve

Typical VAV Box for Volume Control Only

Interface EMS to iTouch Controller

General Building Existing Exhaust Fans, EF- 2, 5, 13

Building Economizer Relief Fans - 3-phase (EF-4, 10, 11, 12)

Provide room thermostats on Ground Floor for IDU-B4 & IDU-B-5

Provide room sensors for VAV/B-11, B-12, B-13, & B-14

Mercer Network Room Temperature Sensor

Conference Room Control (IDUs B-9, B-10, B-11)

Filter Status

ir Handler AH/B-5

Return Air Damper

Fan Status

KEYNOTES: (1) Manual pull station furnished with hood. Mount at finished floor + (13) CP-1 switch panel mounted per Detail F/M-4.0. Provide with 42" at point of egress. inputs/outputs as follows:

(2) Cable and pulley system for manual pull station.

(3) Cable and pulley system from hood to Ansul panel.

(4) Expellant gas line piping to hood.

(5) Ansul R102 (wet chemical) fire protection system cabinet. See plans for location.

(6) Wiring from dry contacts at Ansul panel to EMS. Completion of this circuit notifies the EMS that liquid fire suppressant was released, but the EMS does not take any action.

(7) Wiring from "Alarm Initiating Switch" that the Ansul system was

(8) Fire Alarm Panel (see Electrical Drawings) with input/output (for this system) as follows:

A. Input from Ansul panel B. Output to high-speed relay

C. Output to range-hood-off relay

(9) Fire alarm relay to disconnect Range/cooktop during a hood fire. See Electrical Drawings.

(10) Wiring from CP-1 to hood lights by Division 16.

(11) Grease hood exhaust ducting.

(12) Wiring from hood temperature sensors to EMS. EMS to provide conversions as required to read the correct temperature. If the hood temperature exceeds 100 degrees, the EMS will switch the exhaust fan to high speed.

A. Hood lights B. Fan ON high speed

> C. "Ready for Cooking" green pilot light D. "Not Ready for Cooling" reg pilot light

(14) High-speed relay from CP-1.

(15) High-speed relay if given a signal from the FAP. This relay must be furnished by the Fire Alarm Contractor.

(16) Typical disconnect by Spec. Division 16.

(17) VFD for hood exhaust fan furnish by EMS contractor. Furnish with BACnet card. If the auxiliary contact circuit is completed, the fan will go to high speed. High speed and low speed RPMs are field determined with coordination from the air balancing agency.

At High and Low speeds with clean filters, record the amperage of EF motor. Through BACnet, the EMS shall the check the VFD and determine if the amperage is within +/- 20% of the original determined speed. If it is not, this may indicate a motor fault or dirty filters, and an ALARM will be issued to the system.

(18) VFD enable from the EMS. The default start position is low

(19) BACnet wiring by EMS contractor.

(20) EMS BACnet controller with the minimum interfaces as follows:

A. VFD enable B. Hood temperature reading C. Fan ON switch from CP-1 D. "Ready for cooking" light enable E. "Not ready for cooking" light enable

# IDU FOR CONFERENCE JROOMS -DI AI DO .. .. .. DETAIL F/M-4.0 —

TYPICAL OF CONFERENCE ROOMS B0203, B0204, & B0211

Fire Alarm Shutdown: When Required by 2019 CMC Section 608.1

and chilled central water plant will start as a system.

associated exhaust fans will operate as a system.

IDU/B-19, serving the I.T. Room, may start at any time.

VAV AIR HANDLERS (AH/B-1, B-3 & B-4)

may access the system for further information.

CONFERENCE ROOM CONTROL

from the fire alarm relays to IDU's is high voltage and shall be provided under Division 26.

UNITS WITH BUILT-UP ECONOMIZERS (AH/B-1, B-2, B-3 & B-4)

economizer operation. If more relief is required, then EF-11 will start and modulate.

modulates the fan VFD to maintain a pressure of 0.05" w.c.

AIRFLOW AND VENTILATION REDUCTION

AH/B-1

AH/B-2

open to the value listed in the Air Handler Schedule.

EMS CONTROL OF NON-HVAC SYSTEMS

cooling load. Provide temperature sensors to monitor supply air, return air, mixed air, and outdoor air.

Unless otherwise specified, the first stage of cooling shall be with a mixture of return air and outside air as required to satisfy the

When any smoke or fire is detected by the Fire Alarm System, AH-1 through AH-5 and all the IDU's shall shut down and all

fire/smoke dampers (in the Basement and those located in plane of the Ground Floor) will close. AHU-2 and its associated

return fan will also shut off. Duct detectors and fire alarm relays will be furnished under Division 26. Duct detectors shall be

"Shut down" wiring from the fire alarm relays to air handler VFDs shall be furnished by the EMS contractor. "Shut down" wiring

If off-hours operation is required in the Mercer-Basement side, AH/B-1 through AH/B-4, associated exhaust fans, and the hot

If off-hours operation is required in the Brix-Basement side, AH/B-5, IDU fan coils, the hot and chilled water central plant, and

If the supply air temperature of any handler drops to 45 degrees, this will indicate a failure in the control system valves.

Field-furnished economizer dampers and controls on air handlers must comply with the 2019 California Energy Code,

Subchapter 3, Section 120.2 (i), with respect to function and economizer Fault Detection and Diagnostics.

Airflow monitoring of Outdoor Air is required to ensure minimum airflow when the supply fan reduces volume.

The supply-air set point temperature shall be maintained to satisfy the zone requiring the most cooling. The mixed air low limit

Any fault shall be summarized as a digital output point and reported to the EMS which will issue an alarm. The EMS operator

When AH/B-1 goes into the economizer mode, relief fan EF-4 will start and modulate to offset outdoor air quantities caused by

When AH/B-2 goes into the economizer mode, relief fan EF-12 will start and modulate to offset outdoor air quantities caused by

When AH/B-4 goes into the economizer mode, relief fan EF-10 will start and modulate to offset outdoor air quantities caused by

Relief fans shall react slowly. The unit EMS controller measures the difference in building and outside air static pressure and

Relief and/or exhaust fans operating in conjunction with an air conditioning system shall shut down when the supply fan stops.

Three-phase relief fans shall have the "enable" hard wired through an auxiliary contact of the supply fan VFD. This is required.

The Meeting Room and Activities Room have occupancy sensors CO2 sensors to reduce the supply air and ventilation air if the

600

room is not occupied. If occupancy is not detected for 30 minutes, the supply fan speed shall reduce speed as listed below.

Minimum Outside Air is a function of CO2 sensor reading. As CO2 levels increase beyond 1000 ppm, the O.A. damper will

When occupied, supply airflow of AH/B-1 is determined by the VAV terminals. When the Activities Room is occupied, the

Air Handler Min. Supply Air Min. O.A. CFM

supply airflow of AH/B-2 shall start at 60% of full airflow, and then increase as required by the cooling load.

1200

900

dampers, or hot water supply. If this occurs the air handler shall shut down and the EMS will issue an alarm.

KEYNOTES:

DIAGRAMATIC

installed under Division 23.

Off-Hours Operation

Temperature Control

Airflow Monitoring

Relief Fan Control

economizer operation.

economizer operation.

Meeting Room

Activities Room

shall be set at 45 degrees.

M-10

1 A portion of a nearby EMS controller using

the "DO" to activate a relay at the IDU.

shown shall be provided by the EMS

(2) Occupancy sensor. Provide power from the

(4) Relay to interrupt the fan circuit at the IDU.

(5) Hard-wired, room thermostat furnished with

EMS controller panel.

(3) Wall plate temperature sensor.

(1) digital input, (1) analog input, and (1)

digital output. Provide a power source for

Wiring, sensors, power supplies, and relay

SEQUENCE OF OPERATION:

This sequence shuts off the IDU fan to save energy, it does not vary the Outdoor Air CFM to the room. AH/B-5 supplies Outdoor Air to this room during business hours.

The IDU shall operate one hour prior to occupancy to maintain set point temperature. At time of occupancy, the IDU shall shut OFF.

The IDU shall start if:

A. The occupancy sensor senses people,

B. The room temperature is outside the range of 68 to 76 degrees (software adjustable).

Once the IDU starts, it will stay ON for a period of 10 minutes. The EMS will then check for occupancy or temperature conditions to determine if the fan will stay

M-10



MURATORE ASSOCIATES

CONSULTANT STAMP



# 084 N. Maple Ave., Suite 101

# 21003

FRESNO FIRE DEPARTMENT

REVISION	TABLE:	
REV.	DESCRIPTION	DATE

11/15/2022 DATE: SCALE: As indicated JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379

PROJECT: FRESNO COUNTY DEPT. OF

PUBLIC HEALTH BASEMENT RENOVATION

CONTROL DIAGRAMS

INTERNAL NUMBER: 829

SHEET NUMBER

**APPROVED** 

03/17/2023

COUNTY OF FRESNO

DEVELOPMENT SERVICES

## GENERAL

Failure of any device commanded to start shall signal an alarm and cause the next device in the sequence to start.

No more than 10 HP shall start at one time. This applies during any startup, including startup after power interruption. When new systems are installed on existing buildings with existing motors, allowance shall be made for existing motors. Provide a four second delay between motor startups.

Under Specification Section 230923, provide labor, tools, services, electrical connections and equipment required by the specifications, mechanical plans, control drawings, points list, and sequences of operations. A control device, shown or referenced once, is required; it may not be cross referenced. Devices requiring control shown on the mechanical plans, but which are not addressed by control references or the Mechanical Equipment Schedule, must be interlocked with and/or

Control diagrams are diagrammatic and show the intent of a sequence, but not the exact details pertaining to all points of connection. Provide power supplies and control interfaces as required. If systems are designed to operate under Emergency Power or UPS, the EMS controllers must also function under these modes.

Where existing systems are replaced with new systems, existing control devices, linkages, supports, wiring, conduit, pneumatic tubing, etc. shall be removed on exposed walls. Existing conduit and wiring above hard ceilings which remain, may be abandoned in place.

## Timing Sequences

The opening and closing of dampers and the starting (or ramping) of VFD-controlled motors often involves various time delay sequences to prevent over or under pressurizing rooms or ducts. These timing sequences shall be provided under Specification Section 230923

# Variable Frequency Drives

Variable Frequency Drives shall communicate with the EMS. Input information shall include start/stop and a signal to indicate the desired speed. Information returned to the EMS shall include output speed (in %). A start signal to ENABLE the VFD shall come from a hard-wired connection from the EMS or device, not through BACnet. Drives shall be ABB.

Field programming of VFDs shall be provided by the supplier of that equipment. Programming shall include ramping characteristics, setting the full-load amps for the connected motors, maximum speed, and other information as may be required to satisfy the sequences of operation. VFDs shall be set to ramp down slowly. Output speed signal of equipment with BACnet cards shall be reported by BACnet.

# EMS Control Panels

When existing EMS controllers are reused (with new connections) or replaced, existing connected inputs and outputs must be reconnected. With new controllers, existing circuits must be reprogrammed to operate "as before" or as noted. Whether the controller is reused or replaced, all connections must be documented on the Control Drawings for this project. Locations of new panels shown on the drawings are approximate and require field verification. Power for the controller panel shall come from the A/C unit transformer with wiring and conduit by Specification 230923 unless otherwise noted on the drawings. Provide a separate transformer if required by controller and other connected loads. Power (24 VAC) for VAV terminals shall come from nearby EMS panels.

# Current Sensors

For fan systems with current sensors, the EMS shall be able to detect the difference between a fan under load and one with a broken belt. Current sensors are required on the supply blower, each compressor, and exhaust/relief fans within new equipment. If airflow stations or another method will detect "no flow," then current sensors are not required.

# **EXHAUST FANS**

Exhaust fans shall be interlocked as shown on the Mechanical Equipment Schedule or the Control Diagrams. Toilet room exhaust fans interlocked with the EMS shall follow the same schedule as the A/C system that supplies supply air to the toilet room.

In addition to controlling new exhaust fans, the EMS must be able to start/stop existing fans as shown on Sheet M-3.

# AIR CONDITIONING SYSTEMS (General)

For the purposes of this section, "air conditioning systems" described below shall include, packaged air conditioners and unit heater. General sequences shall apply to all such systems unless otherwise noted. Systems not specifically defined with a control sequence shall follow the sequence of the most similar system.

Air conditioning systems shall start one hour prior to occupancy. O.A. dampers shall open to a minimum position to admit O.A. CFM as specified on the plans.

# Optimal Start: Required per Section 120.2 (k)

When cold, outdoor conditions occur, the EMS may start the units more than one hour before occupancy.

# Supply Fan Control

Whenever supply fans are shut down, outdoor air dampers and exhaust/relief dampers (when automatic) will close, and exhaust fans serving that zone shall also shut down.

Once started, the supply fans of air conditioning systems will remain ON until turned OFF by the EMS at the end of the day.

Each system may have an individual start and stop time. Exhaust fans on any zone served by an air conditioning system shall There are no additional interfaces with building systems.

# SEQUENCE OF OPERATION

DIAGRAMATIC

# EMS POINTS LIST

3. Fans may be new or existing with new motors.


DIAGRAMATIC


NOTES:



M-10

M-10





**ODU-2 WIRING** 

DIAGRAMATIC

**ODU-1 WIRING** 

DIAGRAMATIC



120 VOLTS

SYSTEM ARCHITECTURE

DIAGRAMATIC

**DEVELOPMENT SERVICES** 



11/15/2022 As indicated

M-11.2

INTERNAL NUMBER: 829

M-11.2

Mechanic NRCC-MCH-E											-			CALIFORNIA E	NERGY COMMISSIO
CERTIFICATE C	F COM	PLIANCE													NRCC-MCH
Project Name:							and the same of the same of	t Remodel Rep							(Page 2 of 3
Project Addres	ss:						1221 Fu	Iton Street Date	Prepa	red:				The state of the s	3/4/202
C. COMPLIA	NCE R	ESULTS													
										al requirement compliant for			itable b	y the user. If this t	able says "DOES
01		02		03		04		05		06		07		08	09
System Summary §110.1, §110.2, §140.4	AND	Pumps §140.4(k)	AND	Fans/ Economizers §140.4(c), §140.4(e)	AND	System Controls §110.2, §120.2, §140.4(f)	AND	Ventilation §120.1	AND	Terminal Box Controls §140.4(d)	AND	Distribution §120.3, §140.4(I)	AND	Cooling Towers §110.2(e)2	Compliance Result
(See Table F)		(See Table G)		(See Table H)		(See Table I)		(See Table J)		(See Table K)		(See Table L)		(See Table M)	1
Yes	AND		AND	Yes	AND	Yes	AND	Yes	AND	Yes	AND	Yes	AND		COMPLIES
				Mandatory	Measu	res Complian	ce (Se	Table Q for D	etails)				СОМР	LIES	
D EVCEDTIO	NAL C	ONDITIONS													
I his table is a	iuto-fill	ed with unedit	able co	omments beca	use of .	selections mad	de or d	ata entered in	tables	throughout th	e form.				
E. ADDITION	VAL RE	MARKS													

NRCC-MCH-E							CALIFORNIA ENERGY COMMIS
CERTIFICATE OF COMPLIANCE							NRCC-M
This document is used to demonstrate co path outlined in <u>§140.4</u> , or <u>§141.0(b)2</u> f		cal systems that are wi	thin the scop	e of the permit applic	ation and are	demonstrating o	compliance using the prescripti
Project Name:		Brix Mercer Basement R	emodel Repor	t Page:			(Page 1 c
Project Address:		1221 Fultor	Street Date I	repared:			3/4/
A. GENERAL INFORMATION							
01 Project Location (city)		Fresno	04	Total Conditioned Fl	oor Area		22747
02 Climate Zone		13	05	Total Unconditioned	Floor Area		173
03 Occupancy Types Within Project:			06	# of Stories (Habitab	le Above Gra	de)	1
☑ Office (B)	☐ Retail (M	)		Non-refrigerated Wa	rehouse (S)		
☐ Hotel/ Motel Guest Rooms (R-1)	☐ School (E	:)		Healthcare Facility (I	)		
☐ High-Rise Residential (R-2/R-3)	☐ Relocata	ble Class Bldg (E)	×	Other (write in)	ing the state of t		See Table J
B. PROJECT SCOPE							
This table Includes mechanical systems of	r components that are	within the scope of the	e permit app	lication and are demo	nstrating con	npliance using the	e prescriptive path outlined in
§140.4, or §141.0(b)2 for alterations.							
01			02				03
Air System(s)  Heating Air System			ystem Comp	onents			em Components
			omizer			Air Economize	
		Pumps				Electric Resist	ance Heat
Mechanical Controls		☐ System Pipi	ng			Fan Systems	
Mechanical Controls (existin or new)	g to remain, altered	☐ Cooling Tow	vers		⊠	Ductwork (exi	sting to remain, altered or new
		☐ Chillers				Ventilation	
		☐ Boilers				Zonal Systems	/ Terminal Boxes

Report Version: 2019.1.003

Schema Version: rev 20200601

PLUI DING ENERGY ANALYSIS REPORT		
BUILDING ENERGY ANALYSIS REPORT		
PROJECT:		
Brix Mercer Basement Remodel 1221 Fulton Street		
	1 1	

**Project Designer:** Muratore Associates 2697 W Robinwood LN Fresno, CA 93711 559-365-6543

Report Prepared by: Abel Lopez Lawrence Engineering Group 7084 N Maple Avenue Suite 101 Fresno, CA 93720

559-431-0101

Job Number: 21003

The EnergyPro computer program has been used to perform the calculations summarized in this compliance report. This program has approval and is authorized by the California Energy Commission for use with both the Residential and Nonresidential 2019 Building Energy Efficiency Standards. This program developed by EnergySoft Software - www.energysoft.com.

Registration Provider: Energysoft Registration Provider: Energysoft Registration Number: Registration Date/Time:

STATE OF CALIFORNIA CALIFORNIA ENERGY COMMISSION

(Page 5 of 34)

Variable Air Volume

Design Airflow through

Device (CFM)

Variable Air Volume

Design Airflow through Device (CFM)

Registration Provider: Energysoft

Report Generated: 2022-03-04 09:13:03

CALIFORNIA ENERGY COMMISSION

Constant Volume

Design Airflow through

Device (CFM)

Fan Power Pressure Drop Adjustment - Table 140.4-B

NRCC-MCH-E

(Page 8 of 34)

Fan Power Pressure Drop Adjustment - Table 140.4-B

Power Pressure Drop Adjustment - Table 140.4-B

Registration Date/Time:

Report Version: 2019.1.003

Schema Version: rev 20200601

Mechanical Systems CALIFORNIA ENERGY COMMISSION NRCC-MCH-E CERTIFICATE OF COMPLIANCE NRCC-MCH-E Project Name: Brix Mercer Basement Remodel Report Page: (Page 4 of 34) 1221 Fulton Street Date Prepared

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Report Generated: 2022-03-04 09:13:03

This section does not apply to this project.

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Registration Number:

STATE OF CALIFORNIA

NRCC-MCH-E

Fan Name or

Item Tag

System Name:

01

an Name or

Item Tag

Fan Name or

Item Tag

**Mechanical Systems** 

CERTIFICATE OF COMPLIANCE

I. FAN SYSTEMS & AIR ECONOMIZERS

VRF Other (Transfer, VAV box)

Fan Function

Total System Design Supply Airflow (CFM):

ton)

VRF Other (Transfer, VAV box)

IDU B - 1,2,3 (3 ton)

VRF Other (Transfer, VAV box)

Total System Design Supply Airflow (CFM):

Total System Design Supply Airflow (CFM):

Fan Function

System | IDU B - 1,2,3 (3

y system Equipme	ent Efficiency (other than Package Te	rminal Air Conditi	oners (PIAC) and I	Package Terminal	Heat Pumps (PTHE	'))		
01	02	03	04	05	06	07	08	09
			Heati	ng Mode			Cooling Mode	
Name or Item Tag	Size Category (Btu/h)	Rating Condition (°F)	Efficiency Unit	Minimum Efficiency Required per Tables 110.2 / Title 20	Design Efficiency	Efficiency Unit	Minimum Efficiency Required per Tables 110.2 / Title 20	Design Efficiency
AH -B5	>=240,000					EER IEER	9.8 11.4	12.2 12.9
VRF ODU 1	>=240,000	47 °Fdb/ 43 °Fwb OSA	СОР	3.2	4	EER IEER	9.5 12.7	13 18
ODU 2	>=240,000	47 °Fdb/ 43 °Fwb OSA	СОР	3.2	4	EER IEER	9.5 12.7	13 18
ODU 3	>=65,000 and <135,000	47 °Fdb/ 43 °Fwb OSA	СОР	3.3	4.5	EER	11.0 14.6	13.9 21.3

Registration Date/Time:

Brix Mercer Basement Remodel Report Page:

Economizer: NA: <=54 kBtu/h cooling

Economizer: NA: <=54 kBtu/h cooling

Economizer: NA: <=54 kBtu/h cooling

Maximum Design Supply Airflow

1100

Maximum Design Supply Airflow

1100

Maximum Design Supply Airflow

1100

1100

1221 Fulton Street Date Prepared:

Controls:

Report Version: 2019.1.003

Schema Version: rev 20200601

Economizer Designed per §140.4(e) and

Design HP

0.3

Design HP

0.3

0.3

Design HP

0.3

0.3

HP Unit<sup>2</sup>

BHP

HP Unit<sup>2</sup>

BHP

HP Unit<sup>2</sup>

BHP

Total System Design (B)HP:

Total System Design

Economizer Controls:

Total System Design

(B)HP:

Economizer Controls:

STATE OF CALIFORNIA Mechanical Systems CALIFORNIA ENERGY COMMISSION NRCC-MCH-E CERTIFICATE OF COMPLIANCE NRCC-MCH-E (Page 3 of 34)

his table is used	to demonstrate compliance	for mechanical equipment with mandator	v requirements	found in §11	0.1 and 61	10.2(a) and	nrescriptive	requireme	nts found in	8140 4/2
	<u>140.4(k)</u> or <u>§141.0(b)2</u> for a		y requirements ;	ourid iii jaa	ora direction	unic	prescriptive	requireme	nto jouna n	3140.410
Ory System Equi	pment Sizing (includes air co	nditioners, condensers, heat pumps, VRI	f, furnaces and u	ınit heaters)						
01	02	03	04	05	06	07	08	09	10	11
9					Equipme		er Mechanica 5140.4 (a&b		(kBtu/h)	
			Smallest Size	Hea	ating Outpu	t <sup>2,3</sup>	Cooling C	Output <sup>2,3</sup>	Load Calc	ulations <sup>3,4</sup>
Name or Item Tag	Equipment Category per Tables 110.2	Equipment Type per Tables 110.2 / Title 20	Available <sup>1</sup> §140.4(a)	Per Design (kBtu/h)	Rated (kBtu/h)	Supp. Heating Output (kBtu/h)	Sensible Per Design (kBtu/h)	Rated (kBtu/h)	Total Heating Load (kBtu/h)	Total Sensible Cooling Load (kBtu/h)
AH -B5	Unitary AC/ Condensers	AC, air-cooled pkg (3 phase)	NA: Load Controls	401.9	401.9	0	330.24	321.5	865.17	415.74
VRF ODU 1	Variable Refrigerant Flow	VRF heat pump, air cooled	NA: Load Controls	199.65	228	0	250.21	200	319.77	263.01
ODU 2	Variable Refrigerant Flow	VRF heat pump, air cooled	NA: Load Controls	199.65	228	0	243.3	200	200.54	245.37
ODU 3	Variable Refrigerant Flow	VRF heat pump, air cooled	NA: Load Controls	67.43	77	0	62.58	60	60.28	65.23

<sup>2</sup>It is common practice to show rated output capacity on the equipment schedule. Sensible cooling output comes from specification sheet tables.

<sup>3</sup> If equipment is heating only, leave cooling output and load blank. If equipment is cooling only, leave heating output and load blank. <sup>4</sup> Authority Having Jurisdiction may ask for load calculations used for compliance per <u>§140.4(b)</u>.

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Report Generated: 2022-03-04 09:13:03

STATE OF CALIFORNIA			
Mechanical Systems			
NRCC-MCH-E			CALIFORNIA ENERGY COMMISSION
CERTIFICATE OF COMPLIANCE			NRCC-MCH-E
Project Name:	Brix Mercer Basement Remodel	Report Page:	(Page 6 of 34)
Project Address:	1221 Fulton Street	Date Prepared:	3/4/2022

Registration Date/Time:

Report Version: 2019.1.003

Schema Version: rev 20200601

		H. FAN SYSTEN	IS & AIR ECON	OMIZERS							
System Fan Type:	Constant Volume	System Name:	AH - B3	Econor	nizer:1	Differential Temperature	Economi		Designe	ed per <u>§140.4(e)</u> and (m)	System Fan Type:
07	08	01	02		03	04			05	06	07
Fan Power Pressure Drop	Adjustment - Table 140.4-B	Fan Name or				Maximum Design Supply	Airfland				Fan Power Pressure Drop
Device	Design Airflow through Device (CFM)	Item Tag	Fan Functi	on	Qty	(CFM)	Airiow	НР	Unit <sup>2</sup>	Design HP	Device
NA NA	NA	SF	Supply		1	1600		ı	ВНР	1.2	NA THE
Maximum System Fan Power (B)HP:		Total Syster	m Design Supply	Airflow (CF	M):	1600	Total Sy	stem B)HP:	Design	1.2	Maximum System Fan Power (B)HP:
System Fan Type:	Constant Volume	System Name:	AH - B4	Econor	nizer:1	Differential Temperature	Economi Contro		Designe	ed per <u>§140.4(e)</u> and (m)	System Fan Type:
07	08	01	02		03	04			05	06	07
Fan Power Pressure Drop	Adjustment - Table 140.4-B	Fan Name or				Maximum Design Supply	Airflow				Fan Power Pressure Drop
Device	Design Airflow through Device (CFM)	Item Tag	Fan Functi	on	Qty	(CFM)	Airnow	HP	Unit <sup>2</sup>	Design HP	Device
NA NA	NA	SF	Supply		1	3150		. [	НР	2.3	NΔ
Maximum System Fan		EF	Exhaust		1	0			НР	0.1	NA.
Power (B)HP:  System Fan Type:	Constant Volume	Total Syster	n Design Supply	Airflow (CF	M):	3150	Total Sy	stem   B)HP:	Design	2.4	Maximum System Fan Power (B)HP:
07	08	System Name:	AH -B5	Econor	nizer:1	NA: System operates @ 100% OSA	Economi Control		Designe	d per <u>§140.4(e)</u> and (m)	System Fan Type:
Fan Power Pressure Drop	Adjustment - Table 140.4-B	01	02		03	04			05	06	07
Device	Design Airflow through	Fan Name or				Manian and Davidson Committee	A '- Flance				Fan Power Pressure Drop
NA :	Device (CFM)	Item Tag	Fan Functi	on	Qty	Maximum Design Supply (CFM)	Airnow	HP	Unit <sup>2</sup>	Design HP	Device
Maximum System Fan Power (B)HP:		SF	Supply		1	7000			НР	6	NA
	and the same of th	Total Syster	n Design Supply	Airflow (CF	M):	7000	Total Sy	stem I	Design	6	Maximum System Fan


item iag			(CFIVI)					Device	Device (CFM)
SF	Supply	1	1600			ВНР	1.2	NA.	NA NA
Total Syster	m Design Supply	Airflow (CFM):	1600	Total S	System (B)HP:	Design	1.2	Maximum System Fan Power (B)HP:	
System Name:	AH - B4	Economizer	Differential Temperature	Econor		Designe	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Variable Air Volume
01	02	0:	3 04			05	06	07	08
Fan Name or			Maximum Design Suppl	v Airflow				Fan Power Pressure Drop	Adjustment - Table 140.4-
Item Tag	Fan Function	on Qt	y (CFM)	y All llow	HF	Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)
SF	Supply	1	3150			ВНР	2.3	104	MA
EF	Exhaust	1	0			ВНР	0.1	NA .	VA.
Total Syster	m Design Supply	Airflow (CFM):	3150	Total S	ystem (B)HP:	-	2.4	Maximum System Fan Power (B)HP:	
System Name:	AH -B5	Economizer	NA: System operates @ 100% OSA	Econor		Designe	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02	0:	04			05	06	07	08
Fan Name or			Maximum Design Suppl	v Airflow				Fan Power Pressure Drop	Adjustment - Table 140.4-
Item Tag	Fan Function	on Qt	y (CFM)	y Allilow	НР	Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)
SF	Supply	1	7000			ВНР	6	NA	NA
Total Syster	n Design Supply /	Airflow (CFM):	7000	Total S	ystem (B)HP:		6	Maximum System Fan Power (B)HP:	6.58

Registration Date/Time: CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601

> **APPROVED** 03/17/2023 COUNTY OF FRESNO **DEVELOPMENT SERVICES**









FRESNO FIRE DEPARTMENT

REVISION TABLE:		
REV.	DESCRIPTION	DATE

DATE: 11/15/2022 SCALE: As indicated JOB NUMBER:

ADDRESS:

Registration Provider: Energysoft

Variable Air Volume

Design Airflow through

Registration Provider: Energysoft

Report Generated: 2022-03-04 09:13:03

Pressure Drop Adjustment - Table 140.4-

Report Generated: 2022-03-04 09:13:03

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379 PROJECT:

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:

TITLE 24 DOCUMENTS

SHEET NUMBER

INTERNAL NUMBER: 829

VRF Other (Transfer, VAV box) BHP Maximum System Far Total System Design Total System Design Supply Airflow (CFM): 1350 0.4 (B)HP: Power (B)HP: Designed per §140.4(e) and NA: <=54 kBtu/h cooling System Fan Type: Constant Volume Name: n Power Pressure Drop Adjustment - Table 140.4-B Fan Name or Maximum Design Supply Airflow Fan Function Design HP Design Airflow through Item Tag Device (CFM) VRF Other (Transfer, VAV box) BHP Total System Design Maximum System Fan Total System Design Supply Airflow (CFM): (B)HP: Power (B)HP: System Economizer Designed per §140.4(e) and NA: <=54 kBtu/h cooling 6,7,8,9,13,14,15,1 System Fan Type: Constant Volume Controls: 6 (2 ton) an Power Pressure Drop Adjustment - Table 140.4-B Maximum Design Supply Airflow Fan Name or Fan Function Design Airflow through Item Tag (CFM) Device Device (CFM) VRF Other (Transfer, VAV box) 650 BHP Total System Design Maximum System Far Total System Design Supply Airflow (CFM): 0.1 (B)HP: Power (B)HP:

Registration Number:

This table is used to demonstrate compliance with prescriptive requirements found in \$140.4(c), \$140.4(e) and \$140.4(m) for fan systems. Fan systems serving only process loads are

Brix Mercer Basement Remodel Report Page:

Differential Temperature

4200

Differential Temperature

Maximum Design Supply Airflow

4200

Maximum Design Supply Airflow

3300

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Economizer Designed per §140.4(e) and

3.5

Design HP

0.4

BHP

HP Unit<sup>2</sup>

BHP

Total System Design

(B)HP:

Registration Date/Time:

Brix Mercer Basement Remodel Report Page:

Economizer: NA: <=54 kBtu/h cooling

Maximum Design Supply Airflow

(CFM)

1221 Fulton Street Date Prepared:

Controls:

Report Version: 2019.1.003

Schema Version: rev 20200601

Economizer Designed per §140.4(e) and

Design HP

Total System Design

System Fan Type:

Naximum System Fa

Power (B)HP:

Power (B)HP:

System Fan Type:

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Registration Number:

STATE OF CALIFORNIA

Fan Name or

Item Tag

Registration Number:

STATE OF CALIFORNIA

Project Address:

Fan Name or

Item Tag

Mechanical Systems

CERTIFICATE OF COMPLIANCE

H. FAN SYSTEMS & AIR ECONOMIZERS

System IDU B - 4,5 (4.5

Mechanical Systems

CERTIFICATE OF COMPLIANCE

H. FAN SYSTEMS & AIR ECONOMIZERS

Fan Function

Supply

Fan Function

Supply

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Total System Design Supply Airflow (CFM):

Total System Design Supply Airflow (CFM):

exempt from these requirements and do not need to be included in Table H.

Registration Date/Time: Report Version: 2019.1.003 Schema Version: rev 20200601

Registration Provider: Energysoft Report Generated: 2022-03-04 09:13:03

Registration Number CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Registration Date/Time: Report Version: 2019.1.003 Schema Version: rev 20200601

Report Generated: 2022-03-04 09:13:03

Registration Provider: Energysoft

Registration Provider: Energysoft

Report Generated: 2022-03-04 09:13:03

CALIFORNIA ENERGY COMMISSION

NRCC-MCH-E

(Page 7 of 34)

3/4/2022

Registration Number:

STATE OF CALIFO Mechanic NRCC-MCH-E	cal Systems							CALIFOR	NIA ENERGY COMMISSIO
	F COMPLIANCE								NRCC-MCH-
Project Name: Project Addres				Brix Mercer Basem		et Date Prepare			(Page 11 of 3/4/202
Project Addres	33:			1221	ruiton stre	et Date Prepare	eu.		3/4/202
H. FAN SYST	EMS & AIR ECONO	MIZERS					400		
System Name:	IDU B - 20,23 (HSW .75 ton, 275 CFM)	Econor	mizer:1	NA: <=54 kBtu/h cooling	Econor		gned per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02		03	04		05	06	07	08
Fan Name or Item Tag	Fan Function	n	Qty	Maximum Design Supply (CFM)	Airflow	HP Unit <sup>2</sup>	Design HP	Fan Power Pressure Drop A	Adjustment - Table 140.4 Design Airflow through Device (CFM)
VRF	Other (Transfer, VA	AV box)	1	275	-	ВНР	0.1	NA	Device (Crivi)
Total Sve	stem Design Supply Ai		M).	275	Total 9	System Design		Maximum System Fan	
System	IDU B - 12 (4 ton)	Econor		NA: <=54 kBtu/h cooling	Econor		gned per <u>§140.4(e)</u> and	Power (B)HP: System Fan Type:	Constant Volume
Name: 01	02		03	04	Contr	05	(m) 06	07	08
					Airflow			Fan Power Pressure Drop A	
Fan Name or Item Tag	Fan Function		Qty	Maximum Design Supply (CFM)	Airtiow	HP Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)
VRF	Other (Transfer, VA	AV box)	1	1350	T-1-10	ВНР	0.3	NA	NA
Total Sys	stem Design Supply Ai	irflow (CF	M):	1350	lotal	System Design (B)HP:	0.3	Maximum System Fan Power (B)HP:	
	lumber: nergy Efficiency Standaro	ds - 2019 i	Nonreside	ntial Compliance	Repor	ration Date/Time t Version: 2019.	1.003		
STATE OF CALIFO <b>Mechanic</b> NRCC-MCH-E	nergy Efficiency Standar	ds - 2019 f	Nonreside	ntial Compliance	Repor		1.003	Report Gen	stration Provider: Energysof erated: 2022-03-04 09:13:0: NIA ENERGY COMMISSIC NRCC-MCH
CA Building Entrance of Califo  Mechanic  IRCC-MCH-E  ERTIFICATE O	nergy Efficiency Standard RNIA Cal Systems FCOMPLIANCE	ds - 2019 f	Nonreside	ntial Compliance Brix Mercer Basemi	Report Schem	t Version: 2019. la Version: rev 2	1.003 0200601	Report Gen	erated: 2022-03-04 09:13:0
CA Building Entrance of Califor Mechanic RCC-MCH-E CERTIFICATE O	nergy Efficiency Standard RNIA CAI Systems F COMPLIANCE	ds - 2019 f	Nonreside	Brix Mercer Basem	Report Schement Remod	t Version: 2019. la Version: rev 2	1.003 0200601	Report Gen	NIA ENERGY COMMISSIC  NRCC-MCH  (Page 14 of 3
CA Building Entrance of CALIFO Mechanic RCC-MCH-E ERTIFICATE Oroject Name:	nergy Efficiency Standard RNIA cal Systems F COMPLIANCE		Nonreside	Brix Mercer Basem	Report Schement Remod	el Report Page:	1.003 0200601	Report Gen	NIA ENERGY COMMISSIC  NRCC-MCH  (Page 14 of 3
CA Building Entrate OF CALIFO  Mechanic  RCC-MCH-E  ERTIFICATE O  Project Name:  Project Addres  H. FAN SYST  System	nergy Efficiency Standard RNIA CAI Systems F COMPLIANCE			Brix Mercer Basem	Report Schement Remode Fulton Street	el Report Page: et Date Prepare	1.003 0200601 ed:	Report Gen	erated: 2022-03-04 09:13:0: NIA ENERGY COMMISSIC NRCC-MCH
CA Building Entrate OF CALIFO  Aechanic RCC-MCH-E  ERTIFICATE O  roject Name: roject Addres  I. FAN SYST  System  Name:	RRIIA CAI Systems F COMPLIANCE SS:  EMS & AIR ECONOI  IDU B - 20,23 (HSW .75 ton, 275 CFM)	MIZERS	mizer:1	Brix Mercer Baseme 1221 F NA: <=54 kBtu/h cooling	Report Schement Schement Remode Fulton Street	el Report Page: et Date Prepare	1.003 0200601 ed: gned per <u>§140.4(e)</u> and (m)	CALIFOR  System Fan Type:	NIA ENERGY COMMISSIC NRCC-MCH (Page 14 of 3 3/4/20  Constant Volume
CA Building Entrate OF CALIFO  Aechanic RCC-MCH-E  ERTIFICATE O  roject Name:  Toject Addres  System  Name:  01	RNIA cal Systems  F COMPLIANCE ss:  EMS & AIR ECONOI  IDU B - 20,23 (HSW .75 ton, 275	MIZERS		Brix Mercer Basemo 1221 F NA: <=54 kBtu/h cooling 04	Report Schement Remoder Fulton Street Economer Control	el Report Page: et Date Prepare	1.003 0200601 ed:	CALIFOR  System Fan Type:	NIA ENERGY COMMISSION NRCC-MC-(Page 14 of 3 3/4/20)
CA Building Entrate OF CALIFO  Aechanic RCC-MCH-E  ERTIFICATE O  roject Name:  roject Addres  System  Name:  01	RRIIA CAI Systems F COMPLIANCE SS:  EMS & AIR ECONOI  IDU B - 20,23 (HSW .75 ton, 275 CFM)	MIZERS Econor	mizer:1	Brix Mercer Baseme 1221 F NA: <=54 kBtu/h cooling	Report Schement Remoder Fulton Street Economer Control	el Report Page: et Date Prepare	1.003 0200601 ed: gned per <u>§140.4(e)</u> and (m)	CALIFOR  System Fan Type:	NIA ENERGY COMMISSIC NRCC-MCH (Page 14 of 3 3/4/20  Constant Volume  08 djustment - Table 140.4-
CA Building Entrance of Califor Aechanic RCC-MCH-E ERTIFICATE O roject Name:  System Name:  01	RRIIA CAI Systems F COMPLIANCE SS:  EMS & AIR ECONOI  IDU B - 20,23 (HSW .75 ton, 275 CFM)  02	MIZERS Econor	mizer:1	Brix Mercer Baseme 1221 F NA: <=54 kBtu/h cooling 04 Maximum Design Supply	Report Schement Remode Fulton Street Control C	el Report Page: et Date Prepare  Designols:  O5  HP Unit <sup>2</sup> BHP	1.003 0200601 ed: gned per <u>§140.4(e)</u> and (m)	System Fan Type:  07 Fan Power Pressure Drop A Device	NIA ENERGY COMMISSIC NRCC-MCH (Page 14 of 3 3/4/20  Constant Volume  08 idjustment - Table 140.4- Design Airflow through
CA Building Entrate OF CALIFO VIECHANIC RCC-MCH-E ERTIFICATE O Project Name: Project Address H. FAN SYST System Name: 01 Fan Name or Item Tag  VRF Total Sys	RRIIA CAI Systems F COMPLIANCE SS:  EMS & AIR ECONOI IDU B - 20,23 (HSW .75 ton, 275 CFM)  02 Fan Function Other (Transfer, VA	MIZERS  Econor	nizer:1 03 Qty 1	Brix Mercer Baseme 1221 F NA: <=54 kBtu/h cooling 04 Maximum Design Supply (CFM)	Report Schement Remoderation Street Remoderati	el Report Page: et Date Prepare  nizer Design ols:  05  HP Unit <sup>2</sup> BHP system Design (B)HP:	1.003 0200601 ed: gned per <u>§140.4(e)</u> and (m) 06 Design HP 0.1	CALIFOR  System Fan Type:  07  Fan Power Pressure Drop A	NIA ENERGY COMMISSIC  NRCC-MCH  (Page 14 of 3  3/4/202  Constant Volume  08  idjustment - Table 140.4-  Design Airflow through
CA Building Entrate OF CALIFO Mechanic RCC-MCH-E ERTIFICATE O roject Name: roject Addres  I. FAN SYST System Name: 01 Fan Name or Item Tag  VRF	RRIIA CAI Systems F COMPLIANCE SS:  EMS & AIR ECONOI IDU B - 20,23 (HSW .75 ton, 275 CFM) 02 Fan Functior Other (Transfer, VA	MIZERS  Econor	03 Qty 1 CM):	Brix Mercer Basema 1221 f NA: <=54 kBtu/h cooling 04 Maximum Design Supply (CFM)	Report Schement Remode Fulton Street Control C	el Report Page: et Date Prepare  nizer Design obs:  05  HP Unit²  BHP system Design (B)HP: nizer Design	1.003 0200601 ed: gned per §140.4(e) and (m) 06 Design HP 0.1	System Fan Type:  07 Fan Power Pressure Drop A Device  Maximum System Fan	NIA ENERGY COMMISSIC  NRCC-MCH (Page 14 of 3  3/4/20:  Constant Volume  08  djustment - Table 140.4-  Design Airflow through
CA Building Entrate OF CALIFO  Vechanic  IRCC-MCH-E  CERTIFICATE O  Project Name:  Project Address  H. FAN SYST  System  Name:  01  Fan Name or  Item Tag  VRF  Total System  System	RRIIA CAI Systems F COMPLIANCE SS:  EMS & AIR ECONOI IDU B - 20,23 (HSW .75 ton, 275 CFM)  02 Fan Function Other (Transfer, VA	MIZERS  Econor  AV box)	03 Qty 1 CM):	Brix Mercer Baseme 1221 F  NA: <=54 kBtu/h cooling  04  Maximum Design Supply (CFM)  275	Report Schement Remoder Fulton Street Remoder Control Schement Remoder Control Schement Remoder Remode	el Report Page: et Date Prepare  nizer Design obs:  05  HP Unit²  BHP system Design (B)HP: nizer Design	1.003 0200601 ed: gned per <u>§140.4(e)</u> and (m) 06 Design HP 0.1 0.1	System Fan Type:  07 Fan Power Pressure Drop A Device  Maximum System Fan Power (B)HP: System Fan Type:	NIA ENERGY COMMISSION NRCC-MC- (Page 14 of 3 3/4/20)  Constant Volume  08  Idjustment - Table 140.4  Design Airflow through Device (CFM)  Constant Volume
CA Building Entrate OF CALIFO VIECHANIC RCC-MCH-E ERTIFICATE O Project Name: Project Address H. FAN SYST System Name:  01 Fan Name or Item Tag  VRF  Total Sys System Name:	RRIIA CAI Systems F COMPLIANCE SS:  EMS & AIR ECONOI  IDU B - 20,23 (HSW .75 ton, 275 CFM)  02  Fan Function  Other (Transfer, VA stem Design Supply Ai  IDU B-10,11(1.5 ton)	MIZERS  Econor  AV box)  Irflow (CF  Econor	nizer:1 03 Qty 1 M):	Brix Mercer Basema 1221 f NA: <=54 kBtu/h cooling 04 Maximum Design Supply (CFM) 275 275 NA: <=54 kBtu/h cooling	Report Schement Remoderation Street Remoderation Remoderation Street Remoderation Stre	el Report Page: et Date Prepare  nizer Design ols:  05  HP Unit²  BHP cystem Design (B)HP: nizer Design	1.003 0200601 ed: gned per §140.4(e) and (m) 06 Design HP 0.1 0.1 0.1 gned per §140.4(e) and (m)	CALIFOR  CALIFOR  System Fan Type:  07  Fan Power Pressure Drop A  Device  Maximum System Fan Power (B)HP:  System Fan Type:	NIA ENERGY COMMISSION NRCC-MCI (Page 14 of 3 3/4/20 Constant Volume  08  Idjustment - Table 140.4  Design Airflow through Device (CFM)  Constant Volume

01	02		03	04		05	1 06	0/	U8
Fan Name or				Maximum Design Supply	Airflow			Fan Power Pressure Drop	Adjustment - Table 140.4-I
Item Tag	Fan Functio	n	Qty	(CFM)	Allilow	HP Unit	Design HP	Device	Design Airflow through Device (CFM)
VRF	Other (Transfer, V	AV box)	1	275		ВНР	0.1	NA	NA
Total System Design Supply Airflow (CFM):		1 7/5 1		ystem Desig (B)HP:	0.1	Maximum System Fan Power (B)HP:			
System Name:	IDU B-10,11(1.5 ton)	Econor	nizer:1	NA: <=54 kBtu/h cooling	Econom Contro		signed per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02		03	04		05	06	07	08
Fan Name or				Maximum Design Supply	Maximum Design Supply Airflow			Fan Power Pressure Drop	Adjustment - Table 140.4-F
Item Tag	Fan Functio	n	Qty	(CFM)	님님이 하면 없는 것이 있다면 전 경기에 가지 않는 것이 있다면 하면 하면 하면 있다. (14. Per		Design HP	Device	Design Airflow through Device (CFM)
VRF	Other (Transfer, V	AV box)	1	550		ВНР	0.1	NA NA	NA
Total Syst	Total System Design Supply Airflow (CFM):		1 550 1		ystem Desig (B)HP:	0.1	Maximum System Fan Power (B)HP:		
System Name:	IDU B-10,11(1.5 ton)	Econor	nizer:1	NA: <=54 kBtu/h cooling		Economizer Designed per §140.4(e) and Controls: (m)		System Fan Type:	Constant Volume
01	02		03	04		05	06	07	08
Fan Name or				Maximum Design Sunnly	Airflow			Fan Power Pressure Drop	Adjustment - Table 140.4-E
rail ivaline of	Fan Functio	n	Qty	Maximum Design Supply Airflow (CFM)		HP Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)
Item Tag									
Item Tag VRF	Other (Transfer, V	AV box)	1	550		ВНР	0.1	NA	NA

CERTIFICATE OF	COMPLIANCE								NRCC-MCH
Project Name:				Brix Mercer Baseme	ent Remodel Report	Page:	MARKET AND	M. M	(Page 17 of 3
Project Address:				1221 F	ulton Street Date P	repared:			3/4/20
I. SYSTEM CO	NTROLS								
ODU	3	Multi-zone w/ DDC to	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer	4 Hour Timer	EMCS	Included	Provided
nave setback th Notes: Control	ermostats. s with a * re			s, gravity room heater					
have setback th	ermostats. s with a * re §140.4(f)	vall heaters, gro	the space below		s, non-central elec				toves are not required to
have setback the Notes: Control EXCEPTION 1 to  J. VENTILATIO This table is use occupancies. Fo	ermostats. s with a * re §140.4(f)  N AND IND ed to demonstrations	equire a note in	ALITY  nce with mandate ion systems being		liance is achieved	EX: system 1: SA Te	emp Reset: Exempt	because zones compl	iant with §140.4(d);
have setback the Notes: Control EXCEPTION 1 to  J. VENTILATIO This table is use occupancies. Fo	ermostats. s with a * re §140.4(f)  N AND IND ed to demonstrations	equire a note in property of the property of t	ALITY  nce with mandate ion systems being y be shown on the	explaining how comp ory ventilation requires altered within the sco	s, non-central electrical electri	EX: system 1: SA Te and <u>\$120.2(e)3B</u> for application need to b ated in a spreadshee	emp Reset: Exempt all nonresidential, in the documented in the	because zones compl high-rise residential a his table. In lieu of this	iant with §140.4(d);  Ind hotel/motel  Is table, the required
have setback the Notes: Control EXCEPTION 1 to  J. VENTILATIO This table is use occupancies. For outdoor ventila	ermostats. s with a * re \$140.4(f)  N AND IND d to demonstrate alterations	equire a note in property of the property of t	ALITY  nce with mandate ion systems being y be shown on the ex if the project is	explaining how comp ory ventilation required altered within the sco	liance is achieved.  ments in §120.1 appe of the permit a cions can be presental culations on the	EX: system 1: SA Te	emp Reset: Exempt all nonresidential, in the documented in the	because zones compl high-rise residential a his table. In lieu of this	iant with §140.4(d);  Ind hotel/motel  Is table, the required
have setback the Notes: Control EXCEPTION 1 to J. VENTILATIO This table is use occupancies. Foo the Notes is the Notes is used to the N	ermostats. s with a * re \$140.4(f)  N AND INE ed to demon. or alterations tion rates ar	pall heaters, grandle property of the compliants, only ventialty and airflows may check the both check this bo	ALITY  nce with mandate ion systems being y be shown on the exif the project is exif the project in	explaining how comp ory ventilation require altered within the sca e plans or the calculation showing ventilation ca	ments in §120.1 appe of the permit of ions can be presented or Hotel/Motel s	EX: system 1: SA Te and <u>\$120.2(e)3B</u> for application need to be atted in a spreadshee plans, or attaching to paces	emp Reset: Exempt all nonresidential, in the documented in the	because zones compl high-rise residential a his table. In lieu of this	iant with §140.4(d);  Ind hotel/motel  Is table, the required

occupancies. For	alteration		ems being altered	within the sc	ope of the	permit app	lication nee	B for all nonresidential, and to be documented in the documente		
01		Check the box if the	project is showing	g ventilation o	calculations	on the pla	ns, or attac	hing the calculations ins	tead of completing this	table.
02	×	Check this box if the project included Nonresidential or Hotel/Motel spaces								
02		Check this box if the	k this box if the project included new or altered high-rise residential dwelling units.							
03		Check the box if the	project is using na	atural ventilat	tion in any	nonresiden	itial or hote	/motel spaces to meet	equired ventilation rat	es per <u>§120.1(c)2</u> .
Nonresidential ar	nd Hotel/	Motel Ventilation Sys	tems							
	0	4		05				06		07
			System Desi	gn ΩΔ CEM		System	Dosign		Air Filtration per §12	0.1(c) and §141.0(b)2
System Name		AH - B1	Airfle		1873		System Design Transfer Air CFM 0		Provided per §120.1(c) (NR and Hotel/Motel))	
08		09	10	11	12	13	14	15		16
		Mechanical Ven	tilation Required	per §120.1(c)	3 <sup>3</sup>		Exh. \	/ent per §120.1(c)4		
Space Name ot item Tag	c	occupancy Type <sup>4</sup>	Conditioned Floor Area (ft²)	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	[14] : [15] 이 10 전에 있는 10 전에 되었다면서 10 전에 있는 10 전에	ntrols per <u>§120.1(d)3</u> , and <u>§120.1(e)3</u> <sup>6</sup>
Z1 Mercer 202 - Meeting	Cor	nference/ meeting	3568			1784	0	0	DCV Provided per §120.1(d)4	
Room	-	mercine, meeting	3300			1704			Occ Sensor	NA: Not required space type
Registration Numb	er:				Registra	ation Date/T	ime:		Registr	ation Provider: Energysof

STATE OF CALIFORNIA  Mechanical Systems  NRCC-MCH-E		CALIFORNIA ENERGY COMMISSION
CERTIFICATE OF COMPLIANCE		NRCC-MCH-E
Project Name:	Brix Mercer Basement Remodel Report Page:	(Page 10 of 34)
Project Address:	1221 Fulton Street Date Prepared:	3/4/2022

System Name:	IDU B - 6,7,8,9,13,14,15,1 6 (2 ton)	Econor	mizer:1	NA: <=54 kBtu/h cooling	Econon		Designe	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02		03	04			05	06	07	08
Fan Name or				Maximum Design Supply	Airflow				Fan Power Pressure Drop	Adjustment - Table 140.4-E
Item Tag	Fan Function   Otv		Qty	(CFM)		HP Unit <sup>2</sup>		Design HP	Device	Design Airflow through Device (CFM)
VRF	Other (Transfer, V	AV box)	1	650		ВНР		0.1	NA L	NA
Total Sys	tem Design Supply A	irflow (CF	M):	650	Total S	ystem (B)HP:	Design	0.1	Maximum System Fan Power (B)HP:	
System Name:	IDU B - 17(cc 1.5 ton)	Econor	nizer:1	NA: <=54 kBtu/h cooling	Econon		Designe	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02		03	04			05	06	07	08
Fan Name or				Maximum Design Supply	Airflow				Fan Power Pressure Drop	Adjustment - Table 140.4-E
Item Tag	Fan Functio	n	Qty	(CFM)	Airriow	НР	Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)
VRF	Other (Transfer, V	AV box)	1	350		ı	ВНР	0.1	NA NA	NA
EF	Exhaust	7	1	0			ВНР	2	NA.	NA
Total Sys	tem Design Supply A	irflow (CF	M):	350		ystem (B)HP:	Design	2.1	Maximum System Fan Power (B)HP:	
System Name:	IDU B - 18 (HSW 1.5 ton)	Econor	nizer:1	NA: <=54 kBtu/h cooling	Econon		Designe	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02		03	04			05	06	07	08
Fan Name or				Maximum Design Supply	Airflow				Fan Power Pressure Drop	Adjustment - Table 140.4-E
Item Tag	Fan Functio	n	Qty	(CFM)	All HOW	НР	Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)
VRF	Other (Transfer, V	AV box)	1	400		1	ВНР	0.1	NA NA	NA
Total Sys	tem Design Supply A	irflow (CF	M):	400	Total S	ystem (B)HP:	Design	0.1	Maximum System Fan Power (B)HP:	

CALIFORNIA ENERGY COMMISSIO
NRCC-MCH
ort Page: (Page 13 of 3
Prepared: 3/4/202

Report Version: 2019.1.003

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

I. SYSTEM CONTROLS

Report Generated: 2022-03-04 09:13:03

System Name:	IDU B - 21 (1 ton)	Econon	nizer:1	NA: <=54 kBtu/h cooling	Contro		Designed	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02		03	04			05	06	07	08
Fan Name or				Maximum Dosiga Cupalu	Maximum Design Supply Airflow (CFM)				Fan Power Pressure Drop	Adjustment - Table 140.4-B
Item Tag	Fan Function	n	Qty				Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)
VRF	Other (Transfer, V	AV box)	1	400		E	ВНР	0.1	NA.	NA
Total System Design Supply Airflow (CFM):		M):	400 Total S		System Design (B)HP: 0.1		0.1	Maximum System Fan Power (B)HP:		
System Name:	IDU B - 6,7,8,9,13,14,15,1 6 (2 ton)	Econon	mizer:1	NA: <=54 kBtu/h cooling	Economi		Designed	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02		03	04			05 06		07	08
Fan Name or				Maximum Dacian Sunniu	A ! 6!				Fan Power Pressure Drop	Adjustment - Table 140.4-B
Item Tag	Fan Function	n	Qty	Maximum Design Supply (CFM)	Airnow	HP Unit <sup>2</sup>		Design HP	Device	Design Airflow through Device (CFM)
VRF	Other (Transfer, V/	AV box)	1	650		E	ЗНР	0.1	NA NA	NA
EF	Exhaust		1	0		E	ЗНР	0.1	NA	NA :
Total Syst	tem Design Supply A	irflow (CF	M):	650	Total Sy	stem I B)HP:		0.2	Maximum System Fan Power (B)HP:	

Registration Number:	Registration Date/Time:	Registration Provider: Energysoft
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance	Report Version: 2019.1.003 Schema Version: rev 20200601	Report Generated: 2022-03-04 09:13:03

Project Address:	1221 Fulton Street	Date Prepared:	3/4/202
Project Name:	Brix Mercer Basement Remodel	Report Page:	(Page 16 of 34
CERTIFICATE OF COMPLIANCE			NRCC-MCH-
NRCC-MCH-E			CALIFORNIA ENERGY COMMISSIO
Mechanical Systems			
STATE OF CALIFORNIA			

01	02	03	04	05	06	07	08	09
System Name	System Zoning	Conditioned Floor Area Being Served (ft <sup>2</sup> )	Thermostats \$110.2(b) & (c) <sup>1</sup> , \$120.2(a)or \$141.0(b)2E	Shut-Off Controls §120.2(e)	Isolation Zone Controls §120.2(g)	Demand Response §110.12 and §120.2(b)	Supply Air Temp. Reset §140.4(f)	Window Interlocks per §140.4(n)
AH - B1	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	NA: Serves humidity sensitive process	Provided
AH - B2	Multi-zone w/ DDC to zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	NA: Serves humidity sensitive process	Provided
AH - B3	Single zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	NA: Serves humidity sensitive process	Provided
AH - B4	Multi-zone w/ DDC to zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	NA: Serves humidity sensitive process	Provided
VRF ODU 1	Multi-zone w/ DDC to zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	NA: Serves humidity sensitive process	Provided
ODU 2	Multi-zone w/ DDC to zone	<= 25,000 ft <sup>2</sup>	Setback	Auto Timer Switch	4 Hour Timer	EMCS	Included	Provided

Registration Number:	Registration Date/Time:	Registration Provider: Ene
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance	Report Version: 2019.1.003 Schema Version: rev 20200601	Report Generated: 2022-03-04 09

Project Address:	1221 Fulton Street Date Prepared:	3/4/20
Project Name:	Brix Mercer Basement Remodel Report Page:	(Page 9 of
CERTIFICATE OF COMPLIANCE		NRCC-MCI
STATE OF CALIFORNIA  Mechanical Systems  NRCC-MCH-E		CALIFORNIA ENERGY COMMISSI

System Name:	IDU B - 6,7,8,9,13,14,15,1 6 (2 ton)	Economizer:1		Economizer:1		Economizer:1		NA: <=54 kBtu/h cooling	Economi Contro		Designed	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume
01	02		03	04			05	06	07	08				
Can Name or	In Name or Item Tag Fan Function Qty		Maximum Design Supply	Airflow				Fan Power Pressure Drop	Adjustment - Table 140.4-					
Item Tag			Qty	(CFM)	Altilow	HP	Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)				
VRF	VRF Other (Transfer, VAV box) 1		1	650			ВНР	0.1	NA NA	NA				
Total Syst	Total System Design Supply Airflow (CFM):		M):	650	Total Sy	stem (B)HP:	Design	0.1	Maximum System Fan Power (B)HP:					
System Name:	16 / X 9 13 14 15 1   Franchizer:		nizer:1	NA: <=54 kBtu/h cooling	Economi Contro		Designed	d per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume				
01	02		03	04			05	06	07	08				
Fan Name or				Maximum Design Supply	Airflow	inflam					Fan Power Pressure Drop	Adjustment - Table 140.4-		
Item Tag	Fan Function	Y	Qty	(CFM)	Airnow	HP	Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)				
VRF	Other (Transfer, VA	V box)	1	650		ВНР		HP 0.1	NA	NA .				
Total Syst	em Design Supply Ai	rflow (CF	M):	650	Total System Design (B)HP:		Design	0.1	Maximum System Fan Power (B)HP:					

istration Number:	Registration Date/Time:	
Building Energy Efficiency Standards - 2019 Nonresidential Compliance	Report Version: 2019.1.003 Schema Version: rev 20200601	

Mechanical Systems		
NRCC-MCH-E		CALIFORNIA ENERGY COMMISSION
CERTIFICATE OF COMPLIANCE		NRCC-MC
Project Name:	Brix Mercer Basement Remodel Report Page:	(Page 12 of 3
Project Address:	1221 Fulton Street Date Prepared:	3/4/20

System Name:	IDU B - 6,7,8,9,13,14,15,1 6 (2 ton)	Econor	nizer:1	NA: <=54 kBtu/h cooling	Economizer Controls:	Designe	ed per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume	
01	02		03	04		05 06		07	08	
Fan Name or				Maximum Design Supply	Airflow			Fan Power Pressure Drop	Adjustment - Table 140.4-E	
Item Tag	Fan Function	n	Qty	(CFM)	HP Unit <sup>2</sup> Design HP		Device	Design Airflow through Device (CFM)		
VRF	Other (Transfer, VA	AV box)	1	650	ВНР		0.1	NA	NA NA	
EF	Exhaust		1	0		ВНР		NA	NA NA	
Total Sys	tem Design Supply A	irflow (CF	M):	650	Total System (B)H		0.25	Maximum System Fan Power (B)HP:		
System Name:	IDU B - 6,7,8,9,13,14,15,1 6 (2 ton)	Econor	mizer:1	NA: <=54 kBtu/h cooling	Economizer Controls:	Designe	ed per <u>§140.4(e)</u> and (m)	System Fan Type:	Constant Volume	
01	02		03	04		05	06	07	08	
an Name or				Maximum Dasian Sunniu	Airflow		nít <sup>2</sup> Design HP	Fan Power Pressure Drop	Adjustment - Table 140.4-E	
Item Tag	Fan Function	1	Qty	Maximum Design Supply (CFM)	Airiow	HP Unit <sup>2</sup>		Device	Design Airflow through Device (CFM)	
VRF	Other (Transfer, VA	AV box)	3	1950		ВНР	0.1	NA	NA	
Total Sys	tem Design Supply Ai	rflow (CF	M):	1950	Total Syster (B)H	사람이 있는 경험 시간 사람이 없다.	0.3	Maximum System Fan Power (B)HP:		

Registration Number:	Registration Date/Time:	Registration Provider: Energysoft
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance	Report Version: 2019.1.003 Schema Version: rev 20200601	Report Generated: 2022-03-04 09:13:03

Project Address:	1221 Fulton Street Date Prepared:	3/4/2022
Project Name:	Brix Mercer Basement Remodel Report Page:	(Page 15 of 34)
CERTIFICATE OF COMPLIANCE		NRCC-MCH-E
NRCC-MCH-E		CALIFORNIA ENERGY COMMISSION
Mechanical Systems		
STATE OF CALIFORNIA		

System Name:	IDU B - 19 ( HSW 2 ton)	Econom	izer:1	I NA: <=54 kBtu/h cooling I		onomizer Designed per §140.4(e) and (m)		System Fan Type:	Constant Volume	
01	02		03			05	06	07	08	
Fan Name or								Fan Power Pressure Drop Adjustment - Table 14		
Item Tag	Fan Function		Qty	(CFM)	Airnow	HP Unit <sup>2</sup>	Design HP	Device	Design Airflow through Device (CFM)	
VRF	Other (Transfer, VA	V box)	1	625		BHP 0.1		NA.	NA	
Total Syst	tem Design Supply Air	rflow (CFI	۷):	1 6/5 1		em Design HP:	0.1	Maximum System Fan Power (B)HP:		

<sup>&</sup>lt;sup>1</sup> FOOTNOTES: Computer room economizers must meet requirements of §140.9(a) and will be documented on the NRCC-PRC-E document.

Registration Number: Registration Date/Time: Registration Provider: Energysoft

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Report Version: 2019.1.003 Schema Version: rev 20200601

Registration Date/Time: Registration Provider: Energysoft

Report Version: 2019.1.003
Schema Version: rev 20200601

APPROVED

03/17/2023

COUNTY OF FRESNO
DEVELOPMENT SERVICES





1222 M SHAW AVE. 559 FRESNO, CA 93711 info@muratoreasso

PROFESS PROFESS M2.35

Registration Provider: Energysoft

Report Generated: 2022-03-04 09:13:03



APPROVED

AU3 2 9 2024

FRESNO FIRE DEPARTMENT

<del></del>

DATE:	11/15/2022
SCALE:	As indicated

JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379

PROJECT:

FRESNO COUNTY DEPT OF

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:

TITLE 24 DOCUMENTS

SHEET NUMBER

M-12.2

<sup>&</sup>lt;sup>2</sup> The unit used for HP must be consistent for all fans within a system.

All others  All others  All others  All others  All others  Reception area t  Number: Energy Efficiency Standards - 2019 Nor  FORNIA ical Systems  OF COMPLIANCE e: ess:  TION AND INDOOR AIR QUALIT  All others  Total System Required Min OA 0  04  ODU 3	System Decading Conditioner Floor Area (ft²)  1042  1085  1096  500  500  Fesidential Compliance Compliance Compliance Conditioner Floor Area (ft²)  1010  FM  System Decading Compliance C	ossign OA CFM flow¹  11 d per §120.1(c d # of Shower heads/ toilets  ce	4763  12  13  # of people <sup>5</sup> Registra Report Schema	522 System Transfer 13 Required Min OA CFM 156.3  162.8 0 75 75 75 version: 203 a Version: re	18 Design Air CFM  14 Exh. V Required Min CFM  0  0  0  0  18 Design Air CFM  14 Exh. V Required Min CFM  0  18 Design Air CFM	Ventilation for this S 06  0  15 Vent per §120.1(c)4  Provided per Design CFM  0  0  0  Ventilation for this S 06	Air Filtration per \$12 Provided per \$ Hote  DCV or Sensor Co \$120.1(d)5, i  DCV  Occ Sensor	Yes  O7  20.1(c) and §141.0(b)2 <sup>2</sup> §120.1(c) (NR and I/Motel))  16  Introls per §120.1(d)3, and §120.1(e)3 <sup>6</sup> NA: Not required per §120.1(d)3  NA: Not required per §120.1(d)3
Total System Required Min OA 1  O4  The OP OP Mechanical 1  O9 Mechanical 1  All others  All others  All others  All others  All others  All others  Total Systems  OF COMPLIANCE  e:  Pess:  TION AND INDOOR AIR QUALIT  All others  Total System Required Min OA 0  O4  The ODU 3  O9  Mechanical 1  OP  Mechanical 1  Conference/ meeting	System Dec Aird  10 entilation Required (ft²)  1042  1085  1096  500  500  residential Compliant  The Aird  System Dec Aird  100 entilation Required (Conditioned Conditioned	sign OA CFM flow¹  11 d per §120.1(c d # of Shower heads/ toilets  ce  x Mercer Basen 1221  05 sign OA CFM flow¹	Registra Report Schema	System Transfer  13  Required Min OA CFM  156.3  162.8  0  75  75  version: 201 a Version: re  Report Palet Date Preport  16.5  1311  System	Design Air CFM  14 Exh. V Required Min CFM  0  0  0  0  ime: 9.1.003 v 20200601  ge: ared:	0  15 Vent per §120.1(c)4  Provided per Design CFM  0  0  0  Ventilation for this S	Air Filtration per \$12 Provided per \$ Hote  DCV or Sensor Co \$120.1(d)5, i  DCV  Occ Sensor	07 20.1(c) and §141.0(b)2 <sup>2</sup> §120.1(c) (NR and II/Motel)) 16  Introls per §120.1(d)3, and §120.1(e)3 <sup>6</sup> NA: Not required per §120.1(d)3
Mechanical	System Dec Airi  10 entilation Required Conditioned Floor Area (ft²)  1042  1085  1096  500  500  Fesidential Compliance  The Conditioned	sign OA CFM flow¹  11 d per §120.1(c d # of Shower heads/ toilets  ce  x Mercer Basen 1221  05 sign OA CFM flow¹	Registra Report Schema	System Transfer  13  Required Min OA CFM  156.3  162.8  0  75  75  version: 201 a Version: re  Report Palet Date Preport  16.5  1311  System	Design Air CFM  14 Exh. V Required Min CFM  0  0  0  0  ime: 9.1.003 v 20200601  ge: ared:	0  15 Vent per §120.1(c)4  Provided per Design CFM  0  0  0  Ventilation for this S	Air Filtration per \$12 Provided per \$ Hote  DCV or Sensor Co \$120.1(d)5, i  DCV  Occ Sensor	07 20.1(c) and §141.0(b)2 <sup>2</sup> §120.1(c) (NR and II/Motel)) 16  Introls per §120.1(d)3, and §120.1(e)3 <sup>6</sup> NA: Not required per §120.1(d)3
Mechanical Mechanical Mechanical Mechanical Mechanical Mall others  All others  All others  All others  All others  Reception area at Mumber: Energy Efficiency Standards - 2019 Normal Mechanical Mec	Airi  10 entilation Required Conditioned Floor Area (ft²)  1042  1085  1096  500  500  Fesidential Compliance  The system Desidential Conditioned Conditioned Conditioned Conditioned	flow¹  11 d per §120.1(c d # of Shower heads/ toilets  ce  x Mercer Basen 1221  05 sign OA CFM flow¹	Registra Report Schema	Required Min OA CFM  156.3  162.8  0  75  75  version: 201a Version: re  Report Palet Date Preport Palet Date Pale	Air CFM  14 Exh. V Required Min CFM  0  0  0  0  ime: -9.1.003 v 20200601  ge: ared:	Provided per Design CFM  0  0  0  Ventilation for this S	Provided per s Hote  DCV or Sensor Co \$120.1(d)5, s  DCV  Occ Sensor	\$120.1(c) (NR and I/Motel))  16  Introls per \$120.1(d)3, and \$120.1(e)3 6  NA: Not required per \$120.1(d)3
Mechanical Mechanical Mechanical Mechanical Mechanical Mall others  All others  All others  All others  All others  Reception area at Mumber: Energy Efficiency Standards - 2019 Normal Mechanical Mec	10 entilation Required Conditioned Floor Area (ft²)  1042  1085  1096  500  500  residential Compliant  The system Desidential Conditioned Conditioned Conditioned Conditioned	tolets  11 deper \$120.1(c) dep	Registra Report Schema	Required Min OA CFM  156.3  162.8  0  75  75  ation Date/T Version: 201 a Version: re  Report Pal t Date Prep	14 Exh. V Required Min CFM  0 0 0 0 0 ime: 9.1.003 v 20200601 ge: ared:  0 18	Provided per Design CFM  0  0  0  Ventilation for this S	DCV or Sensor Constant Sensor Constant Sensor DCV Occ Sensor CCV Occ Sensor CCV Occ Sensor CCV Occ Sensor CCV Occ Sensor CCALIFORNI CCALIFORNI DCV Occ Sensor CCALIFORNI DCV Occ	I/Motel))  16  Introls per \$120.1(d)3, and \$120.1(e)3 <sup>6</sup> NA: Not required per \$120.1(d)3
Mechanical	Condition Required (ft²)  1042  1085  1096  500  500  residential Compliance  The system Description Required Conditioned Conditioned Conditioned Conditioned Conditioned	d per §120.1(c d # of Shower heads/ toilets  ce  x Mercer Basen 1221  05 sign OA CFM flow <sup>1</sup>	Registra Report Schema	Required Min OA CFM  156.3  162.8  0  75  75  ation Date/T Version: 201a Version: re  Report Pal Date Prepi	Exh. V Required Min CFM  0  0  0  0  ime: 9.1.003 v 20200601  ge: ared:  0  18	Vent per §120.1(c)4  Provided per Design CFM  0  0  0  Ventilation for this S	S120.1(d)S, is  DCV  Occ Sensor  DCV  Occ Sensor  DCV  Occ Sensor  DCV  Occ Sensor  CALIFORNI  DCV  Occ Sensor	ntrols per \$120.1(d)3, and \$120.1(e)3 <sup>6</sup> NA: Not required per \$120.1(d)3  NA: Not required space type  NA: Not required per \$120.1(d)3
All others  All others  All others  All others  All others  All others  Reception area  Reception area  Number: Energy Efficiency Standards - 2019 Nor  FORNIA ical Systems  OF COMPLIANCE e: ess:  All others  Total System Required Min OA O  O4  OB  OB  OB  OB  OB  OB  OB  OB  O	Floor Area (ft²)  1042  1085  1096  500  500  Pesidential Compliance  The system Desidential Conditioned Condition	heads/ toilets  ce  x Mercer Basen 1221  05  sign OA CFM flow <sup>1</sup>	Registra Report Schema	Min OA CFM  156.3  162.8  0  75  75  ation Date/T Version: 201 a Version: re  Report Pal t Date Prep	0 0 0 0 0 0 ime: 9.1.003 v 20200601 ge: ared:	O O O O O O O O O O O O O O O O O O O	S120.1(d)S, is  DCV  Occ Sensor  DCV  Occ Sensor  DCV  Occ Sensor  DCV  Occ Sensor  CALIFORNI  DCV  Occ Sensor	NA: Not required per \$120.1(d)3
All others  All others  All others  All others  Reception area  Reception area  Number: Energy Efficiency Standards - 2019 Nor  FORNIA ical Systems  OF COMPLIANCE e: ess:  TION AND INDOOR AIR QUALIT  All others  Total System Required Min OA O  O4  OB  OB  OB  OB  OB  OCCUPANCY Type <sup>4</sup> Conference/ meeting	1042 1085 1096 500 500 Fesidential Compliance The system Description Required Conditioned Conditioned	os sign OA CFM	Registra Report Schema	156.3  162.8  0  75  75  ation Date/T Version: 201 a Version: re  Report Pa tt Date Prep	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	O O O O O O O Ventilation for this S	Occ Sensor  DCV Occ Sensor  DCV Occ Sensor  DCV Occ Sensor  CALIFORNI  DCV Occ Sensor	S120.1(d)3  NA: Not required space type  NA: Not required per \$120.1(d)3
All others  All others  All others  All others  Reception area  Reception area  Number: Energy Efficiency Standards - 2019 Nor  FORNIA ical Systems  OF COMPLIANCE e: ess:  TION AND INDOOR AIR QUALIT  All others  Total System Required Min OA O  O4  OB  OB  OB  OB  OB  OCCUPANCY Type <sup>4</sup> Conference/ meeting	1085  1096  500  500  Fesidential Compliance  110  FM  System Des Airf  10  Conditioned  Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	162.8  0  75  75  ation Date/T Version: 201 a Version: re  Report Pal tt Date Prep	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	O O O O Ventilation for this S	Occ Sensor  DCV Occ Sensor  DCV Occ Sensor  DCV Occ Sensor  CALIFORNI  DCV Occ Sensor	S120.1(d)3  NA: Not required space type  NA: Not required per \$120.1(d)3
All others  d Reception area tt  d Reception area tt  n Number: Energy Efficiency Standards - 2019 Nor compliance e: ess:  TION AND INDOOR AIR QUALITY  All others  Total System Required Min OA (O)  O4  O9  Mechanical Vale  OCCUPANCY Type <sup>4</sup>	1096  500  500  Fesidential Compliance  Brit  110  FM  System Des Airf  10  entilation Required  Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	75 75 75 ation Date/T Version: 201 a Version: re  Report Pa tt Date Prep	0 0 0 ime: 9.1.003 v 20200601 ge: ared: 0 18	O O O Ventilation for this S	DCV Occ Sensor DCV Occ Sensor DCV Occ Sensor DCV Occ Sensor Registr Report General CALIFORNI DCV Occ Sensor	space type  NA: Not required per \$120.1(d)3
All others  d Reception area tt  d Reception area tt  n Number: Energy Efficiency Standards - 2019 Nor compliance e: ess:  TION AND INDOOR AIR QUALITY  All others  Total System Required Min OA (O)  O4  O9  Mechanical Vale  OCCUPANCY Type <sup>4</sup>	1096  500  500  Fesidential Compliance  Brit  110  FM  System Des Airf  10  entilation Required  Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	75 75 75 ation Date/T Version: 201 a Version: re  Report Pa tt Date Prep	0 0 0 ime: 9.1.003 v 20200601 ge: ared: 0 18	O O O Ventilation for this S	Occ Sensor  DCV Occ Sensor  DCV Occ Sensor  DCV Occ Sensor  Registr  Report General  CALIFORNI  DCV Occ Sensor	S120.1(d)3  NA: Not required space type  NA: Not required per \$120.1(d)3  NA: Not required space type  ration Provider: Energysoft ated: 2022-03-04 09:13:03  IA ENERGY COMMISSION NRCC-MCH-1 (Page 23 of 34 3/4/202; Page 23 of 34 3/4/202; Page 24 3 NA: Not required per \$120.1(d)3  NA: Not required per \$120.1(d)3  NA: Not required space type
d doy Reception area to do	500  500  Fesidential Compliance  Brit  110  FM  System Desidential To Required Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	75 75 75 75 Ation Date/T Version: 201 a Version: re Report Pal tt Date Preport 16.5 1311 System	0 0 ime: .9.1.003 v 20200601 ge: ared:	0  0  Ventilation for this S	Occ Sensor  DCV Occ Sensor  Registr Report General  CALIFORNI  DCV Occ Sensor	S120.1(d)3  NA: Not required space type  NA: Not required per \$120.1(d)3  NA: Not required per \$120.1(d)3  NA: Not required per \$120.1(d)3  NA: Not required space type  ration Provider: Energysoft ated: 2022-03-04 09:13:03  IA ENERGY COMMISSION NRCC-MCH-1 (Page 23 of 34 3/4/2023)  NA: Not required per \$120.1(d)3  NA: Not required space type
Reception area  Reception area	500  residential Compliance  Brit  110  System Des Airf  10  entilation Required  Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	75 ation Date/T Version: 201 a Version: re Report Pa tt Date Prep	0 ime: .9.1.003 v 20200601 ge: ared:	0  Ventilation for this S	Occ Sensor  DCV Occ Sensor  Registr Report General  CALIFORNI  DCV Occ Sensor	NA: Not required per \$120.1(d)3  NA: Not required space type  NA: Not required per \$120.1(d)3  NA: Not required space type  ration Provider: Energysoft ated: 2022-03-04 09:13:03  IA ENERGY COMMISSION NRCC-MCH-1 (Page 23 of 34 3/4/2023)  NA: Not required per \$120.1(d)3  NA: Not required space type
Reception area  Reception area	500  residential Compliance  Brit  110  System Des Airf  10  entilation Required  Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	75 ation Date/T Version: 201 a Version: re Report Pa tt Date Prep	0 ime: .9.1.003 v 20200601 ge: ared:	0  Ventilation for this S	DCV Occ Sensor Registr Report General CALIFORNI DCV Occ Sensor ystem Complies?	NA: Not required space type  NA: Not required per \$120.1(d)3  NA: Not required space type  ration Provider: Energysoft ated: 2022-03-04 09:13:03  IA ENERGY COMMISSION NRCC-MCH-1 (Page 23 of 34 3/4/2022)  NA: Not required per \$120.1(d)3  NA: Not required space type
Reception area  Number: Energy Efficiency Standards - 2019 Nor  FORNIA ical Systems  OF COMPLIANCE e: ress:  TION AND INDOOR AIR QUALIT  All others  Total System Required Min OA 0  04  ODU 3  OP  Mechanical V  De  Grouperence/meeting	Brit 110  System Des Airf 10  entilation Required Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	ation Date/T Version: 201 a Version: re Report Pa tt Date Prep	o 18	0 Ventilation for this S	DCV Occ Sensor Registr Report General CALIFORNI DCV Occ Sensor ystem Complies?	NA: Not required per \$120.1(d)3  NA: Not required space type  ration Provider: Energysoft ated: 2022-03-04 09:13:03  IA ENERGY COMMISSION NRCC-MCH-1 (Page 23 of 34 3/4/2022)  NA: Not required per \$120.1(d)3  NA: Not required space type
Reception area  Number: Energy Efficiency Standards - 2019 Nor  FORNIA ical Systems  OF COMPLIANCE e: ess:  TION AND INDOOR AIR QUALIT  All others  Total System Required Min OA 0  04  ODU 3  OP  Mechanical Nor  Conference/ meeting	Brit 110  System Des Airf 10  entilation Required Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	ation Date/T Version: 201 a Version: re Report Pa tt Date Prep	o 18	0 Ventilation for this S	Occ Sensor  Registr  Report General  CALIFORNI  DCV  Occ Sensor  ystem Complies?	S120.1(d)3  NA: Not required space type  ration Provider: Energysoft ated: 2022-03-04 09:13:03  IA ENERGY COMMISSIOI NRCC-MCH-(Page 23 of 34 3/4/202:  NA: Not required per \$120.1(d)3  NA: Not required space type
Energy Efficiency Standards - 2019 Nor  FORNIA  ical Systems  OF COMPLIANCE e: ess:  ITION AND INDOOR AIR QUALIT  All others  Total System Required Min OA (  04  04  09  Mechanical (  10  10  10  10  10  10  10  10  10  1	FM System Des Airf 10 entilation Required Conditioned	x Mercer Basen 1221 05 sign OA CFM	Report Schema	Version: 201 a Version: re  Report Pa tt Date Prep	9.1.003 v 20200601 ge: ared:	Ventilation for this S	CALIFORNI  DCV  Occ Sensor  ystem Complies?	IA ENERGY COMMISSION NRCC-MCH-I (Page 23 of 34 3/4/2023  NA: Not required per §120.1(d)3  NA: Not required space type
FORNIA  ical Systems  OF COMPLIANCE e: ess:  ITION AND INDOOR AIR QUALIT  All others  Total System Required Min OA 0  O4  The ODU 3  O9  Mechanical Value  George Occupancy Type <sup>4</sup> Conference/ meeting	FM System Des Airf 10 entilation Required Conditioned	x Mercer Basen 1221 05 sign OA CFM	Schema	Report Palt Date Preport Palt 16.5	v 20200601  ge: ared:  0  18	Ventilation for this S	DCV Occ Sensor ystem Complies?	NA: Not required per \$120.1(d)3  NA: Not required per \$120.2(d)3
ical Systems  OF COMPLIANCE e: ress:  TION AND INDOOR AIR QUALIT  All others  Total System Required Min OA 0  O4  OB  OB  Mechanical V  De  G  Conference/ meeting	System Des Airf  10 entilation Required Conditioned	05 Sign OA CFM	nent Remode	Report Part Date Preport Part Date Part Date Preport Part Date Preport Part Date Preport Part Date Part Date Preport Part Date Preport Part Date Preport Part Date Part Date Preport Part Date Part Da	ge: ared:  0 18 Design	Ventilation for this S	DCV Occ Sensor ystem Complies?	NRCC-MCH-I (Page 23 of 34 3/4/2022  NA: Not required per §120.1(d)3  NA: Not required space type
ical Systems  OF COMPLIANCE e: ress:  TION AND INDOOR AIR QUALIT  All others  Total System Required Min OA 0  O4  OB  OB  Mechanical V  De  G  Conference/ meeting	System Des Airf  10 entilation Required Conditioned	05 Sign OA CFM	Fulton Stree	16.5 1311 System	0 18 Design	Ventilation for this S	DCV Occ Sensor ystem Complies?	NRCC-MCH-I (Page 23 of 34 3/4/2022  NA: Not required per §120.1(d)3  NA: Not required space type
OF COMPLIANCE e: ess:  All others  Total System Required Min OA 0  O4  OB  OB  Mechanical V  Conference/ meeting	System Des Airf  10 entilation Required Conditioned	05 Sign OA CFM	Fulton Stree	16.5 1311 System	0 18 Design	Ventilation for this S	DCV Occ Sensor ystem Complies?	NRCC-MCH-I (Page 23 of 34 3/4/2022  NA: Not required per §120.1(d)3  NA: Not required space type
e:  ress:  All others  Total System Required Min OA 0  04  ODU 3  O9  Mechanical V  ne  Occupancy Type <sup>4</sup> Conference/ meeting	System Des Airf  10 entilation Required Conditioned	05 Sign OA CFM	Fulton Stree	16.5 1311 System	0 18 Design	Ventilation for this S	Occ Sensor ystem Complies?	NA: Not required per §120.1(d)3  NA: Not required space type
All others  Total System Required Min OA 0  O4  OB  OB  Mechanical V  Conference/ meeting	System Des Airf  10 entilation Required Conditioned	05 sign OA CFM		16.5 1311 System	0 18	Ventilation for this S	Occ Sensor ystem Complies?	NA: Not required per §120.1(d)3  NA: Not required space type
All others  Total System Required Min OA 0  04  ne ODU 3  09  Mechanical V  ne Gonference/ meeting	System Des Airf  10 entilation Required Conditioned	sign OA CFM	898	1311 System	18 Design	Ventilation for this S	Occ Sensor ystem Complies?	§120.1(d)3  NA: Not required space type
Total System Required Min OA 0  04  ne ODU 3  09  Mechanical V  ne Gonference/ meeting	System Des Airf  10 entilation Required Conditioned	sign OA CFM	898	1311 System	18 Design	Ventilation for this S	Occ Sensor ystem Complies?	§120.1(d)3  NA: Not required space type
04  me ODU 3  09  Mechanical V  ne g Occupancy Type <sup>4</sup> Conference/ meeting	System Des Airf  10 entilation Required Conditioned	sign OA CFM	898	System	Design	Ventilation for this S	ystem Complies?	space type
04  me ODU 3  09  Mechanical V  ne g Occupancy Type <sup>4</sup> Conference/ meeting	System Des Airf  10 entilation Required Conditioned	sign OA CFM	898	System	Design			Vos
ODU 3  O9  Mechanical \ Occupancy Type <sup>4</sup> Conference/ meeting	10 entilation Required Conditioned	sign OA CFM	898		Design			07
09  Mechanical \ ne  Google Occupancy Type <sup>4</sup>	10 entilation Required Conditioned	low <sup>1</sup>	898				Air Filtration per §12	20.1(c) and §141.0(b)2 2
Mechanical \ ne  B Occupancy Type <sup>4</sup> Conference/ meeting	entilation Required	11			Air CFM	0		1/Motel))
Occupancy Type <sup>4</sup>	Conditioned	ner 6120 1/c	12	13	14 Fxh \	15 /ent per §120.1(c)4		16
Conference/ meeting	· FIGUR DEDS	# of Shower	# of	Required	Required	Provided per Design		ntrols per <u>§120.1(d)3</u> , and <u>§120.1(e)3</u> <sup>6</sup>
Conterence/ meeting	(ft²)	heads/ toilets	people <sup>5</sup>	Min OA CFM	Min CFM	CFM	91ZU.1(0)5, 8	
1	435			217.5	0	0	DCV Occ Sensor	NA: Not required per \$120.1(d)3 NA: Not required space type
							DCV	NA: Not required per
e Conference/ meeting	448			224	0	0	Occ Sensor	§120.1(d)3  NA: Not required
								space type  NA: Not required per
All others	197			29.6	0	0	DCV	§120.1(d)3 NA: Not required
Total System Required Min OA O	- L			471	18	Ventilation for this S	Occ Sensor	space type Yes
ES: System CFM should include both		tural ventilati	ion for the z			ventuation for this 5	/stem compiles r	Tes
Number: Energy Efficiency Standards - 2019 Non ORNIA ical Systems	esidential Compliand	ce	Report	ation Date/Ti Version: 201 Version: rev	9.1.003			ation Provider: Energysoft ated: 2022-03-04 09:13:03
OF COMPLIANCE							CALIFORNI	A ENERGY COMMISSION
e: ess:	Brix	Mercer Basem	nent Remode Fulton Street				ata di santa di salah	(Page 26 of 34)
		****	- Julie					377/2022
UTION (DUCTWORK and PIPING		onditioned spa	aces					
The scope	f the project includ	des extending	an existing			constructed, insulated or		
and diagno	tic testing in accor	dance with pr	rocedures in	the Refere	nce Nonres	to have been previously s sidential Appendix NA2.	ealed as confirmed th	nrough field verification
Yes Duct system s to the questions below apply to the	shall be sealed in		th the Califo	-		leakage testing triggered	for these systems?	l No
No The scope	f the project includ	des only duct s	systems ser	ving health	care facilitie	es		I NO
	provides condition		_			olume, single zone, space- area.	conditioning system.	
No The combin	ed surface area of					n 25% of the total surface	area of the entire du	ct system:
						nan the u-factor of the cei		
	requirements		1B or if the			r openings to the outside/		
	In other unco	onditioned spa	aces					
					****	constructed, insulated or s to have been previously s		
THE COURT		dance with pr	ocedures in	the Refere	nce Nonres	sidential Appendix NA2.		
and diagno		stems:	AH - I	B4	Duct	leakage testing triggered	for these systems?	No
and diagno Yes Duct system to the questions below apply to the		les only duct s				es lume, single zone, space-o	conditioning system	
and diagno Yes Duct system to the questions below apply to the No The scope of	f the project include	ned air to an c	F 3	<sup>2</sup> of conditi	oned floor			
and diagno Yes Duct system to the questions below apply to the No The scope No Duct system Yes The space of	f the project include provides condition anditioning system	serves less th			-1		area of the entire do	
and diagno Yes Duct system to the questions below apply to the No The scope No Duct system Yes The space of	f the project include provides condition anditioning system	serves less th		locations i	s more than	n 25% of the total surface	c. o. the entire du	ct system:

Registration Date/Time:

Report Version: 2019.1.003

Schema Version: rev 20200601

Registration Provider: Energysoft

Report Generated: 2022-03-04 09:13:03

Registration Number:

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

OF CALIFOR Chanica MCH-E	<sup>NIA</sup> al Systems							CALIFORN	IA ENERGY COMMISSI
	COMPLIANCE								NRCC-MC
ct Name: ct Address	1	Brix	Mercer Baser 1221	L Fulton Stree					(Page 19 of 3/4/2
						-			
NTILATIO	ON AND INDOOR AIR QUALITY	T		<b>.</b>	Γ	T		T	Provided per
Z3	Assembly- multiuse	2010			1005	0	0	Occ Sensor	9120.1(d)4 NA: Not required
17	Total System Required Min OA CFM	<u> </u>			1005	18	Ventilation for this		space type Yes
	04		05				06		07
n Name	AH - B4	System Desi Airfl		705		Design Air CFM	0	Provided per	20.1(c) and §141.0(b); §120.1(c) (NR and I/Motel))
08	09	10	11	12	13	14	15		16
Name	Mechanical Ventila				In	-	Vent per §120.1(c)4	DCV or Sensor Co	ntrols per <u>§120.1(d)3</u> ,
m Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft²)	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	네 그 이 이 그는 사람들이 하는 것이 되었다. 그런 그렇게 되었는데 하나 없었다.	and §120.1(e)3 <sup>6</sup>
ep Food	Restaurant Dining Rooms	400			200	0	550	DCV	NA: Not required p
ulling								Occ Sensor	NA: Not required
torage	All others	449			67.4	0	0	DCV	NA: Not required p §120.1(d)3
								Occ Sensor	NA: Not required space type
eakout	Conference/ meeting	175			87.5	0	0	DCV	Provided per <u>§120.1(d)4</u>
nom								Occ Sensor	NA: Not required space type
									NA: Not required p
by, Hall	All others	1113			167	0	0	DCV	§120.1(d)3
bby, Hall torage tration Nu uilding Ene	All Others Imber: ergy Efficiency Standards - 2019 Nonreside	1113		Report	167 ation Date/T Version: 201 version: re	19.1.003	0	Occ Sensor Registr	
bby, Hall torage tration Nu iilding Ene iiiding Ene iiiding Ene iiding Ene iiding Ene iiding Ene iiding Ene	All others  Imber: ergy Efficiency Standards - 2019 Nonreside			Report	ation Date/T	ime:	0	Occ Sensor Registi Report Gener	MA: Not required space type ration Provider: Energyscated: 2022-03-04 09:13:0
oby, Hall forage cration Nu ilding Ene f CALIFORI hanica CCH-E	All Others Imber: ergy Efficiency Standards - 2019 Nonreside	ntial Compliance	Mercer Basen	Report Schema	version: 201 version: re	ime: 19.1.003 v 20200601	0	Occ Sensor Registi Report Gener	MA: Not required space type ration Provider: Energyscated: 2022-03-04 09:13:0
oby, Hall orage  ration Nuilding Energy CALIFORI hanica CH-E ICATE OF: Name:	All others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  al Systems  COMPLIANCE	ntial Compliance	Mercer Basen	Report Schema	version: 201 Version: re	ime: 19.1.003 v 20200601	0	Occ Sensor Registi Report Gener	S120.1(d)3  NA: Not required space type  ration Provider: Energyscated: 2022-03-04 09:13:0
oby, Hall orage  ration Nuilding End  F CALIFORI  hanica  CH-E  ICATE OF  Name:	All others  Imber: ergy Efficiency Standards - 2019 Nonreside  NIA al Systems  COMPLIANCE	ntial Compliance	Mercer Basen	Report Schema	version: 201 Version: re	ime: 19.1.003 v 20200601	0	Occ Sensor Registi Report Gener	S120.1(d)3  NA: Not required space type  ration Provider: Energyscated: 2022-03-04 09:13:0  IA ENERGY COMMISSION NRCC-MCI (Page 22 of
ration Nu ilding End CALIFORI CATE OF Name: Address:	All others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  al Systems  COMPLIANCE	ntial Compliance	Mercer Basen	Report Schema	version: 201 Version: re	ime: 19.1.003 v 20200601	0	Occ Sensor Registi Report Gener	MA: Not required space type  ration Provider: Energyson ated: 2022-03-04 09:13:1  IA ENERGY COMMISSI NRCC-MCI (Page 22 of
oby, Hall orage ration Nu ilding Ene F CALIFORI hanica CH-E CATE OF Name:	All Others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  Al Systems  COMPLIANCE  :	ntial Compliance	Mercer Basen 1221 05 gn OA CFM	Report Schema	Version: 201 Version: rev	ime: 19.1.003 v 20200601 ge: ared:		Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §	\$120.1(d)3  NA: Not required space type  ration Provider: Energyso ated: 2022-03-04 09:13:0  IA ENERGY COMMISSI NRCC-MCI (Page 22 of 3/4/20)  07  00.1(c) and §141.0(b)3  120.1(c) (NR and
oby, Hall forage cration Nuilliding End hanical CH-E ICATE OF: Name: Address:	Imber: ergy Efficiency Standards - 2019 Nonreside NIA al Systems COMPLIANCE : DN AND INDOOR AIR QUALITY 04	ntial Compliance Brix System Desi	Mercer Basen 1221 05 gn OA CFM	Report Schema nent Remode Fulton Street	Version: 201 Version: rev	ime: 19.1.003 v 20200601 ge: ared:	06	Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §	S120.1(d)3  NA: Not required space type  ration Provider: Energyscated: 2022-03-04 09:13:0  IA ENERGY COMMISSIN NRCC-MCI (Page 22 of 3/4/20)  07  00.1(c) and §141.0(b)2
oby, Hall orage ration Nuilding Energy CALIFORN hanica CH-E ICATE OF Name: Address: ITILATIC	All others  Imber: ergy Efficiency Standards - 2019 Nonreside  NIA Al Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2	Brix System Designation 10 tion Required	05 gn OA CFM ow <sup>1</sup> 11 per §120.1(c)	Report Schema	Report Pal Date Preport	ime: 19.1.003 v 20200601 ge: ared: Design Air CFM	06 0	Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §  Hote	S120.1(d)3  NA: Not required space type  ration Provider: Energyson ated: 2022-03-04 09:13:1  IA ENERGY COMMISSI  NRCC-MCI  (Page 22 of 3/4/20  07  0.1(c) and §141.0(b)2  120.1(c) (NR and //Motel))
oby, Hall orage ration Nuilding Energy Hanica CH-E ICATE OF: Address: Address: ITILATIC IN Name	All others  Imber: ergy Efficiency Standards - 2019 Nonreside  NIA Al Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09	Brix System Designation	05 gn OA CFM ow <sup>1</sup> 11 per §120.1(c)	Report Schema	Report Pal t Date Preparents	ime: 19.1.003 v 20200601 ge: ared: Design Air CFM	06 0 15	Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §  Hote	S120.1(d)3  NA: Not required space type  ration Provider: Energyso ated: 2022-03-04 09:13:0  IA ENERGY COMMISSI NRCC-MCI (Page 22 of 3/4/20)  07  00.1(c) and §141.0(b)2  i120.1(c) (NR and /Motel))
poby, Hall forage ration Nuilliding Energy Hanica CH-E ICATE OF: Address: Address: TILATIC Name Name	All Others  Imber: ergy Efficiency Standards - 2019 Nonreside  NIA al Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila  Occupancy Type <sup>4</sup>	Brix  System Designation Required Floor Area (ft²)	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/	Report Schema	System Transfer  13  Required Min OA CFM	ge: ared: Design Air CFM  14 Exh. V  Required Min CFM	06 0 15 Vent per §120.1(c)4 Provided per Design CFM	Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §  Hote	\$120.1(d)3  NA: Not required space type  ration Provider: Energysolated: 2022-03-04 09:13:1  IA ENERGY COMMISSI  NRCC-MCI  (Page 22 of 3/4/20  07  07  00.1(c) and §141.0(b)3  120.1(c) (NR and l/Motel))  16  NA: Not required p §120.1(d)3
oby, Hall forage cration Nuilliding End	All others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  All Systems  COMPLIANCE  :  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila	System Designation Required Floor Area	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/	Report Schema	Version: 201 Version: rev  Report Pal t Date Preport  System Transfer  13  Required Min OA	ge: Design Air CFM  14 Exh.	06 0 15 Vent per <u>\$120.1(c)4</u> Provided per Design	Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §  Hote  DCV or Sensor Col §120.1(d)5, 3	\$120.1(d)3  NA: Not required space type  ration Provider: Energysolated: 2022-03-04 09:13:1  IA ENERGY COMMISSI NRCC-MCI (Page 22 of 3/4/20  07  00.1(c) and §141.0(b)3  i120.1(c) (NR and l/Motel))  16  NA: Not required p §120.1(d)3, and §120.1(e)3 6
oby, Hall orage ration Nu ilding Ene F CALIFORE HANICA CH-E ICATE OF Name: Address: ITILATIC IN Name Name Name Name Name Name Name Name	All Others  Imber: ergy Efficiency Standards - 2019 Nonreside  NIA al Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila  Occupancy Type <sup>4</sup>	Brix  System Designation Required Floor Area (ft²)	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/	Report Schema	System Transfer  13  Required Min OA CFM	ge: ared: Design Air CFM  14 Exh. V  Required Min CFM	06 0 15 Vent per §120.1(c)4 Provided per Design CFM	Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §  Hote  DCV or Sensor Cor  §120.1(d)5, i	\$120.1(d)3  NA: Not required space type  ration Provider: Energysolated: 2022-03-04 09:13:1  IA ENERGY COMMISSI  NRCC-MCI  (Page 22 of 3/4/20  07  00.1(c) and §141.0(b)3  i120.1(c) (NR and 1/Motel))  16  NA: Not required p  §120.1(d)3  NA: Not required p  §120.1(d)3
oby, Hall orage ration Nu ilding Ene F CALIFORN hanica CH-E ICATE OF Name: Address: ITILATIC IN Name Name Name Name Name Name	All Others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  All Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila  Occupancy Type <sup>4</sup> Office space	System Designation Required Floor Area (ft²)	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/ toilets	Report Schema	System Transfer  13  Required Min OA CFM  216.8	Design Air CFM  14 Exh. V Required Min CFM	06 0 15 Vent per §120.1(c)4 Provided per Design CFM 0	Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §  Hote  DCV or Sensor Cor  §120.1(d)5, ii  DCV  Occ Sensor	\$120.1(d)3  NA: Not required space type  ration Provider: Energysolated: 2022-03-04 09:13:1  IA ENERGY COMMISSI  NRCC-MCI  (Page 22 of 3/4/20  07  00.1(c) and §141.0(b)2  120.1(c) (NR and //Motel))  16  NA: Not required p §120.1(d)3
poby, Hall forage ration Nu ilding Ene F CALIFORI hanica CH-E ICATE OF I Name: Address: Address: TILATIC In Name Pm Tag	All Others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  All Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila  Occupancy Type <sup>4</sup> Office space	System Designation Required Floor Area (ft²)	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/ toilets	Report Schema	System Transfer  13  Required Min OA CFM  216.8	Design Air CFM  14 Exh. V Required Min CFM	06 0 15 Vent per §120.1(c)4 Provided per Design CFM 0	Occ Sensor  Registr  Report Gener  CALIFORN  Air Filtration per §12  Provided per §  Hote  DCV or Sensor Cor  §120.1(d)5, ii  DCV  Occ Sensor  DCV	\$120.1(d)3  NA: Not required space type  ration Provider: Energysolated: 2022-03-04 09:13:1  NA: ENERGY COMMISSI  NRCC-MCI  (Page 22 of 3/4/20  07  00.1(c) and \$141.0(b)2  1120.1(c) (NR and /Motel))  16  NA: Not required p \$120.1(d)3  NA: Not required space type  NA: Not required p \$120.1(d)3
oby, Hall orage ration Nu ilding Ene F CALIFORI hanica CH-E ICATE OF Name: Address: ITILATIC In Name 108	All others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  All Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila  Occupancy Type <sup>4</sup> Office space  Toilet, public	System Designation Required (ft²)  1045  1445	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/ toilets	Report Schema	System Transfer  13  Required Min OA CFM  216.8	Design Air CFM  14  Exh. V  Required Min CFM  0  350	06  15 Vent per \$120.1(c)4  Provided per Design CFM  0  600	Air Filtration per \$1.2  Provided per \$1.2  DCV or Sensor Co. \$120.1(d)5, i. DCV  Occ Sensor  DCV  Occ Sensor	S120.1(d)3  NA: Not required space type  Tation Provider: Energyson ated: 2022-03-04 09:13:1  NA: ENERGY COMMISSI NRCC-MCI (Page 22 of 3/4/20)  O7  O1(c) and \$141.0(b)2  \$120.1(c) (NR and /Motel))  NA: Not required p \$120.1(d)3  NA: Not required space type  NA: Not required p \$120.1(d)3
oby, Hall orage ration Nu ilding End F CALIFORI hanica CH-E ICATE OF Name: Address: Address: TILATIC IN Name IN Tag III III III III III III III III III I	All others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  All Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila  Occupancy Type <sup>4</sup> Office space  Toilet, public	System Designation Required (ft²)  1045  1445	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/ toilets	Report Schema	System Transfer  13  Required Min OA CFM  216.8	Design Air CFM  14  Exh. V  Required Min CFM  0  350	06  15 Vent per \$120.1(c)4  Provided per Design CFM  0  600	Air Filtration per §1.  Provided per § Hote  DCV or Sensor Col §120.1(d)5, i  DCV  Occ Sensor  DCV  Occ Sensor  DCV	S120.1(d)3  NA: Not required space type  Tation Provider: Energyson ated: 2022-03-04 09:13:1  NA: ENERGY COMMISSI NRCC-MCI (Page 22 of 3/4/20)  O7  O1(c) and \$141.0(b);  \$120.1(c) (NR and /Motel))  NA: Not required p \$120.1(d)3  NA: Not required space type  NA: Not required p \$120.1(d)3
poby, Hall forage ration Nuilliding Energy Hanica CH-E ICATE OF: Address: Address: TILATIC Name Name	All others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  all Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila  Occupancy Type <sup>4</sup> Office space  Toilet, public  Break room	System Designation Required (True)  Conditioned Floor Area (ft²)  1445  633	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/ toilets	Report Schema	System Transfer  13  Required Min OA CFM  216.8  0  959.5	Design Air CFM  14 Exh. V Required Min CFM  0  350	06 0 15 Vent per §120.1(c)4 Provided per Design CFM 0 600	Air Filtration per §12 Provided per § Hote  DCV or Sensor  DCV  Occ Sensor  DCV  Occ Sensor  DCV  Occ Sensor	S120.1(d)3  NA: Not required space type  Tation Provider: Energyson ated: 2022-03-04 09:13:1  NA: ENERGY COMMISSI NRCC-MCI (Page 22 of 3/4/20)  O7  O1(c) and §141.0(b)2  1120.1(c) (NR and /Motel))  NA: Not required p §120.1(d)3  NA: Not required space type  NA: Not required p §120.1(d)3
oby, Hall orage ration Nu ilding End CALIFORI hanica CH-E CATE OF Name: Address: TILATIO n Name m Tag	All others  Imber:  ergy Efficiency Standards - 2019 Nonreside  NIA  all Systems  COMPLIANCE  DN AND INDOOR AIR QUALITY  04  ODU 2  09  Mechanical Ventila  Occupancy Type <sup>4</sup> Office space  Toilet, public  Break room	System Designation Required (True)  Conditioned Floor Area (ft²)  1445  633	Mercer Basen 1221 05 gn OA CFM ow¹ 11 per §120.1(c) # of Shower heads/ toilets	Report Schema	System Transfer  13  Required Min OA CFM  216.8  0  959.5	Design Air CFM  14 Exh. V Required Min CFM  0  350	06 0 15 Vent per §120.1(c)4 Provided per Design CFM 0 600	Air Filtration per §12 Provided per § Hote  DCV or Sensor  DCV  Occ Sensor  DCV  Occ Sensor  DCV  Occ Sensor  DCV  Occ Sensor  DCV	S120.1(d)3  NA: Not required space type  Tation Provider: Energyson ated: 2022-03-04 09:13:1  NA: ENERGY COMMISSI NRCC-MCI (Page 22 of 3/4/20)  O7  O1(c) and \$141.0(b)2  1120.1(c) (NR and /Motel))  NA: Not required p \$120.1(d)3  NA: Not required space type  NA: Not required p \$120.1(d)3  NA: Not required p \$120.1(d)3

C	00113	System Desi	gn OA CFM	2007	System	Design		•	20.1(c) and §141.0(b)2
System Name	ODU 2	Airflo	ow <sup>1</sup>	2987		Air CFM	0		§120.1(c) (NR and el/Motel))
08	09	10	11	12	13	14	15		16
	Mechanical Ve	ntilation Required	per §120.1(c)	3 <sup>3</sup>		Exh. \	Vent per §120.1(c)4		
Space Name ot item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft²)	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM		ntrols per <u>§120.1(d)3</u> , and <u>§120.1(e)3</u> <sup>6</sup>
B12	Office space	1445			216.8	0	0	DCV	NA: Not required pe §120.1(d)3
BIZ	Office space	1443			210.8		O	Occ Sensor	NA: Not required space type
B13	Toilet, public	633	5		0	350	600	DCV	NA: Not required pe §120.1(d)3
B13	ionet, public	033	3		0	330	600	Occ Sensor	NA: Not required space type
B14-16	Break room	1919			959.5	0	0	DCV	NA: Not required pe 5120.1(d)3
614-10	break room	1919			959.5		0	Occ Sensor	NA: Not required space type
B21	Corridor	295			44.2	0	0	DCV	NA: Not required pe §120.1(d)3
521	Corridor	295			44.2		U	Occ Sensor	NA: Not required space type
B22	Corridor	492			73.8	0	275	DCV	NA: Not required pe §120.1(d)3
522	Corridor	492			/3.0		2/3	Occ Sensor	NA: Not required space type

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance	Report Version: 2019.1.003 Schema Version: rev 20200601	Report Generated: 2022-03-04 09:13:03
STATE OF CALIFORNIA		
Mechanical Systems		
NRCC-MCH-E		CALIFORNIA ENERGY COMMISSIO
CERTIFICATE OF COMPLIANCE		NRCC-MCH-

Brix Mercer Basement Remodel Report Page:

L. DISTRIBUTION							
		iance with manda	tory pipe insulation requirem	ents found in §120.3	and p	prescriptive requirements found in <u>§140.4(I)</u> for duct leakage t	esting.
Duct Leakage Sea							
			following duct systems:	AH - B1		Duct leakage testing triggered for these systems?	No
11	No		the project includes only duct				
12	Yes	Duct system p	rovides conditioned air to an	occupiable space for	a con	stant volume, single zone, space-conditioning system.	
13	Yes	The space cor	ditioning system serves less t	han 5,000 ft <sup>2</sup> of cond	litione	ed floor area.	
14	No	The combined	surface area of the ducts in	the following location	is is m	nore than 25% of the total surface area of the entire duct syste	m:
			Outdoors				
						reater than the u-factor of the ceiling, or if the roof does not n vents or openings to the outside/ unconditioned spaces	neet the
			In an unconditioned craw	space			
			In other unconditioned sp	aces			
15		The scope of t	the project includes extending	g an existing duct syst	em, v	which is constructed, insulated or sealed with asbestos.	
16						mented to have been previously sealed as confirmed through a Nonresidential Appendix NA2.	field veri
17	Yes	Duct system s	hall be sealed in acordance w	ith the California Me	chanie	cal Code	
The answers to the	e questions be	low apply to the t	following duct systems:	AH - B2		Duct leakage testing triggered for these systems?	No
11	No	The scope of t	he project includes only duct	systems serving heal	thcar	e facilities	
12	No	Duct system p	rovides conditioned air to an	occupiable space for	a con	stant volume, single zone, space-conditioning system.	
13	Yes	The space con	ditioning system serves less t	than 5,000 ft <sup>2</sup> of cond	itione	ed floor area.	
14	No	The combined	surface area of the ducts in t	the following location	s is m	ore than 25% of the total surface area of the entire duct syste	m:
			Outdoors				
			In a space directly under a	a roof that has a U-far	ctor g	reater than the u-factor of the ceiling, or if the roof does not n	neet the
14	] NO		Outdoors  In a space directly under a	a roof that has a U-fac	ctor gr		oof does not m
			In an unconditioned craw	cnaco			

Registration Number:	Registration Date/Time:	Registration Provider: Energysoft
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance	Report Version: 2019.1.003	Report Generated: 2022-03-04 09:13:03

Schema Version: rev 20200601

STATE OF CALIFORN	AIA
Mechanica	Syste

(Page 25 of 34)

Micchailleal Systems		
NRCC-MCH-E		CALIFORNIA ENERGY COMMISSION
CERTIFICATE OF COMPLIANCE		NRCC-MCH-E
Project Name:	Brix Mercer Basement Remodel Report Page:	(Page 18 of 34)
Project Address:	1221 Fulton Street Date Prepared:	3/4/2022

17	Total System Required Min OA CF	М			1784	18	Ventilation for this	System Complies?	Yes	
	04		05				06		)7	
		System Desig	n OA CEM	1000	System	Design		Air Filtration per §120	0.1(c) and §141.0(b)2	
System Name	AH - B2		System Design OA CFM Airflow <sup>1</sup>		System Design Transfer Air CFM		0	Provided per §120.1(c) (NR and Hotel/Motel))		
08	09	10	11	12	13	14	15		16	
	Mechanical Ventilation Required per §120.1(c)3 3					Exh. \	Vent per §120.1(c)4			
Space Name ot item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft²)	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	그렇게 살아보니 하는 그 이번에 대한 사람들이 없는 것이 없다면 없었다.	trols per <u>§120.1(d)3</u> , and <u>§120.1(e)3</u> <sup>6</sup>	
Z2	Toilet, public	972	8		0	560	1000	DCV	Provided per §120.1(d)4	
22	ionet, public	3/2				300	1000	Occ Sensor	NA: Not required space type	
<b>Z2</b>	Corridor	658			98.7	0	0	DCV	Provided per §120.1(d)4	
	Comuo	030			36.7		Ü	Occ Sensor	NA: Not required space type	
17	Total System Required Min OA CF	М			99	18	Ventilation for this	System Complies?	Yes	
	04		05				06	07		
		System Desig	System Design OA CFM		System	Design		Air Filtration per §120.1(c) and §141.0(b)		
System Name	AH - B3	Airflo		1047	Transfer		0	Provided per §1 Hotel/	<u>20.1(c)</u> (NR and Motel))	
08	09	10	11	12	13	14	15	1	6	
	Mechanical Ver	ntilation Required p	per §120.1(c)	3 <sup>3</sup>		Exh. \	/ent per §120.1(c)4			
Space Name ot item Tag	Occupancy Type <sup>4</sup>	Conditioned Floor Area (ft²)	# of Shower heads/ toilets	# of people <sup>5</sup>	Required Min OA CFM	Required Min CFM	Provided per Design CFM	DCV or Sensor Cont §120.1(d)5, ar	rols per <u>§120.1(d)3</u> , ad <u>§120.1(e)3</u> <sup>6</sup>	

Registration Number:	
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance	

Registration Date/Time:

Registration Provider: Energysoft Report Generated: 2022-03-04 09:13:03

STATE OF CALIFORNIA **Mechanical Systems** NRCC-MCH-E

CALIFORNIA ENERGY COMMISSION NRCC-MCH-E Brix Mercer Basement Remodel Report Page: 1221 Fulton Street Date Prepared: (Page 21 of 34) 3/4/2022

B6	All others	696		104.4	0	0	DCV	NA: Not required per §120.1(d)3
ВО	All others	656		104.4		O	Occ Sensor	NA: Not required space type
B7	All others	596		0	0	0	DCV	NA: Not required per §120.1(d)3
<i>D7</i>	Alloulers	350	U		U	Occ Sensor	NA: Not required space type	
B8	All others	476		71.4	0	0	DCV	NA: Not required per §120.1(d)3
	Alloulers	470		71.4		0	Occ Sensor	NA: Not required space type
B9 204	Conference/ meeting	574		287	0	0	DCV	NA: Not required per §120.1(d)3
Conference	contentice/ meeting	3/4		207			Occ Sensor	NA: Not required space type
B17	Kitchen (cooking)	296		44.4	207.2	2500	DCV	NA: Not required per §120.1(d)3
B17	Kitchen (Cooking)	250		44.4	207.2	2500	Occ Sensor	NA: Not required space type
B18	All others	294		44.1	0	0	DCV	NA: Not required per §120.1(d)3
	All Others	254		44.1		•	Occ Sensor	NA: Not required space type
B23	Corridor	273		40.9	0	0	DCV	NA: Not required per §120.1(d)3
D23	Corridor	2/3		40.3			Occ Sensor	NA: Not required space type
17	Total System Required Min OA CFM			1061	18	Ventilation for thi	is System Complies?	Yes

Registration Number:

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance Schema Version: rev 20200601

Registration Date/Time: Report Version: 2019.1.003

Registration Provider: Energysoft Report Generated: 2022-03-04 09:13:03

Yes

STATE OF CALIFORNIA

**Mechanical Systems** CALIFORNIA ENERGY COMMISSION NRCC-MCH-E CERTIFICATE OF COMPLIANCE NRCC-MCH-E Brix Mercer Basement Remodel Report Page: (Page 24 of 34) 1221 Fulton Street Date Prepared: 3/4/2022

J. VENTILATION AND INDOOR AIR QUALITY <sup>2</sup> Air filtration requirements apply to the following three system types per §120.1(c)1A: space conditioning systems utilizing ducts to supply air to occupiable space; supply-only ventilation systems providing outside air to occupiable space; supply side of balanced ventilation systems including heat recovery and energy recovery ventilation systems providing

outside air to occupiable space. <sup>3</sup> Uniform Mechanical Code may have more stringent ventilation requirements; the most stringent code requirement takes precedence.

<sup>4</sup> See Standards Tables 120.1-A and 120.1-B.

<sup>5</sup> For lecture halls with fixed seating, the expected number of occupants shall be shall be determined in accordance with the California Building Code. <sup>6</sup> <u>§120.2(e)3</u> requires systems serving rooms that are required by <u>§130.1(c)</u> to have lighting occupancy sensing controls to also have occupancy sensing zone controls for ventilation. Examples of spaces which require lighting occupancy sensors include offices 250ft<sup>2</sup> or smaller, multipurpose rooms less than 1,000 ft<sup>2</sup>, classrooms, conference rooms, restrooms, aisles

and open areas in warehouses, library book stack aisles, corridors, stairwells, parking garages, and loading and unloading zones, unless excepted by §130.1(c).

K. TERMINAL BOX CO	ONTROLS										
This table is used to der	monstrate compliance with p	rescriptive	zone contro	l requireme	nts in <u>§140</u>	).4(d).					-
01	02	03	04	05	06	07	08	09	10	11	
			Design		De	adband Comp	liance	Reheated	Recooled, Mixed	Air Compliance	
Zone/System/VAV Box Name or Item Tag	Zonal Control Strategy per §140.4(d)	Peak Primary Airflow CFM	Primary Air in Deadband CFM	Reheated Recooled Mixed Airflow CFM	Outside Air CFM	20% (30% if no DDC) of Peak Primary Airflow CFM	Max Deadband Airflow CFM	50% of Peak Primary Airflow	1 <sup>st</sup> Stage Modulates <=95 °F and Maintains DB Rate?	I DR Flow to	Co
Z1 Mercer 202 - Meeting Room	NA: Peak SA <= 300 CFM	0	0	0	1873.2	0	1874.2	0	Yes	Yes	
Z2	NA: Peak SA <= 300 CFM	0	0	0	0	0	1	0	Yes	Yes	
70	NA D. 1 CA . 200 0714		1	_		<del></del>			<del> </del>	<del> </del>	-

 Z2
 NA: Peak SA <= 300 CFM</td>
 0
 0
 98.7
 0
 99.7
 0
 Yes
 Yes
 Yes

 Z4 Prep Food Handling
 NA: Peak SA <= 300 CFM</td>
 0
 0
 0
 200
 0
 201
 0
 Yes
 Yes
 Yes

 Z4 Storage
 NA: Peak SA <= 300 CFM</td>
 0
 0
 67.4
 0
 68.4
 0
 Yes
 Yes
 Yes

 Z4 Breakout Room
 NA: Peak SA <= 300 CFM</td>
 0
 0
 87.5
 0
 88.5
 0
 Yes
 Yes
 Yes

 Z4 Prep Food Handling NA: Peak SA <= 300 CFM 0 0 200 0 201 Z4 Lobby, Hall & NA: Peak SA <= 300 CFM 167 0 168 Storage

Registration Number:


CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Report Version: 2019.1.003 Schema Version: rev 20200601

Registration Date/Time: Registration Provider: Energysoft Report Generated: 2022-03-04 09:13:03

**APPROVED** 03/17/2023 COUNTY OF FRESNO **DEVELOPMENT SERVICES** 





CONSULTANT STAMP





FRESNO FIRE DEPARTMENT

REV.	DESCRIPTION	DATE

DATE: 11/15/2022 SCALE: As indicated JOB NUMBER:

ADDRESS:

BRIX & MERCER BLDGS 1221 FULTON ST FRESNO, CA 93721

AHJ #: 21-1137 21-105379 PROJECT:

FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT RENOVATION

SHEET TITLE:

TITLE 24 DOCUMENTS

SHEET NUMBER

M-12.3

on Provider: Energys d: 2022-03-04 09:13: ENERGY COMMISSI NRCC-MC (Page 32 of 3/4/2
:: 2022-03-04 09:13: :NERGY COMMISSI NRCC-MC
d: 2022-03-04 09:13:
d: 2022-03-04 09:13:
n Provider: Energys
Fail
ld Inspector
Additional Remark
3/4/
(Page 29 o
NRCC-M
ENERGY COMMIS
<u>A</u>

lections have been made based on information provided in previous tables of this document. If any select ese documents must be provided to the building inspector during construction and can be found online at tps://www.energy.ca.gov/title24/2019standards/2019_compliance_documents/Nonresidential_Documen		able E Additio	nal Remark
Form/Title	Systems/Spaces To Be Field	Field In	spector
	Verified	Pass	Fail
CA-MCH-13-A Automatic FDD for Air Handling Units and Zone Terminal Units Acceptance	*Daikin Vision - CAH012GDAM; **Daikin Vision - CAH008GDAC; ***Daikin Vision - CAH006GDAC; ****Daikin Vision - CAH008GDAC;		
CA-MCH-16-A Supply Air Temperature Reset Controls	Rotary Inverter - REYQ240AAYDA; Daikin - REYQ72XAYDA;		
CA-MCH-18-A Energy Management Control Systems	*Daikin Vision - CAH012GDAM; **Paikin Vision - CAH008GDAC; ***Paikin Vision - CAH006GDAC; ****Paikin Vision - CAH008GDAC; Rotary Inverter - REYQ240AAYDA; ROTARY Inverter - REYQ240AAYDA; Daikin - REYQ72XAYDA;		

Registration Number:	Registration Date/Time:	Registration Provider: Energysoft
CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance	Report Version: 2019.1.003 Schema Version: rev 20200601	Report Generated: 2022-03-04 09:13:03

	IPLIANCE						NRCC-MCH-
oject Name:			Brix Mercer Bas	sement Remodel Report Page	2:		(Page 28 of 34
oject Address:				21 Fulton Street Date Prepar			3/4/202
DISTRIBUTION	(DUSTINO)	V I DIDIVIO				The state of the s	
DISTRIBUTION	(DUCTWOR		1.				
4.5			In other unconditioned				
15					, which is constructed, insulated or sealed wit		
16		and diagnosti	c testing in accordance with	procedures in the Referer	cumented to have been previously sealed as conce Nonresidential Appendix NA2.	onfirmed thro	ugh field verification
17	Yes		hall be sealed in acordance	with the California Mecha	nical Code		na protesta de la composição de la composi La composição de la composição
ne answers to the	questions be	low apply to the	following duct systems:	ODU 3	Duct leakage testing triggered for these	systems?	No
11	No		the project includes only due				
12	No	Duct system p	provides conditioned air to a	n occupiable space for a c	onstant volume, single zone, space-conditioni	ng system.	
13	Yes		nditioning system serves less			***************************************	
			e combined surface area of the ducts in the following locations is more than 25% of the total surface area of the entire duct system:				
			Outdoors				
			In a space directly under	a roof that has a U-factor	greater than the u-factor of the ceiling, or if t	he roof does r	ot meet the
			requirements of §140.3(	a)1B or if the roof has fixe	ed vents or openings to the outside/ uncondit	ioned spaces	
			and an arrange and arrange arrange and arrange arrange arrange and arrange				
			In other unconditioned s	1			
The scope of the project includes extending an existing duct system, which is constructed, insulated or sealed with asbestos.							
16	The scope of the project includes an existing duct system that is documented to have been previously sealed as confirmed through field verificati and diagnostic testing in accordance with procedures in the Reference Nonresidential Appendix NA2.			ugh field verification			
17	Yes	Duct system sl	hall be sealed in acordance v	with the California Mechai	nical Code		
. COOLING TOW	/ERS						
is section does no	t apply to thi	s project.					

CERTIFICATE OF COMPLIANCE				NRCC-MCH-E	
Project Name:					
Project Address:	ess: 1221 Fulton Street Date Prepared:			3/4/2022	
These documents must be provided to	ERTIFICATES OF ACCEPTANCE  Information provided in previous tables of this document. If any selection needs to be to the building inspector during construction and can be found online at 019standards/2019_compliance_documents/Nonresidential_Documents/NRCA/	e changed, please explain why in	Table E Additio	nal Remarks.	
	Form/Title Systems/Spaces To Be Field			spector	
	Tottly fide	Verified	Pass	Fail	
NRCA-MCH-05-A - Air Economizer Col		*Daikin Vision - CAH012GDAM; **Daikin Vision - CAH008GDAC; ***Daikin Vision - CAH006GDAC; ****Daikin Vision - CAH008GDAC;			
NRCA-MCH-06-A Demand Control Ver controlled ventilation (refer to §120.1 dioxide (CO <sub>2</sub> ) concentration setpoints	ntilation Systems must be submitted for all systems required to employ demand L(c)3) can vary outside ventilation flow rates based on maintaining interior carbon is.	*Daikin Vision - CAH012GDAM; **Daikin Vision - CAH008GDAC; ***Daikin Vision - CAH006GDAC; ****Daikin Vision - CAH008GDAC;			
NRCA-MCH-07-A Supply Fan Variable		*Daikin Vision - CAH012GDAM; **Daikin Vision - CAH008GDAC; ***Daikin Vision - CAH006GDAC; ****Daikin Vision - CAH008GDAC;			
NRCA-MCH-11-A Automatic Demand	Shed Controls	*Daikin Vision - CAH012GDAM; **Daikin Vision - CAH008GDAC; ***Daikin Vision - CAH006GDAC; ****Daikin Vision - CAH008GDAC; Rotary Inverter - REYQ240AAYDA; Rotary Inverter - REYQ240AAYDA; Daikin - REYQ72XAYDA;			

Registration Date/Time:

Report Version: 2019.1.003

Schema Version: rev 20200601

STATE OF CALIFORNIA

Registration Number:

STATE OF CALIFORNIA

NRCC-MCH-E

Mechanical Systems

CERTIFICATE OF COMPLIANCE

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

NRCC-MCH-E


**Mechanical Systems** 

Project Na		Brix Mercer Basement Remodel	Report Page:	(Page 34 of 34		
Project A	ddress:	1221 Fulton Street	Date Prepared:	3/4/202		
DOCUM	ENTATION AUTHOR'S DECLARA	ATION STATEMENT		ter foreign of the second seco		
I certify	that this Certificate of Complia	ance documentation is accurate and comple	te.			
	tion Author Name:		Documentation Author Signature:	The term of the te		
Abel Lope	ez		Abel Lopez			
Company:			Signature Date:			
Lawrence	Engineering Group		22-03-04			
Address:		, , , , , , , , , , , , , , , , , , , ,	CEA/ HERS Certification Identification (if applicable):			
7084 N N	laple Avenue Suite 101					
City/State/7	•		Phone:			
Fresno C	A 93720		559-431-0101			
RESPON	SIBLE PERSON'S DECLARATION	STATEMENT				
certify the	following under penalty of perjury, under	the laws of the State of California:				
1.	The information provided on this Certificat	ded on this Certificate of Compliance is true and correct.				
2.	I am eligible under Division 3 of the Busine	of the Business and Professions Code to accept responsibility for the building design or system design identified on this Certificate of Compliance (responsible designer)				
3.	The energy features and performance sper of Title 24, Part 1 and Part 6 of the Californ	cifications, materials, components, and manufactured device: nia Code of Regulations.	s for the building design or system design identified on this Certificate of Compli	ance conform to the requirements		
4.	The building design features or system des plans and specifications submitted to the	system design features identified on this Certificate of Compliance are consistent with the information provided on other applicable compliance documents, worksheets, calculations, tted to the enforcement agency for approval with this building permit application.				
5.	I will ensure that a completed signed copy inspections. I understand that a completed	of this Certificate of Compliance shall be made available with	the building permit(s) issued for the building, and made available to the enforc e included with the documentation the buildor provides by the building owner a	ement agency for all applicable at occupancy.		
Responsible	Designer Name: D. Cantelmi		Responsible Designer Signature:			
Company:			Date Signed:			
Lawrence Engineering Group			2022-03-04			
Address:			License:			
-	th Maple Avenue Suite 101		M23588			
City/State/Z			Phone:			
Fresno CA	93720		5594310101			

Report Version: 2019.1.003

Schema Version: rev 20200601

-		A TO CO ZUPEZ		
Company Lawren	r: ce Engineering Group	Signature Date: 22-03-04		
Address:		CEA/ HERS Certification Identification (if applicable):		
7084 N	Maple Avenue Suite 101	TERS Certification identification (if applicable):		
City/State	e/Zip:	Phone:		
Fresno	CA 93720	559-431-0101		
RESPO	NSIBLE PERSON'S DECLARATION STATEMENT			
certify th	he following under penalty of perjury, under the laws of the State of California:			
1.	The information provided on this Certificate of Compliance is true and correct.			
<ol><li>I am eligible under Division 3 of the Business and Professions Code to accept responsibility for the b</li></ol>		ding design or system design identified on this Certificate of Compliance (responsible designer)		
3. The energy features and performance specifications, materials, components, and manufactured devices for the building design or system design identified on this Certificate of Compliance conform to the requi of Title 24, Part 1 and Part 6 of the California Code of Regulations.				
4.	The building design features or system design features identified on this Certificate of Compliance are plans and specifications submitted to the enforcement agency for approval with this building permit a	consistent with the information provided on other applicable compliance documents, worksheets, calculations,		
5.	I will ensure that a completed signed copy of this Certificate of Compliance shall be made available wi inspections. I understand that a completed signed copy of this Certificate of Compliance is required to	th the building permit(s) issued for the building, and made available to the enforcement agency for all applicable		
	ole Designer Name: l D. Cantelmi	Responsible Designer Signature:		
Company:		Date Signed:		
awrenc	ce Engineering Group	2022-03-04		
Address:		License:		
-	orth Maple Avenue Suite 101	M23588		
City/State, Fresno (		Phone:		
		5594310101		



STATE OF CALIFORNIA

CALIFORNIA ENERGY COMMISSION

Registration Provider: Energysoft

Report Generated: 2022-03-04 09:13:03

CALIFORNIA ENERGY COMMISSION

Report Generated: 2022-03-04 09:13:03

NRCC-MCH-E

Registration Number:

STATE OF CALIFORNIA

roject Name:

Registration Number:

**Mechanical Systems** 

CERTIFICATE OF COMPLIANCE


Mandatory Measures Note Block

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance

Q. MANDATORY MEASURES DOCUMENTATION LOCATION

Compliance with Mandatory Measures documented through MCH

CA Building Energy Efficiency Standards - 2019 Nonresidential Compliance



Registration Date/Time:

Brix Mercer Basement Remodel Report Page: 1221 Fulton Street Date Prepared:

This table is used to indicate where mandatory measures are documented in the plan set or construction documentation.

Report Version: 2019.1.003

Schema Version: rev 20200601

**APPROVED** 

03/17/2023 **COUNTY OF FRESNO** 

**DEVELOPMENT SERVICES** 

Registration Date/Time:

Report Version: 2019.1.003

Schema Version: rev 20200601



Registration Provider: Energysoft

Report Generated: 2022-03-04 09:13:03

Registration Provider: Energysoft

Report Generated: 2022-03-04 09:13:03

M-Sheets



FRESNO FIRE DEPARTMENT

11/15/2022

	REVISION TABLE	:	
CALIFORNIA ENERGY COMMISSION	REV.	DESCRIPTION	DATE
NRCC-MCH-E			
(Page 33 of 34)			
3/4/2022			
02			
UZ			

SCALE:	As indicated
JOB NUMBER:	
ADDRESS:	
BRIX & MERCER BLDGS	
1221 FULTON ST	

FRESNO, CA 93721 AHJ #: 21-1137 21-105379

PROJECT: FRESNO COUNTY DEPT. OF PUBLIC HEALTH BASEMENT

RENOVATION

SHEET TITLE:

TITLE 24 DOCUMENTS

SHEET NUMBER

