



County of Fresno

DEPARTMENT OF PUBLIC WORKS AND PLANNING
STEVEN E. WHITE, DIRECTOR

July 17, 2026

Contract No. 26-04-M

ADDENDUM NO. 1 to RMRA (SB-1) ASPHALT CONCRETE OVERLAYS, revising the Bidding and Contract Documents as follows:

SPECIAL PROVISIONS

ADD:

Replace Section 19-9.04 with:

The shoulder backing will be constructed as shown in the project details. Materials for shoulder backing shall be only the materials produced from the cold plane operation of this project. The portion that is identified as "Grade and Compact Native Soil (CNS) to 95% Relative Compaction for 1' minimum width" shall have a minimum thickness of 6 inches and it will be paid per cubic yard (CY) under Pay Item number 42.

PROPOSAL/BID BOOK: PAPER

DELETE: Bid Item List – Proposal 2

REPLACE with: Bid Item List – Proposal 2A

PROPOSAL/BID BOOK: BID EXPRESS

Bid Item List – Proposal 2 has been replaced with Bid Item List – Proposal 2A

END OF ADDENDUM NO. 1

Please attach this Addendum to the inside cover of the Specifications booklet. If you have given the Bidding and Contract Documents to someone else, please forward this Addendum.

7/17/2026

Date Signed



Supervising Engineer: _____

Neva Popenoe

Neva Popenoe, PE C73818

FRESNO COUNTY
Department of Public Works and Planning
m/a 2220 Tulare Street, Suite 720
Fresno, CA 93721-2106

Fresno County Department of Public Works and Planning

Bid Item List - Proposal 2A

Contract #

26-04-M

Contract Name

Road Maintenance And Rehabilitation Account (SB-1) Asphalt Concrete Overlays

Location

Various Locations in Fresno County

Base Items

Item ID	Quantity	Unit	Unit Price	Total
Description				
1	70,000	\$	\$1.00	\$70,000.00
SUPPLEMENTAL WORK (PAYMENT ADJUSTMENT FOR PRICE INDEX FLUCTUATIONS)				
2	50,000	\$	\$1.00	\$50,000.00
SUPPLEMENTAL WORK				
3	100,000	\$	\$1.00	\$100,000.00
SUPPLEMENTAL WORK (ROAD WORK PREPARATION)				
4	8	EA	\$	\$
CONSTRUCTION PROJECT FUNDING SIGNS				
5	1	LS	\$	\$
TRAFFIC CONTROL SYSTEM				
6	4	EA	\$	\$
PORTABLE CHANGEABLE MESSAGE SIGN				
7	1	LS	\$	\$
JOB SITE MANAGEMENT				
8	1	LS	\$	\$
PREPARE WATER POLLUTION PREVENTION PLAN IMPLEMENT & MAINTAIN				
9	243	CY	\$	\$
SHOULDER BACKING				

Item ID	Quantity	Unit	Unit Price	Total
10	1	LS	\$	\$
FINISHING ROADWAY				
11	15,954	TON	\$	\$
HOT MIX ASPHALT (TYPE A 3/4" GRADING)				
12	100	TON	\$	\$
MINOR HOT MIX ASPHALT				
13	40,755	SY	\$	\$
GEOSYNTHETIC PAVEMENT INTERLAYER (PAVING MAT)				
14	46	TON	\$	\$
GEOSYNTHETIC BINDER				
15	415	LF	\$	\$
PLACE HOT MIX ASPHALT DIKE (TYPE E) CASE-R				
16	15	TON	\$	\$
TACK COAT				
17	9	EA	\$	\$
TRAFFIC INDUCTIVE LOOPS (TYPE D & E)				
18	800	CY	\$	\$
REPLACE ASPHALT CONCRETE PAVEMENT				
19	415	LF	\$	\$
REMOVE ASPHALT CONCRETE DIKE				
20	87,118	SY	\$	\$
COLD PLANE ASPHALT CONCRETE PAVEMENT				
21	4	EA	\$	\$
SURVEY MONUMENTS (TYPE D)				

Item ID	Quantity	Unit	Unit Price	Total
22	415	SF	\$	\$
PAINT DIKE 2-COAT				
23	1	LS	\$	\$
REMOVE PAVEMENT MARKERS				
24	281	EA	\$	\$
PAVEMENT MARKER (RETROREFLECTIVE) (TYPE G)				
25	6,684	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 5)				
26	9,990	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 12)				
27	1,960	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 18)				
28	1,751	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 21)				
29	4,035	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 27B)				
30	945	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 38)				
31	860	LF	\$	\$
THERMOPLASTIC TRAFFIC STRIPE EXTRUDED (DETAIL 38A)				
32	410	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (LIMIT LINE)				
33	280	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (RAILROAD CROSSING)				

Item ID	Quantity	Unit	Unit Price	Total
34	252	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (SIGNAL AHEAD)				
35	265	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (STOP AHEAD)				
36	270	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (TYPE IV ARROW)				
37	28	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (TYPE I ARROW 10')				
38	50	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (TYPE I ARROW 18')				
39	42	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (TYPE VI ARROW MERGE')				
40	27	SF	\$	\$
THERMOPLASTIC PAVEMENT MARKING (TYPE VII ARROW RIGHT)				
41	1	LS	\$	\$
MOBILIZATION				
42	92	CY	\$	\$
SAFETY EDGE SUBGRADE				

Base Bid Items Total (Items 1 through 42):

\$

Additive 1 (CSA 35B - Redwing Lane)

Item ID	Quantity	Unit	Unit Price	Total
Description				
43	5,000	\$	\$1.00	\$10,000.00
SUPPLEMENTAL WORK (PAYMENT ADJUSTMENT FOR PRICE INDEX FLUCTUATIONS)				
44	10,000	\$	\$	\$
SUPPLEMENTAL WORK				
45	1	LS	\$	\$
TRAFFIC CONTROL SYSTEM				
46	1	LS	\$	\$
JOB SITE MANAGEMENT				
47	1	LS	\$	\$
CLEARING & GRUBBING				
48	1	LS	\$	\$
PREPARE WATER POLLUTION PREVENTION PLAN IMPLEMENT AND MAINTAIN				
49	50	CY	\$	\$
REPLACE ASPHALT CONCRETE				
50	1	LS	\$	\$
FINISHING ROADWAY				
51	557	TON	\$	\$
HOT MIX ASPHALT (TYPE A 3/4" GRADING)				
52	20	TON	\$	\$
MINOR HOT MIX ASPHALT				
53	2,852	LF	\$	\$
PLACE HOT MIX ASPHALT DIKE (TYPE E)				

Item ID	Quantity	Unit	Unit Price	Total
Description				
54	2	TON	\$	\$
TACK COAT				
55	650	LF	\$	\$
REMOVE ASPHALT CONCRETE DIKE				
56	2	EA	\$	\$
OVERSIDE DRAINAGE INLET				
57	1	LS	\$	\$
MOBILIZATION				

Additive Bid Items Total (Items 43 through 57):

\$

Total Bid (Base Bid Items + Additive Items) Items 1 through 57:

\$