



County of Fresno

DEPARTMENT OF PUBLIC WORKS AND PLANNING
STEVEN E. WHITE, DIRECTOR

April 26, 2021

Contract No. 20-17-C

ADDENDUM NO. 1 to American Avenue Disposal Site Entrance Improvements, revising the Plans as follows:

TABLE OF CONTENTS

No changes

NOTICE TO BIDDERS

No changes

SPECIAL PROVISIONS

26 AGGREGATE BASES

Add:

Add to section 26-1.03C:

Biaxial geogrid must comply with the requirements in Section 96-1.02P of the Standard Specifications

39 ASPHALT CONCRETE

39-3.02B Materials

Delete:

The grade of the asphalt binder must be PG 64-10 or PG 64-16

Replace with:

The grade of the asphalt binder must be PG 70-10

80 FENCES

Add to section 80-1.03:

Temporary chainlink fence shall be installed along the similar layout/perimeter of the proposed permanent fence and provide necessary room for Contractor to perform work. The temporary gate shall be located near the location of the proposed permanent gate. The temporary gate leaves shall be long enough to accommodate landfill haulers without interruption of the traffic and shall be lockable.

BID BOOK

PROPOSAL

Replace Proposal 2 with Proposal 2A attached.

AGREEMENT

No changes

PROJECT DETAILS

No changes

PLANS

No changes

END OF ADDENDUM NO. 1

Please attach this Addendum to the inside cover of the Specifications booklet. If you have given the Bidding and Contract Documents to someone else, please forward this Addendum.



4/26/2021

Date Signed

Supervising Engineer: _____

Sebastian Artal, PE C76724

FRESNO COUNTY
Department of Public Works and Planning
m/a 2220 Tulare Street, Suite 720
Fresno, CA 93721-2106

COUNTY OF FRESNO
DEPARTMENT OF PUBLIC WORKS AND PLANNING
PROJECT: AMERICAN AVENUE DISPOSAL SITE ENTRANCE IMPROVEMENTS

ITEM NO.	ESTIMATED QUANTITY	F	UNIT OF MEASURE	ITEM	ITEM PRICE (IN FIGURES)	TOTAL PRICE (IN FIGURES)
1	50000		\$	SUPPLEMENTAL WORK	\$1.00	\$50,000.00
2	20000		\$	SUPPLEMENTAL WORK (PAYMENT ADJUSTMENT FOR PRICE INDEX FLUCTUATIONS)	\$1.00	\$20,000.00
3	1		EA	CONSTRUCTION PROJECT INFORMATION SIGN		
4	1		LS	TRAFFIC CONTROL SYSTEM		
5	1		LS	JOB SITE MANAGEMENT		
6	1		LS	PREPARE STORM WATER POLLUTION PREVENTION PLAN		
7	1		LS	STORM WATER ANNUAL REPORT		
8	1200		\$	STATE WATER RESOURCES CONTROL BOARD NOTICE OF INTENT FILING FEE	\$1.00	\$1,200.00
9	20		LF	REMOVE CURB		
10	19		LF	REMOVE CONCRETE (VALLEY GUTTER)		
11	210		LF	REMOVE & DISPOSE 4" PVC WATER PIPELINE		
12	335		LF	REMOVE & DISPOSE 3" HDPE LEACHATE LINE		
13	200		LF	REMOVE & DISPOSE 3/4" PVC IRRIGATION PIPE		
14	410		LF	REMOVE & DISPOSE CHAINLINK FENCE		
15	5		EA	REMOVE CHAIN LINK FENCE LANDFILL SIGN STRUCTURE		
16	1		EA	REMOVE & DISPOSE GATE & MOTOR ASSEMBLY		
17	1		LS	CLEARING AND GRUBBING		
18	10		EA	REMOVE TREE		
19	3300	F	CY	ROADWAY EXCAVATION		
20	200	F	CY	BERM EXCAVATION		
21	30		CY	REMOVE & DISPOSE TEMPORARY PAVEMENT FOR PHASE II STAGING		
22	8		EA	BERM FOR ROADWAY DITCH		
23	15		CY	STRUCTURE BACKFILL (MINOR CONCRETE W/ REBAR)		
24	2700	F	CY	ROADWAY DITCH EXCAVATION		
25	1100	F	CY	LANDFILL DITCH EXCAVATION		
26	210	F	CY	EMBANKMENT CONSTRUCTION		
SUBTOTAL (BID ITEMS 1 THROUGH 26)						

Proposal 2.1-A
Contract No: 20-17-C

COUNTY OF FRESNO
DEPARTMENT OF PUBLIC WORKS AND PLANNING
PROJECT: AMERICAN AVENUE DISPOSAL SITE ENTRANCE IMPROVEMENTS

ITEM NO.	ESTIMATED QUANTITY	F	UNIT OF MEASURE	ITEM	ITEM PRICE (IN FIGURES)	TOTAL PRICE (IN FIGURES)
27	5990		SY	SUBGRADE ENHANCEMENT GEOGRID		
28	225		LF	INSTALL 4" PVC PIPE CLASS 315 WATER LINE		
29	6600		SF	HYDROSEED BLANKET		
30	1		LS	FINISHING ROADWAY		
31	2900	F	CY	CLASS 2 AGGREGATE BASE		
32	60		CY	REPLACE ASPHALT CONCRETE SURFACING		
33	2300		TON	HOT MIX ASPHALT (TYPE A 3/4" GRADING)		
34	240		SY	PLACE HOT MIX ASPHALT (MISCELLANEOUS AREAS)		
35	800		SY	COLD PLANE ASPHALT CONCRETE PAVEMENT		
36	2		CY	CONSTRUCT RETAINING WALL		
37	6		CY	REINFORCED GATE MOTOR CONCRETE PAD - MINOR CONCRETE		
38	3		CY	REINFORCED CULVERT OUTLET SPLASH PAD W/ CURB - MINOR CONCRETE		
39	222		LF	18" REINFORCED CONCRETE PIPE CLASS IV		
40	28		LF	INSTALL 12" STEEL PIPE		
41	35		LF	INSTALL 8" STEEL PIPE		
42	1		EA	INSTALL CONCRETE DRAIN INLET PER SHEET 4		
43	65		LF	REMOVE & DISPOSE 18" CORRUGATED METAL PIPE		
44	40		LF	REMOVE & DISPOSE 8" CORRUGATED METAL PIPE		
45	10		CY	SMALL-ROCK SLOPE PROTECTION (RIP RAP)		
46	17		LF	MINOR CONCRETE (CURB)		
47	19		LF	MINOR CONCRETE (VALLEY GUTTER)		
48	1		LS	TEMPORARY CHAIN LINK FENCE		
49	560		LF	CHAIN LINK FENCE (CL-6)		
50	1		EA	CHAIN LINK SLIDE GATE ASSEMBLY		
51	1		LS	CHAIN LINK MOTORIZED GATE ASSEMBLY		
52	5		EA	INSTALL CHAINLINK FENCE FOR SALVAGED SIGNS		
SUBTOTAL (BID ITEMS 27 THROUGH 52)						

Proposal 2.2-A
Contract No: 20-17-C

COUNTY OF FRESNO
DEPARTMENT OF PUBLIC WORKS AND PLANNING
PROJECT: AMERICAN AVENUE DISPOSAL SITE ENTRANCE IMPROVEMENTS

ITEM NO.	ESTIMATED QUANTITY	F	UNIT OF MEASURE	ITEM	ITEM PRICE (IN FIGURES)	TOTAL PRICE (IN FIGURES)
53	1		EA	ROADSIDE SIGN (R1-1) WITH HIGH VISIBILITY SLEEVE		
54	1		EA	ROADSIDE SIGN (MOD I-13)		
55	1		EA	ROADSIDE SIGN (R3-7)		
56	1		EA	ROADSIDE SIGN (MOD G20-3 CA)		
57	2		EA	INSTALL BOLLARD		
58	270		LF	THERMOPLASTIC TRAFFIC STRIPE (DETAIL 8)		
59	965		LF	THERMOPLASTIC TRAFFIC STRIPE (DETAIL 38A)		
60	3470		LF	THERMOPLASTIC TRAFFIC STRIPE (DETAIL 27B)		
61	480		LF	THERMOPLASTIC TRAFFIC STRIPE (DETAIL 21)		
62	395		SF	THERMOPLASTIC PAVEMENT MARKINGS WORDS		
63	100		SF	THERMOPLASTIC PAVEMENT MARKINGS ARROWS (A24A)		
64	10		LF	THERMOPLASTIC TRAFFIC STRIPE (DETAIL A24E)		
65	1		LS	ELECTRICAL AND CONTROL		
66	309	F	LF	INSTALL 8" HDPE SDR 11 SLEEVE (DIRECTIONAL BORING)		
67	335		LF	INSTALL 3" HDPE PIPE		
68	1		LS	MOBILIZATION		
SUBTOTAL (BID ITEMS 53 THROUGH 68)						

TOTAL BID (ITEMS 1 THROUGH 68)		
--------------------------------	--	--

F - FINAL PAY ITEM

Proposal 2.3-A
Contract No: 20-17-C